THE UNIVERSITY OF ALBERTA

EPR AND NMR STUDIES OF LIGAND COORDINATION AND

EXCHANGE FOR VANADYL COMPLEXES

by

Ⓒ

GERALD ALBERT MILLER

A THESIS

SUBMITTED TO THE FACULTY OF GRADUATE STUDIES AND RESEARCH

IN PARTIAL FULFILMENT OF THE REQUIREMENTS FOR THE DEGREE

OF

DOCTOR OF PHILOSOPHY

DEPARTMENT OF CHEMISTRY

EDMONTON, ALBERTA

FALL, 1973

ABSTRACT

Vanadyl dithiophosphinates and vanadyl perchlorates were investigated by EPR and NMR techniques to study the properties of the two different coordination sites of the vanadyl ion; namely, the four equivalent equatorial sites and the one axial site. The results are discussed within the context of previous studies.

Chapter III gives the results of an EPR study of the five coordinate vanadyl complexes, bis-(dimethyldithiophos-phinato)-oxo-vanadium(IV), bis-(diphenyldithiophosphinato-oxo-vanadium(IV), and bis-(O,O'-diethyldithiophosphato)-oxo-vanadium(IV) in the non-coordinating solvents toluene and CS_2. The EPR spectra correspond to the interaction of the un-paired electron with the ^{51}V nucleus and two equivalent ^{31}P nuclei. Addition of 1-5% by volume of the strongly coordin-ating ligands pyridine, dimethylformamide, or hexamethylphos-phoramide results in EPR spectra indicative of hyperfine interactions with the ^{51}V nucleus and a single ^{31}P nucleus. It is shown that, in this vanadyl species, the added ligand coordinates at an equatorial site, resulting in a five co-ordinate species in which one of the dithiophosphinate groups is monodentate and a six coordinate species in which one of the chelating dithiophosphinates is rearranged so that one sulfur atom occupies an equatorial position and the other the axial position. The equilibrium constants and heats of adduct formation for the equatorial ligand

ABSTRACT

Vanadyl dithiophosphinates and vanadyl perchlorates
were investigated by EPR and NMR techniques to study the
properties of the two different coordination sites of the
vanadyl ion: namely, the four equivalent equatorial sites
and the one axial site. The results are discussed within
the context of previous studies.

Chapter III gives the results of an EPR study of the
five coordinate vanadyl complexes, bis-(dimethyldithiophos-
phinato)-oxo-vanadium(IV), bis-(diphenyldithiophosphinato-
oxo-vanadium(IV), and bis-(O,O'-diethyldithiophosphonato)-oxo-
vanadium(IV) in the non-coordinating solvents toluene and
CS_2. The EPR spectra correspond to the interaction of the un-
paired electron with the ^{51}V nucleus and two equivalent ^{31}P
nuclei. Addition of 1-5% by volume of the strongly coordin-
ating ligands pyridine, dimethylformamide, or hexamethylphos-
phoramide results in EPR spectra indicative of hyperfine
interactions with the ^{51}V nucleus and a single ^{31}P nucleus.
It is shown that, in this vanadyl species, the added ligand
coordinates at an equatorial site, resulting in a five co-
ordinate species in which one of the dithiophosphinate
groups is monodentate and a six coordinate species in which
one of the chelating dithiophosphinates is rearranged so
that one sulfur atom occupies an equatorial position and
the other the axial position. The equilibrium constants
and heats of adduct formation for the equatorial ligand

addition were determined from the EPR spectra. At higher ligand concentrations, the EPR spectra show no ^{31}P hyperfine interactions which indicates that both chelating dithiophosphinate groups become monodentate. Infrared and conductivity measurements indicated that the vanadyl dithiophosphinate dissociates completely in solutions with still higher ligand concentrations, but that several vanadyl species containing one or two dithiophosphinate moieties coordinated to the vanadium atom are present in these solutions.

Chapter IV presents the results of NMR line broadening studies of solvent resonances in solutions of VO^{2+} in dimethylformamide (DMF) and dimethylacetamide (DMA). These results indicate that chemical exchange from axial and equatorial coordination sites can control the formyl proton relaxation in DMF, but axial exchange does not produce broadening of the methyl resonances in either DMF or DMA which could be distinguished from outer sphere broadening. The results also showed an inner-sphere broadening region which was attributed to relaxation by a dipole-dipole interaction for the formyl proton resonance in DMF and the C-methyl resonance in DMA and to hyperfine interactions for the N-methyl resonances. These assertions were substantiated by the values of the tumbling times of the complexes in solution which were determined from analyses of the EPR spectra of the complexes in the particular solvents. Similar studies of bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)

in DMF and DMA are also presented in Chapter IV and indicate that DMA completely displaces the dithiophosphinate chelate from the first coordination sphere of VO^{2+} but that in DMF at least one monodentate dithiophosphinate remains coordinated to the vanadyl ion.

ACKNOWLEDGEMENT

TABLE OF CONTENTS

LIST OF TABLES

LIST OF TABLES

LIST OF TABLES

CHAPTER I

INTRODUCTION

A. General Considerations

The chemistry of vanadium(IV) is dominated by the oxo-vanadium(IV) species, more commonly referred to as the vanadyl species. The vanadyl unit, VO^{2+}, remains intact in most environments used for chemical reactions and hence vanadyl coordination complexes with a large variety of ligands including multidentate ligands have been prepared. These vanadyl complexes which may be anions, cations or neutral complexes are often unstable in air. Surveys of the known vanadyl complexes have been compiled in review articles by Selbin.[1,2]

A special aspect of the vanadyl ion is its facility to form both five and six coordinate complexes. For example, in bis-(acetylacetonato)-oxo-vanadium(IV), [VO(acac)$_2$], the vanadium atom lies at approximately the center of gravity of the five oxygen atoms arranged in a rectangular pyramid.[3] The axial position, _trans_ to the vanadyl oxygen, is vacant in this complex but has been shown to readily accept a sixth ligand which has strong electron donor properties.[4-7] Adducts of VO(acac)$_2$ have also been isolated in which one oxygen atom of the one acetylacetonate chelate occupies the axial position and the second coordinating oxygen occupies an equatorial position (_cis_ to vanadyl

oxygen).[7,8] The remaining equatorial coordination site is
occupied by a Lewis base type ligand. Whether the Lewis
base occupies an axial or equatorial coordination site in the
$VO(acac)_2$ adduct is probably a function of its base strength
and its steric characteristics but no general correlations
have been proposed.

Differences in the coordination properties of the axial
and equatorial sites of the vanadyl ion should also be
reflected in the differences in ligand exchange rates from
the two types of sites. Since one expects Lewis base co-
ordination at the axial site, _trans_ to the vanadyl oxygen,
to be weaker than at the equatorial sites, the rate of
exchange from the axial site should be faster. In Chapter
IV the results of ligand exchange studies by the nuclear
magnetic resonance (NMR) solvent line broadening technique
show that this is indeed the case for the vanadyl ion in
the Lewis base solvents N,N-dimethylformamide and N,N-di-
methylacetamide.

The recent interest in sulphur chemistry has resulted
in the preparation of a variety of vanadyl complexes con-
taining the bidentate monothio-acetylacetonate[9], dithio-
carbamate[10,11], 1,2-dithiolene[12], or dithiophosphinate[13-
15] ligands. The results of a spectroscopic investigation
of three vanadyl dithiophosphinate complexes are presented
in this thesis. In particular, the complexes studied
were bis-(dimethyldithiophosphinato)-oxo-vanadium(IV)[13],

bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)[13,16] and

bis-(O,O'-diethyldithiophosphato)-oxo-vanadium(IV) [13,17,18]

and will be referred to individually as the methyl, phenyl

and ethoxy complexes respectively. An X-ray [19] crystal

structure of the methyl complex indicated that it is struct-

urally similar to VO(acac)$_2$ with the four sulphur atoms

forming the base of a rectangular pyramid and the coordin-

ation site <u>trans</u> to the vanadyl oxygen being vacant. (See

Fig. I-1). These complexes were conveniently studied by

electron paramagnetic resonance (EPR) spectroscopy. The

changes in the EPR spectra upon addition of Lewis bases to

solutions of the vanadyl complexes are sensitive to changes

in the coordination of the vanadyl ion. The results indi-

cate that several distinct species can be formed when a

Lewis base coordinates to a vanadyl dithiophosphinate com-

plex.

B.   EPR Spectra

EPR spectroscopy [20] is a useful technique for studying

the environment of the single unpaired electron in the

vanadyl systems. The application of a magnetic field re-

moves the spin state degeneracy and transitions between the

spin states can be induced by the introduction of energy

in the microwave region. The EPR spectrum is essentially

a recording of energy absorptions as a function of the

applied magnetic field strength. The spectrum of a vanadyl

FIGURE I-1 Structure of bis-(dimethyldithiophosphinato)-oxo-
vanadium(IV).[19]

complex in liquid solutions is characterized by an iso-
tropic g-value g_o, which is a measure of the magnitude of
the electronic Zeeman interaction, and a hyperfine splitting
constant a_o^V which describes the interaction between the
electron and ^{51}V nuclear magnetic moment. Since the ^{51}V
nucleus has a spin of 7/2, the EPR spectrum consists of
eight lines with the spacing approximately equal to a_o^V,
centered at magnetic flux $B = \hbar\omega_o/g_o\beta_o$ where $\hbar$ is Planck's
constant divided by 2π, ω_o is the spectrometer frequency
in sec^{-1} and β_o is the Bohr magneton.

The vanadium hyperfine splitting constant is pro-
portional to the unpaired electron spin density[20] at the
vanadium nucleus. In turn, one expects this unpaired
electron spin density to depend upon coordination at the
vacant site of a five coordinate complex. Coordination
of ligands to the vanadyl ion has been extensively studied,
[21-23] but the results give limited information because it
is difficult to assess the site of ligand coordination from
changes in a_o^V.

EPR results for the vanadyl dithiophosphinates are
much more enlightening because, in addition to the ^{51}V hyper-
fine splitting, the spectra show a second hyperfine splitt-
ing, a^P, due to the two equivalent ^{31}P nuclei of spin 1/2.
a^P depends on the amount of overlap of the phosphorus s-type
orbitals and the orbital of vanadium in which the unpaired
electron resides. On this basis, changes in a^P observed

6.

when a ligand coordinates to vanadyl dithiophosphinates can be directly related to the position of the phosphorus atoms relative to the orbital containing the unpaired electron.

The EPR spectra of solid solutions of vanadyl complexes indicate that the Zeeman interaction and the ^{51}V hyperfine interaction are both anisotropic, i.e. the magnitude of the g-value and the ^{51}V hyperfine splitting constant depend on the orientation of the vanadyl species relative to the applied magnetic field. These anisotropies contain information about the highest occupied and some of the lower unoccupied molecular orbitals of the complex.[24-27]

The anisotropic magnetic interactions are not completely averaged by the rotational motion of the complexes in liquid solutions, and produce variations in the linewidths of the hyperfine components of the EPR spectra.[28] An analysis of the solution EPR linewidths, combined with the anisotropic magnetic parameters determined from the spectra of the solid solutions, permits the calculation of the reorientational correlation time, τ_r, of the complex. This correlation time, which can qualitatively be viewed as the time required for the complex to reorient by 1 radian, controls the rate of numerous magnetic relaxation mechanisms and is intimately involved in the interpretation of the relaxation times of the nuclei on ligands attached to the paramagnetic vanadyl ions. These relaxation times are considered in detail in Chapter IV in connection with solvent NMR line broadening by vanadyl ions.

C.   Electronic Spectra

In general, the room temperature spectra of vanadyl complexes display three bands in the 7.5 to 30 kilokaeyser (kK) region which are designated Band I (11 - 16 kK), Band II (14.5 - 19 kK) and Band III (20 - 30 kK).[1,2] Band III is often concealed under an intense band attributed to a charge transfer transition. The three bands are assigned to the transitions from the non-bonding $d_{x^2-y^2}$ orbital to the anti-bonding levels on the basis of the following discussion.

Considerable controversy still surrounds the interpretation of the electronic spectra of vanadyl complexes. All bonding schemes proposed for vanadyl complexes agree that the unpaired electron resides in a molecular orbital which is essentially the non-bonding $3d_{x^2-y^2}$ atomic orbital of vanadium. However, the ordering of the antibonding levels to which the electron is promoted in the optical excitations is not firmly established. Early crystal field models [29] employing crystal fields of C_{4v} symmetry appropriate to $VO(H_2O)_5^{2+}$, suggested the order $d_{x^2-y^2} < d_{xz}, d_{yz} < d_{xy} < d_{z^2}$, but did not account for the known multiple bond character of the vanadyl unit.[30] Ballhausen and Gray [31] presented a molecular orbital treatment of $VO(H_2O)_5^{2+}$ in which the molecular orbitals were constructed from appropriate linear combinations of metal 3d, 4s and 4p orbitals, the 2s, $2p_z$, $2p_x$ and $2p_y$ orbitals of the vanadyl oxygen and

the sp_σ hybrid orbitals for the water oxygens. The result-ing bonding scheme, shown in Fig. I-2, assigns π bonding to the vanadyl unit and has served as a model for a host of vanadyl systems. The unpaired electron is localized mainly in the non-bonding $d_{x^2-y^2}$ orbital and the antibonding orbit-als have the same relative order as predicted by the crystal field model.

Vanquickenborne and McGlynn [32] performed extended-Hückel type molecular orbital calculations for $VO(H_2O)_5^{2+}$ and showed that the relative energies of the antibonding orbitals were particularily sensitive to the $\overset{O}{\overset{\|}{V}}$-O angle. A change of 15° caused shifts of 5-10 kK and could result in a crossover of the $d_{xy}(b_2)$ and the d_{xz}, $d_{yz}(e)$ levels. Since the $\overset{O}{\overset{\|}{V}}$-O angle is undoubtedly changed by the coordina-tion of a Lewis base at the axial position of a five co-ordinate complex, caution is necessary when comparing the electronic spectra of the same complex in different sol-vents [22,23] or different complexes in the same coordinating solvent.[10] Selbin [1,2] has also pointed out that equatorial bonding may invert the order of the $d_{xy}(b_2)$ and the d_{xz}, $d_{yz}(e)$ levels. This inverted order is supported by McCormick [10] from studies of the vanadyl dithiocarbamates.

Hitchman and Belford [27] have assigned the bands of cis-bis-(benzoylacetonato)-oxo-vanadium(IV). Their criteria for assignment was the scheme which gave the most reasonable values for the molecular orbital coefficients which were

9.

FIGURE I-2   Ballhausen and Gray molecular orbital

scheme [31] for $VO(H_2O)_5^{2+}$.

calculated from measured anisotropic EPR parameters and electronic transition energies. Their assignment required the relative energy ordering proposed by Ballhausen and Gray. This conclusion also agrees with the results of a low-temperature polarized single crystal spectrum of $VO(H_2O)_5^{2+}$.[33,34]

Ballhausen and Gray [31] have also pointed out that their assignment of electronic transitions agrees with an assignment based on the relative intensities of the observed bands. In C_{4v} symmetry, the electric dipole vector components transform as the A_1 and E representations and thus only transitions from the b_1 ground state to excited states of b_1 or e symmetries are allowed, i.e. the transition to the d_{xz}, d_{yz} (e) level is expected to be more intense than the other two transitions. The assignments proposed for the complexes studied in this work also agree with the expected intensity of the bands and show that the relative energies depend on the type of ligand coordinated to the VO^{2+} unit.

D.   Infrared Spectra

Infrared spectroscopy is another technique commonly applied in the study of vanadyl complexes. The infrared spectrum is characterized by a sharp intense band at approximately 1000 cm^{-1} which is attributed to the vanadium-oxygen stretch.[1,2] Since the multiple bond character of

the VO unit is believed to arise from electron donation from filled p_x and p_y orbitals of oxygen to empty d_{xz} and d_{yz} vanadium orbitals, coordination of a Lewis base in the axial position of a five coordinate complex should reduce the vanadium acceptor properties and lower the VO^{2+} stretching frequency. For example, addition of a pyridine molecule to $VO(acac)_2$ lowers the vanadyl V-O stretching frequency [35] from 996 to 964 cm^{-1}. The V-O stretching frequencies of a number of $VO(acac)_2$ adducts with substituted pyridines have been studied, and the observed shifts in the V-O stretch upon adduct formation fall into either of two ranges, namely 42 ± 4 cm^{-1} or 29 ± 4 cm^{-1}. [8,36] It has also been shown that the complexes producing the small shift had the substituted pyridine coordinated in the axial position, and that the large shift corresponded to complexes having the substituted pyridine coordinated at an equatorial site. [7,8]

Infrared spectroscopy is also useful for studying the nature of the ligands coordinated to the vanadyl unit. The P-S stretches in dithiophosphinates are sensitive to the type of coordination in which the dithiophosphinate is involved. [13] This coordination may be bidentate, monodentate or ionic. The characteristic feature of the infrared spectra of vanadyl complexes containing the amides N,N-dimethylformamide and N,N-dimethylacetamide as ligands is the carbonyl absorption in the region 1600-1700 cm^{-1}. The changes in the absorption frequencies observed upon

coordination to the vanadyl ion suggest that the amides coordinate <u>via</u> the carbonyl oxygen. [37,38]

E. Kinetic Studies

The host of experimental results already quoted and the theoretical descriptions of the bonding in vanadyl com-plexes definitely support the hypothesis that the chemical properties of the axial and equatorial coordination sites of vanadyl are quite different. It is well known that the axial vanadium-ligand bond is weaker than the equatorial bonds, since many six-coordinate vanadyl complexes release the ligand from the axial position when heated or dissolved in inert solvents.[5,39] One would expect therefore, that the rates of chemical exchange of the two types of coordinated ligands with uncoordinated ligands in solution would be rather different.

The effect of the coordination site on the exchange rate can be delineated by investigating complexes where all five of the ligands coordinated to the vanadyl ion are the same. The exchange of ligands from bulk solvent to the inner coordination spheres of two such complexes, penta-(N,N-dimethylformamido)-oxo-vanadium(IV) perchlorate (VO(DMF)$_5$(ClO$_4$)$_2$) and penta-(N,N-dimethylacetamido)-oxo-vanadium(IV) perchlorate (VO(DMA)$_5$(ClO$_4$)$_2$), have been studied and the results are discussed in detail in Chapter IV. When VO(DMF)$_5$(ClO$_4$)$_2$ is dissolved in DMF, an exchange

reaction may occur in which a coordinated DMF ligand is replaced by a DMF molecule from the bulk solvent. Such a reaction involves no net chemical change but can be studied by NMR because it has been well established that NMR lineshapes are influenced by dynamic processes such as an exchange of nuclei between nonequivalent magnetic sites.[40,41] The width of an NMR line depends on the transverse relaxation rate of the nuclei which in turn may be controlled by chemical exchange processes. Furthermore, the nuclear relaxation rate depends on its magnetic interactions with the paramagnetic species and the overall effect, as shown in mathematical detail in Chapter IV, is to broaden the NMR line of the bulk solvent.

In ^{17}O NMR studies of the solvent line broadening by vanadyl ions in ^{17}O-enriched water [42,43] the existence of two distinct types of coordinated water molecules was invoked in order to explain the observed line broadenings. The equatorially coordinated water molecules exchanged with those in the bulk solvent at a rate which could be determined from the line broadening data. The broadening due to the second type of coordinated water molecules indicated that their exchange rate was considerably faster than that for the equatorially coordinated water molecules. This second type of coordinated water could be either an axially coordinated molecule in the first coordination sphere, or

water molecules in outer solvation spheres, since both
would be expected to exhibit rapid exchange with the bulk
solvent. NMR studies of vanadyl perchlorate in other sol-
vents [44-46], and studies of vanadyl complexes in water [47]
have not resolved this ambiguity. In all cases, the rates
of the axial exchange process and second coordination
sphere exchange were too rapid to permit quantitative
study by the line broadening method.

EPR studies of vanadyl acetylacetonate and its amine
adducts in benzene solution [39] have shown that the rate of
elimination of an axially coordinated amine ligand is in
the range 10^6 - 10^8 sec^{-1} at room temperature. The rate
of exchange of equatorially coordinated water molecules
in vanadyl perchlorate solutions [42,43] is in the range
10^2 to 10^3 sec^{-1}, several orders of magnitude slower than
that observed for axial ligand elimination from the vanadyl
acetylacetonate adducts. The rate of this latter reaction
is too large to measure by NMR line broadening techniques,
but was obtained from the EPR measurements. [39]

The NMR line broadening of the formyl proton in
dimethylformamide (DMF) solutions of vanadyl perchlorate
has been reported by Angerman and Jordan. [44,45] They
obtained an activation energy of 7.25 kcal/mole for the
exchange of DMF molecules between the first coordination
sphere of the vanadyl ion and the bulk solvent. This
activation energy is considerably lower than the 13.7

kcal/mole found for the exchange of equatorial water ligands in aqueous solutions of vanadyl perchlorate [42,43], and similar values for other solvent ligands.[48] This observation indicated that further investigation of the vanadyl perchlorate - DMF system was warranted.

CHAPTER II

E X P E R I M E N T A L   T E C H N I Q U E S

A.   Purification of Solvents

The solvents toluene (Allied Chemical Reagent), car-
bon disulfide (Mallinckrodt Analytical Reagent), pyridine
(Raylo Reagent), hexamethylphosphoramide (Aldrich), N,N-
dimethylformamide (Baker Reagent), N,N-dimethylacetamide
(Fisher Certified) and N,N-diethylformamide (Eastman Organic
Chemicals) were all purified by double vacuum distillation
from phosphorus pentoxide or from molecular sieves (BDH
type 3A) and stored under vacuum over molecular sieves.
All solvents were subsequently transferred by distillation
under vacuum except for hexamethylphosphoramide (B.P. =
100°C at 6 torr) [49] which was transferred with a syringe
under a dry nitrogen atmosphere.

B.   Preparation and Characterization of Complexes
1.   Vanadyl Dithiophosphinates [13,14]

The vanadyl complexes bis-(dimethyldithiophosphinato)-
oxo-vanadium(IV), bis-(diphenyldithiophosphinato)-oxo-vanad-
ium(IV) and bis-(O,O'-diethyldithiophosphato)-oxo-vanadium-
(IV), to be referred to as the methyl, phenyl and ethoxy
complexes respectively, were prepared by adding the sodium
salt of the corresponding dithiophosphinic or dithiophosphoric
acid obtained from Dr. R. G. Cavell, University of Alberta,

to an aqueous solution saturated with vanadyl sulfate
(Fisher). The resulting blue paste was extracted with
chloroform. The vanadyl dithiophosphinate was left be-
hind when the chloroform was removed under vacuum. The
ethoxy complex was sensitive to air, but the phenyl and
methyl complexes were washed in air with ether and then
dried under vacuum. The methyl and phenyl complexes were
stored under nitrogen with no decomposition, whereas the
ethoxy complex showed black deposits within 15 minutes of
exposure to air.

The complexes were characterized by their EPR
spectra.[13] In addition the phenyl complex was subjected
to microanalysis.

Analysis:

$VO(S_2P\phi_2)_2$: Calc: C: 50.97 H: 3.56 S: 22.68

Found: C: 49.08 H: 3.72 S: 22.22

2.   Vanadyl Perchlorates

$VO(DMF)_5(ClO_4)_2$ was prepared by dissolving hydrated
vanadyl perchlorate [44,45] in DMF and distilling off the
water as a benzene-water azeotrope. Upon cooling the
solution to -10°C, blue crystals appeared which were col-
lected by filtration. Drying under vacuum removed the
excess solvent from the crystals. $VO(DMA)_5(ClO_4)_2$ was
prepared by the same method with DMF being replaced by
DMA. Characterization consisted of microanalysis.

Analysis:

VO(DMF)$_5$(ClO$_4$)$_2$: Calc: C: 29.59 H: 5.59 N: 11.08

Found: C: 28.48 H: 5.76 N: 10.93

VO(DMA)$_5$(ClO$_4$)$_2$ Calc: C: 34.25 H: 6.47 N: 9.98

Found: C: 33.50 H: 6.45 N: 9.86

3.   Bis-(o-phenanthroline)-oxo-vanadium(IV) perchlorate[50]

VO(C$_{12}$H$_8$N$_2$)$_2$(ClO$_4$)$_2$ was prepared by adding an acetone
solution of o-phenanthroline to an acetone solution of
VO(H$_2$O)$_5$(ClO$_4$)$_2$ which was acidified with dilute perchloric
acid. Within several minutes of stirring, a fine green
precipitate appeared. After cooling to -10°, the green
powder was filtered, washed with acetone, washed with ether
and dried under vacuum. The complex was characterized by
microanalytical results.

Analysis:
Calc: C: 46.03 H: 2.58 N: 8.95

Found: C: 45.87 H: 3.46 N: 8.33

4.   Other Complexes

Numerous attempts were made to prepare HMP and
pyridine adducts of the vanadyl dithiophosphinates in
crystalline form by adding an excess of ligand and then
removing this under vacuum. In all cases only an oil re-
sulted. However, when VO(acac)$_2$ was dissolved in HMP and

the excess HMP pumped off there remained a green powder which was shown to be VO(acac)$_2$·HMP.

Analysis:

Calc: C: 43.26 H: 7.26

Found: C: 43.01 H: 7.14

Thermogravimetric analysis showed the loss of one HMP group per VO(acac)$_2$·HMP at a temperature of 90°C.

C.   Sample Preparation

Solutions of the vanadyl dithiophosphinate complexes were prepared under vacuum by distilling a calibrated volume of solvent (CS$_2$ or toluene) into a vessel containing a weighed amount of the vanadyl complex. Required amounts of coordinating ligand were either distilled in (DMF and pyridine), or added with a syringe under dry N$_2$ atmosphere in a glove bag. The solution was then thoroughly degassed by several freeze-pump-thaw cycles and transferred under vacuum to an attached 1 cm quartz spectrophotometer cell for optical measurements and/or a 4 mm pyrex tube suitable for EPR measurements. For NMR studies, an NMR tube was attached to the vessel and 5% by volume of hexamethyldisilane or cyclopentane were distilled in to serve as internal references to facilitate chemical shift measurements. All EPR and NMR tubes were sealed and stored at liquid N$_2$ temperature until used.

The vessel was constructed such that after the EPR and NMR tubes had been sealed, the vessel could be placed into a modified cell compartment of the Cary 14 spectrophotometer. Samples of vanadyl perchlorates were prepared in an analogous manner.

Toluene solutions of the complexes containing pyridine consistently showed black deposits in the sample tube when prepared at room temperature. At lower temperatures, no decomposition was observed, but the EPR lines were so broad at these temperatures that the hyperfine splitting details of the spectra were not resolved. In order to study the pyridine-vanadyl dithiophosphinate complexes, CS_2 was used as a solvent. The much lower viscosity of CS_2 produced spectra showing well-resolved hyperfine structures over the temperature range -45°C to +45°C. The disadvantage of using CS_2 as a solvent is that the complexes do not remain in solution as the frozen state is approached and glass spectra could not be obtained.

Solutions for conductance and infrared measurements were prepared under bench conditions using only the most stable of the dithiophosphinate complexes, the phenyl complex. These solutions showed color changes after approximately a thirty minute exposure to air. Experiments quoted were completed within this time. Nujol mulls of the vanadyl perchlorates were prepared under dry N_2 in a glove bag and the spectra recorded immediately

after preparation.

D.   Instrumentation and Measurement Techniques

Electronic and near infrared spectra were recorded
on a Cary 14 spectrophotometer equipped with a vertically
extended cell compartment to accommodate sample vessel
and spectrophotometer cell. Infrared spectra were recorded
on both a Perkin-Elmer 457 using cesium iodide plates and
a Beckman IR-11 using 0.5 mm cesium bromide cells.

The EPR spectra were obtained with a Varian V-4502
EPR spectrometer equipped with an Alpha model 3093 Digital
NMR Gaussmeter for magnetic field calibration. Normal
precautions were taken to prevent lineshape distortion by
excessive 100 Kc field modulation. The g-values were measured
relative to Fremy's salt (g = 2.00550) [51] using a Varian
V-4532 dual cavity accessory or calculated from the ratio
of the magnetic field to the klystron frequency. Klystron
frequencies were measured using a Hewlett Packard model
X532B frequency meter. Both methods gave g-values which
were equal within the experimental error. The sample was
maintained at constant temperature ($\pm$1°C) with a Varian
V-4557 temperature controller and the temperature was
measured with a copper constantan thermocouple combined
with a Hewlett-Packard 3420A DC Differential Voltmeter.

Proton NMR spectra were recorded on Varian A60-D
and HA-100 NMR spectrometers equipped with variable

temperature accessories. Sample temperatures on the A60-D
were determined by comparison of the peak to peak separation
of methanol or ethylene glycol samples with calibration
charts published by Varian Associates.[52] Temperatures on
the HA-100 were determined with a copper constantan thermo-
couple. In both cases temperatures were accurate to $\pm1°C$.
Linewidths were measured on expanded sweeps and were re-
producible to ±1 Hz. The normal precautions were taken to
prevent signal saturation and ensure correct phasing. Chem-
ical shifts relative to the internal standards cyclopentane
or hexamethyldisilane were measured directly on a 500 Hz
sweep spectrum for the A60-D spectra whereas a Hewlett-
Packard model 5326C frequency counter was used to obtain
shifts on the HA-100. The accuracy of the shift measure-
ments were limited by the error involved in determining the
centers of the solvent resonance lines.

Conductance results were obtained by measuring the
resistance of a YSI 3400 series conductance cell from
Yellow Springs Instrument Co. with an Impedance Bridge Type
1650-A from the General Radio Company, Concord, Massachusetts.
Thermogravimetric analyses were carried out under vacuum
using the Dupont Model 950 Thermogravimetric Analyzer com-
bined with the Dupont 900 Differential Thermal Analyzer.

Chemical analysis for C, H, N and S were performed
by the microanalytical service at the University of Alberta,
Department of Chemistry.

CHAPTER III

STUDY OF THE COORDINATION OF LEWIS BASES TO VANADYL DITHIO-
PHOSPHINATES

A.   Introduction

The formation of six-coordinate vanadyl complexes from
five-coordinate complexes may be investigated by monitoring
the changes in the spectroscopic properties of the vanadyl
system caused by the addition of a Lewis base. The vanadyl
dithiophosphinates are suitable complexes for these studies
since the position trans to the vanadyl oxygen is vacant in
non-coordinating solvents and this position is expected to
accept a good electron donor group.

In vanadyl dithiophosphinates, the single unpaired
electron couples to the ^{51}V and the two ^{31}P nuclei and ex-
hibits a 24 line EPR spectrum in non-coordinating solvents.
(See Fig. III-1). Additions of small amounts of Lewis base
produce dramatic changes in the ^{31}P hyperfine structure of
the EPR spectra. The changes were found to be reversible
and to vary with temperature and ligand concentration. The
results could not be accommodated by the simple model pro-
posed in studies of adducts of vanadylacetylacetonate with
Lewis bases [39], in which the Lewis base coordinates to the
vacant trans position of the vanadyl complex. Instead,
changes in the arrangement of the chelating dithiophosphinate
groups about the vanadyl ion must occur if the measurements

of the dithiophosphinate complexes are to be explained.

The EPR studies of the dithiophosphinates and their reactions with Lewis bases in solution are described in this chapter. The magnetic parameters which characterize the various vanadyl species and the determination of these parameters from the EPR spectra are discussed in the context of the relevant theory of EPR in section III-B. The experimental measurements are described in section III-C, the results obtained from these measurements are given in section III-D and the interpretation of the results and their implications in the chemistry of vanadyl dithiophosphinates is given in section III-E.

The visible spectra of the vanadyl dithiophosphinates show changes when the coordination about the vanadyl ion is modified. In the following sections, the electronic spectra of the various vanadyl species are given, the major transitions assigned and the transition energies are used in conjugation with the measured magnetic parameters to gain some insight into the MO occupied by the unpaired electron.

B.   Theory

A general spin Hamiltonian for vanadyl dithiophosphinate complexes is

$$\hat{\mathcal{H}} = \beta_0 \hat{\vec{S}} \cdot \underline{g} \cdot \vec{B} + \hbar \hat{\vec{I}}_V \cdot \underline{A}^V \cdot \hat{\vec{S}} + \hbar \hat{\vec{I}}_{P1} \cdot \underline{A}^{P1} \cdot \hat{\vec{S}} + \hbar \hat{\vec{I}}_{P2} \cdot \underline{A}^{P2} \cdot \hat{\vec{S}} \ ,$$

$$(III-1)$$

where $\beta_\circ$ is the Bohr magneton, $\hat{\vec{S}}$ is the electron spin oper-
ator, $\underline{g}$ is the Zeeman interaction tensor, $\vec{B}$ is the flux of
the applied magnetic field and $\hbar$ is Planck's constant divided
by 2π. $\hat{\vec{I}}_V$, $\hat{\vec{I}}_{P1}$ and $\hat{\vec{I}}_{P2}$ are respectively the nuclear spin
operators for the ^{51}V nucleus (spin 7/2) and the two ^{31}P
nuclei (spin 1/2). $\underline{A}^V$, $\underline{A}^{P1}$ and $\underline{A}^{P2}$ are the nuclear-elect-
ronic hyperfine interaction tensors for the ^{51}V and the two
^{31}P nuclei respectively.

The observed EPR spectra of the vanadyl dithiophosphin-
ates in solid solutions indicate that both the Zeeman and
^{51}V hyperfine interactions have axial symmetry and that the
^{31}P hyperfine interactions are isotropic. It is then con-
venient to expand the tensor interactions into individual
terms and write the spin Hamiltonian as

$$\hat{\mathcal{H}} = \beta_\circ g_{||} B\cos\theta \hat{S}_z - \beta_\circ g_\perp B\sin\theta \hat{S}_x + \hbar A_{||}^V \hat{I}_{Vz}\hat{S}_z + \hbar A_\perp^V (\hat{I}_{Vx}\hat{S}_x +$$

$$\hat{I}_{Vy}\hat{S}_y) + \hbar A^{P1}(\hat{\vec{I}}_{P1}\cdot\hat{\vec{S}}) + \hbar A^{P2}(\hat{\vec{I}}_{P2}\cdot\hat{\vec{S}}) \quad , \qquad \text{(III-2)}$$

where θ is the angle between the molecular symmetry axis
and the laboratory z-axis, $g_{||}$ and $g_\perp$ are the g-values par-
allel to and perpendicular to the symmetry axis respectively,
and $A_{||}^V$ and $A_\perp^V$ are the ^{51}V parallel and perpendicular hyper-
fine splitting constants (in $\sec^{-1}$). A^{P1} and A^{P2} are the
isotropic hyperfine splitting constants for the two ^{31}P
nuclei (in $\sec^{-1}$). The solution of the Schrödinger equation

for the spin system represented by the Hamiltonian (III-2) in an appropriate set of basis functions, gives the allowed energy levels of the spin system. The electron spin transition probabilities between the states can be calculated by using time dependent perturbation theory [41] to describe the effects of the oscillating microwave field which is applied in a direction perpendicular to the static field B in an EPR experiment. The result is an EPR spectrum described by the resonance condition [28,53,54]

$$\omega_o = \frac{g\beta_o B}{\hbar} + A^V M_V + \frac{\hbar A_{\perp}^{V^2}(A_{||}^{V^2} + A^{V^2})}{4g\beta_o B \quad A^{V^2}} \cdot [I(I + 1) - M_V^2]$$

$$+ A^{P1} M_{P1} + A^{P2} M_{P2} \quad , \qquad\qquad\qquad (III-3)$$

where $\qquad g^2 = g_{\perp}^2 \sin^2\theta + g_{||}^2 \cos^2\theta \quad , \qquad\qquad (III-4)$

and $\qquad g^2 A^{V^2} = g_{\perp}^2 A_{\perp}^{V^2} \sin^2\theta + g_{||}^2 A_{||}^{V^2} \cos^2\theta \quad . \qquad (III-5)$

In equation (III-3), ω_o is the spectrometer operating frequency in $\sec^{-1}$, B is the applied magnetic flux in Gauss, M_V is the vanadium nuclear spin quantum number, I has the value 7/2 and M_{P1} and M_{P2} are the phosphorus nuclear spin quantum numbers. The [51]V hyperfine interaction is considered to second order [55] while the [31]P hyperfine interactions appear

only to first order since the corresponding second order con-
tributions are very small.

Since the ^{31}P interactions are isotropic, the aniso-
tropic information is all described by the first three terms
of equation (III-3). It is therefore convenient to consider
the field positions B_{M_V} at the centres of each of the ^{31}P
superhyperfine multiplets. The spectrum arising from
molecules whose molecular axes are parallel to the applied
magnetic field is described by the resonance condition

$$\omega_o = \frac{g_{||}\beta_o B_{M_V}}{\hbar} + A_{||}^V M_V + \frac{\hbar}{g_{||}\beta_o B_{M_V}} \cdot \frac{A_{\perp}^{V^2}}{2} \cdot [I(I + 1) - M_V^2],$$

$$(III-6)$$

which is obtained from equation (III-3) with $\theta = 0$. Setting
$\theta = \pi/2$, one obtains the resonance condition for the per-
pendicular spectrum

$$\omega_o = \frac{g_{\perp}\beta_o B_{M_V}}{\hbar} + A_{\perp}^V M_V + \frac{\hbar}{g_{\perp}\beta_o B_{M_V}} \cdot \frac{A_{\perp}^{V^2} + A_{||}^{V^2}}{4} \cdot [I(I + 1) - M_V^2].$$

$$(III-7)$$

Usually, the values of the magnetic field, B_{M_V}, for a
resonance of given M_V value can be measured experimentally.
The hyperfine constant for the parallel lines in the spectrum
is expressed to a good approximation by

$$\frac{\hbar A_{||}^{V}}{g_{||}\beta_{o}} = a_{||}^{V} = \frac{1}{2}(B_{M_{V}} - B_{M_{V}-1} + B_{-M_{V}+1} - B_{-M_{V}}) \qquad \text{(III-8)}$$

where $A_{||}^{V}$ is the hyperfine splitting in $\sec^{-1}$ and $a_{||}^{V}$ is the splitting in units of Gauss. Units of Gauss are usually used when comparing splitting constants of various systems while units of $\sec^{-1}$ are convenient in expressions describing relaxation interactions as will be shown in Chapter IV. An expression similar to equation (III-8) can be given for $A_{\perp}^{V}$ and $a_{\perp}^{V}$ which characterize the resonance lines in the perpendicular spectrum. Since the vanadium hyperfine splitting constant is negative [56], the lowest field multiplet corresponds to $M_{V} = -7/2$.

The g-values are determined from spectra recorded using a dual sample cavity, in which the sample of interest experiences the same magnetic flux and microwave frequency as a reference sample. The magnetic field at resonance for the standard, B_{s}, is different from that of the sample, $B_{M_{V}}$, if the standard g-value, g_{s}, is different from the sample g-value. The resonance condition for the sample is given by equation (III-3) and that for the reference by

$$\omega_{o} = g_{s}\frac{\beta_{o}}{\hbar}B_{s} \ . \qquad \text{(III-9)}$$

Combining equation (III-9) with (III-6) and (III-7), one

obtains the following expressions for the anisotropic g-
values.

$$g_{||} = g_s B_s / (B_{M_V} + a_{||}^V M_V) - \frac{g_\perp^2 a_\perp^{V2}}{2 g_{||} B_{M_V}} \cdot \frac{[I(I + 1) - M_V^2]}{(B_{M_V} + a_{||}^V M_V)} \cdot$$

(III-10)

$$g_\perp = g_s B_s / (B_{M_V} + a_\perp^V M_V) - \frac{g_{||}^2 a_{||}^{V2} + g_\perp^2 a_\perp^{V2}}{4 g_\perp B_{M_V}} \cdot \frac{[I(I + 1) - M_V^2]}{(B_{M_V} + a_\perp^V M_V)} \cdot$$

(III-11)

In equation (III-10) the field values B_{M_V} correspond to the
parallel spectrum and in equation (III-11) they refer to the
perpendicular spectrum. After determining $a_{||}^V$ and $a_\perp^V$ from
equation (III-8), the anisotropic g-values are calculated
by an iterative procedure using equations (III-10) and
(III-11).

In liquid solutions, rapid molecular reorientations
average out the anisotropic Zeeman and hyperfine interactions
and the effective spin Hamiltonian is

$$\hat{\mathcal{H}} = \beta_o g_o \hat{\vec{S}} \cdot \vec{B} + \hbar A_o^V \hat{\vec{I}}_V \cdot \hat{\vec{S}} + \hbar A^{P1} \hat{\vec{I}}_{P1} \cdot \hat{\vec{S}} + \hbar A^{P2} \hat{\vec{I}}_{P2} \cdot \hat{\vec{S}} \qquad \text{(III-12)}$$

where g_o is the isotropic g-value and A_o^V is the [51]V isotropic
hyperfine splitting constant. Again the solution of the
Schrödinger equation in an appropriate basis set yields the

energy levels of the spin system and the allowed spin transi-
tions are determined by considering the oscillating micro-
wave field as a time dependent perturbation. The results
show that the EPR spectrum in solution is described by the
resonance condition [28]

$$\omega_o = \frac{g_o \beta_o B}{\hbar} + A_o^V M_V + \frac{A_o^{V^2} \hbar}{2} \cdot \frac{[I(I+1) - M_V^2]}{g_o \beta_o B} + A^{P1} M_{P1}$$

$$+ A^{P2} M_{P2} \quad . \tag{III-13}$$

Since the ^{31}P interactions are adequately described by a
first order interaction, the separation between the reson-
ance lines arising from molecules with different ^{31}P nuclear
spin quantum numbers, but the same value of M_V, will be
equal. These separations in Gauss give the values of a^{P1}
and a^{P2}, the ^{31}P hyperfine splitting constants in units of
Gauss. The values can be converted to units of $\sec^{-1}$ by
multiplication by the factor $g_o \beta_o / \hbar$. As in the analysis of
the anisotropic spectra, it is convenient to consider the
field positions B_{M_V} at the centres of the ^{31}P superhyper-
fine multiplets in order to determine g_o and A_o^V from spectra
recorded with a dual-sample cavity. By considering the
resonance conditions at B_{M_V} and B_{-M_V}, one derives the result

$$\frac{\hbar A_o^V}{g_o \beta_o} = a_o^V = -(B_{M_V} - B_{-M_V})/M_V , \tag{III-14}$$

where a_o^V is the ^{51}V hyperfine splitting in units of Gauss.
Combining equation (III-13) with equation (III-9), one
obtains the following expression for g_o.

$$g_o = g_s + g_s \left\{ \frac{2B_s - (B_{M_V} - B_{-M_V})}{B_{M_V} + B_{-M_V}} \right\} - \frac{2A_o^V{}^2 \hbar^2}{g_s \beta_o{}^2} \frac{[I(I+1) - M_V{}^2]}{\left(B_{M_V} + B_{-M_V}\right)^2} .$$

$$(III-15)$$

A_o^V and g_o are calculated by an iterative procedure using
equations (III-14) and (III-15) for each pair of M_V and $-M_V$
resonance lines. The average of the four results is the
value reported. The isotropic ^{51}V hyperfine splitting which
is determined from the spectrum in liquid solution is re-
lated to the anisotropic splittings determined from the glass
spectrum by

$$A_o^V = (A_{||}^V + 2A_{\perp}^V)/3 . \qquad (III-16)$$

Similarily the isotropic and anisotropic g-values are related
by

$$g_o = (g_{||} + 2g_{\perp})/3 . \qquad (III-17)$$

Another feature of EPR spectra of vanadyl complexes
in liquid solutions is the variation of linewidths with the
vanadium nuclear spin quantum number M_V. The general line-
width theory developed by Kivelson and coworkers [28,57] indi-
cates that electron spin relaxation in dilute (10^{-3} M) oxygen
free solutions is caused primarily by the modulation of the

anisotropic Zeeman and [51]V hyperfine interactions by the
rotational motion of the molecules [28] and by collisional
modulation of spin-rotational interactions.[57] Incomplete
averaging of the anisotropic interactions results in lines
whose widths vary with M_V. The peak-to-peak derivative
linewidths of the hyperfine lines, ΔB_{M_V}, can be fitted to the
equation

$$\Delta B_{M_V} = \alpha + \beta M_V + \gamma M_V^2 + \delta M_V^3 \quad , \qquad \text{(III-18)}$$

using a least squares procedure to determine α, β, γ, and δ.
These linewidth parameters are functions of the anisotropic
magnetic parameters and the rotational tumbling time τ_r.[28]
The transverse relaxation time for the electron T_{2e} is
related to the peak-to-peak width ΔB by

$$\frac{1}{T_{2e}} = \frac{\sqrt{3}}{2} g_0 \frac{\beta_0}{\hbar} \Delta B \quad . \qquad \text{(III-19)}$$

τ_r may be calculated from the α, β, γ or δ values combined
with the measured anisotropic parameters. An expression for
τ_r is also given by the Debye theory of rotational relaxation[58]
as

$$\tau_r = \frac{4\pi \eta r^3}{3kT} \qquad \text{(III-20)}$$

where η is the coefficient of viscosity, r is the hydrodyn-
amic radius of the molecule, k is the Boltzman constant and
T is the absolute temperature. Equation (III-20) indicates
that the linewidth depends on the molecular dimensions of

the vanadyl complex.

The basic relationships given above will be used in subsequent sections to analyze the experimental EPR spectra of the vanadyl dithiophosphinates, and in Chapter IV to analyze the spectra of the vanadyl perchlorates.

C.   Experimental Measurements

The majority of the experimental work involved the recording of the EPR spectra of the vanadyl dithiophosphin-ates in solid and liquid solutions. All solutions were prepared as described in Chapter 2.   First, the EPR spectra of the complexes in the non-coordinating solvents toluene and CS_2 at several temperatures were recorded in order to characterize the five coordinate complexes on the basis of their magnetic parameters. Next were recorded at several temperatures the EPR spectra of the vanadyl dithiophosphin-ate complexes in toluene which contained a small amount (5% by volume) of HMP and DMF. Since the spectra in small amounts of pyridine in toluene at room temperature indicated decomposition of the vanadyl complexes, the complexes were investigated in pyridine-CS_2 mixtures in the liquid range of CS_2 (-45°C to 45°C). Under these conditions, no indica-tion of decomposition was observed. The cases of the methyl and phenyl complexes in pyridine/CS_2 were also studied at constant temperature as a function of pyridine

concentration (0.1% - 5.0% by volume). The complicated spectra in the mixed solvents were analyzed with the support of computer synthesized spectra. Finally, the EPR spectra of the complexes in the pure Lewis bases HMP, DMF and Pyridine were recorded. Portions of the solutions prepared for the EPR samples were simultaneously transferred to a spectrophotometer cell for the recording of the electronic spectra. Additional solutions were prepared if larger complex concentrations were required to give adequate electronic absorption spectra.

The results of the EPR investigation were complemented by infrared studies. Infrared spectral investigations were limited to the pyridine-CS_2 solvent system which is relatively free of absorptions in the regions of interest. The vanadyl V-O stretching frequencies for the phenyl and methyl complexes in CS_2 and 5% pyridine/CS_2 were recorded. In addition, the symmetric P-S stretching frequency of the phenyl complex in CS_2 was recorded as a function of added pyridine. This P-S stretch is sensitive to the type of coordination of the dithiophosphinate group.

Solutions of the complexes in mixed solvents and pure Lewis bases were tested for the presence of ionic species by conductance measurements at room temperature.

D.   Results

1.   Analysis of EPR Spectra in Toluene and CS_2

        Changes in the coordination in vanadyl complexes generally affect the magnitudes of the magnetic parameters which are manifest in the EPR spectra. To isolate the changes that occur when a Lewis base coordinates to the five coordinate vanadyl dithiophosphinates, it is necessary to characterize the free complexes by their magnetic parameters in non-coordinating solvents such as toluene and CS_2.

        The EPR spectra of 10^{-3} $\underline{M}$ solutions of the three vanadyl complexes in toluene at 30°C are shown in Fig. III-1 and are similar to those reported previously by other workers.[14,16-18] These liquid solution spectra consist of eight lines due to the interaction of the unpaired electron with the ^{51}V nuclear spin ($I = 7/2$); each of these eight lines is further split into a 1:2:1 triplet of lines by the interaction of the electron with two equivalent ^{31}P nuclei ($I = 1/2$). Some of the 24 possible lines are not resolved in the spectra of the ethoxy complex because the phosphorus hyperfine splitting is approximately half as large as the vanadium splitting so that there is considerable overlapping of lines. The spectra in CS_2 are similar to those in toluene, but the lines were narrower because the CS_2 solutions are less viscous.

        The isotropic magnetic parameters are readily determined from the spectra in Fig. III-1 using the methods

FIGURE III-1   EPR spectra of 10^{-3} $\underline{M}$ liquid
solutions of the vanadyl dithiophosphinate
complexes in toluene at 30°C.

(a) bis-(dimethyldithiophosphinato)-oxo-
    vanadium(IV);

(b) bis-(diphenyldithiophosphinato)-oxo-
    vanadium(IV);

(c) bis-(O,O'-diethyldithiophosphato)-oxo-
    vanadium(IV).

The experimental spectra are shown above
the computer simulations in each case.

described in the previous section. The phosphorus hyper-
fine splitting a^P (Gauss) is simply the spacing between the
components of the triplet. a_o^V and g_o are calculated from
spectra recorded using a dual-cavity by an iterative pro-
cedure using equations (III-14) and (III-15). The values
of the isotropic magnetic parameters for the toluene and
CS_2 solutions of the three complexes are given in Table
III-1. The magnitudes of the variations in these para-
meters with temperature is similar to that observed for
$VO(acac)_2$ [28] and indicates that the molecular structure
does not change with temperature.

The relative widths of the various lines in the
spectrum were estimated from the peak-to-peak intensities
of the lines. Measurement of the width of one of the
lines which is relatively free of overlap on an expanded
field sweep gave an absolute width from which estimates
of the absolute widths of the various hyperfine lines were
obtained. This procedure assumes the lineshapes are
Lorentzian, in which case the product of the height and
the square of the width is a constant. This method is
inaccurate at low temperatures where the intensities are
affected by overlapping of adjacent lines and for spectra
of the ethoxy complex where overlapping of lines is severe.

Since the overlapping of lines in the spectra of
the ethoxy complex and the variation of the linewidth of
the hyperfine components introduces significant error in
the calculation of a_o^V and a^P, the observed spectra were

TABLE III-1

Isotropic Magnetic Parameters[†] for Vanadyl Dithiophosphinates in CS_2 and Toluene Solutions

Substituent of Dithiophos- phinate	CS_2 at $-30°$			CS_2 at $30°$			Toluene at $30°$			Toluene at $116°$		
	g_o	a_o^V	a^P	g_o	a_o^V	a^P	g_o	a_o^V	a^P	g_o	a_o^V	a^P
Methyl	1.9777	94.8	34.0	1.9766	95.4	33.4	1.9773	94.8	32.8	1.9728	95.7	32.4
Phenyl	1.9787	95.0	34.2	1.9781	95.5	33.3	1.9784	95.5	33.0	1.9765	95.9	32.6
Ethoxy	1.9819	94.8	50.7	1.9811	95.2	50.2	1.9814	95.0	49.7	1.9798	95.6	49.2

[†]
Hyperfine splittings are in Gauss. Estimated errors are $\pm$ .3 Gauss for hyperfine splittings and $\pm$ .0003 for g-values.

compared with those synthesized by a digital computer. The computer program (see Appendix C) sets up a stick spectrum from input hyperfine splitting constants and assigns to each line a Lorentzian lineshape with a width characterized by an input parameter. Adjustments are made in the hyperfine splitting constants and linewidths on successive simulations until the agreement between the observed and calculated spectra is satisfactory. The calculated spectra which agree best with the observed ones are shown below the experimental spectra in Fig. III-1. The excellent fit for the spectrum of the ethoxy complex shows that this method allows the determination of splitting constants and linewidths under conditions of significant overlap. For cases where there is a minimum of overlap, the hyperfine splitting constants determined from the computer synthesized spectra agree with the values determined by direct calculation. The line-widths determined from the computer synthesized spectra are given for the three complexes in Table III-2. The much smaller linewidths of the methyl complex can be attributed to its small molecular radius compared to the radii of the phenyl and ethoxy complexes. The linewidth decrease with increasing temperature results from the decrease in solvent viscosity and the consequently smaller τ_r values at higher temperatures.

The EPR spectrum of the phenyl complex in toluene at -150°C is shown in Fig. III-2a. a^p is measured directly

TABLE III-2

EPR Linewidths in Gauss of Hyperfine Components of Vanadyl Di-thiophosphinates at Various Temperatures in Toluene and CS_2.

Methyl Complex in Toluene

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
0	7.50	6.29	5.78	5.80	6.41	7.47	9.19	11.3
30	6.03	5.36	5.18	5.20	5.57	6.25	7.17	8.40
60	5.08	4.69	4.61	4.67	4.96	5.41	6.04	6.76
90	5.14	4.83	4.77	4.82	5.06	5.37	5.88	6.45
116	5.40	5.09	5.09	5.14	5.29	5.54	5.87	6.28

Methyl Complex in CS_2

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
-45	7.65	6.42	5.87	5.87	6.45	7.51	9.10	11.2
-30	6.80	5.88	5.47	5.54	5.99	6.88	8.15	9.59
-15	6.29	5.53	5.26	5.33	5.69	6.45	7.51	8.80
0	5.78	5.19	4.94	5.00	5.33	5.98	6.86	7.84
15	5.42	4.96	4.80	4.86	5.15	5.69	6.39	7.33
30	5.11	4.82	4.69	4.82	5.11	5.58	6.23	7.09
45	4.71	4.45	4.41	4.54	4.78	5.20	5.93	6.69

TABLE III-2 (continued)

Phenyl Complex in Toluene

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
0	21.2	15.4	12.6	12.1	14.0	18.0	24.2	32.6
30	13.7	10.4	8.82	8.68	9.91	12.6	16.3	21.1
60	10.1	7.87	7.02	7.04	8.04	10.0	12.3	15.2
90	8.22	6.79	6.17	6.25	6.97	8.40	10.4	13.1
116	6.96	5.97	5.58	5.65	6.25	7.28	8.81	10.5

Phenyl Complex in CS_2

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
-30	19.5	13.6	11.0	10.7	12.3	16.4	23.4	32.9
-15	15.7	11.5	9.52	9.29	10.7	13.7	18.7	26.3
0	13.2	10.0	8.43	8.28	9.42	11.9	15.8	21.7
15	11.5	8.89	7.65	7.60	8.57	10.7	13.9	18.4
30	10.1	7.99	7.00	6.98	7.85	9.58	12.3	15.9
45	9.20	7.41	6.65	6.68	7.48	9.06	11.4	14.4

Ethoxy Complex in Toluene

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
0	17.5	14.3	12.5	12.1	12.9	15.0	18.1	22.3
30	13.8	11.9	10.7	10.6	11.1	12.5	14.5	17.3

TABLE III-2 (continued)

Ethoxy Complex in Toluene (continued)

Temp °C	-7/2	-5/2	-3/2	-1/2	1/2	3/2	5/2	7/2
60	10.7	9.64	9.06	9.01	9.40	10.3	11.6	13.3
75	10.2	9.25	8.74	8.67	9.05	9.83	11.0	12.5
90	9.02	8.29	7.93	7.89	8.19	8.87	9.82	11.0
105	8.42	7.77	7.46	7.46	7.75	8.34	9.19	10.3

44.

FIGURE III-2. EPR spectra of 10^{-3} $\underline{M}$ solid solutions
of bis-(diphenyldithiophosphinato)-
oxo-vanadium(IV) at -150°C in (a) tolu-
ene and (b) 5% HMP/toluene.

as the spacing of the components of the triplet of the parallel spectrum. The value is equal to that found in the liquid spectrum. Some of the previous EPR work [18] indicated that the ^{31}P hyperfine interaction was anisotropic, but the observed isotropic phosphorus splittings do not agree well with those predicted from the anisotropic splittings. Since there is considerable overlapping of lines in the perpendicular part of the solid solution spectrum, only $g_{||}$ and $A_{||}^{V}$ are determined directly from the spectra. Values for $g_{\perp}$ and $A_{\perp}^{V}$ were computed from the isotropic parameters using equation (III-16) and (III-17). The magnetic parameters determined from the glass spectra are given in Table III-3. Values for solid CS_2 solutions could not be obtained because the vanadyl dithiophosphinates became insoluble as the CS_2 freezing point was approached and the EPR spectrum of the solid consisted of a single broad line.

2.   Analysis of EPR Spectra in Mixed Solvents

The appearance of the EPR spectra of the vanadyl complexes is changed dramatically when a small amount of a strongly coordinating ligand is added to the solution in an inert solvent at room temperature. The triplet structure superimposed on the vanadium hyperfine components is replaced by a doublet pattern indicative of a species in which the unpaired electron is interacting with only one phosphorus nucleus. See Fig. III-3a. Furthermore, the phosphorus

TABLE III-3

Anisotropic Magnetic Parameters[†] of the Vanadyl Dithiophosphinate Complexes in Different Solvents at -150°C

Solvent	Methyl Complex				Phenyl Complex				Ethoxy Complex			
	$g_\parallel$	$g_\perp$	$a_\parallel^V$	$a_\perp^V$	$g_\parallel$	$g_\perp$	$a_\parallel^V$	$a_\perp^V$	$g_\parallel$	$g_\perp$	$a_\parallel^V$	$a_\perp^V$
Toluene[††]	1.959	1.986	168	58	1.957	1.989	167	60	1.968	1.988	167	59
5% HMP/toluene	+++	+++	+++	+++	1.923	1.974	203	77	1.949*	1.980*	180*	62*
HMP	1.922	1.975	206	77	1.923	1.974	201	76	1.922	1.974	206	78
5% DMF/toluene	+++	+++	+++	+++	1.936	1.977	195	71	1.933	1.975	196	72
DMF	1.935	1.977	198	72	1.932	1.977	197	73	1.935	1.976	196	72
5% pyridine/toluene	+++	+++	+++	+++	1.956	1.982	169	58	1.959**	1.982**	168**	60**
Pyridine	1.956	1.977	174	58	1.954	1.979	171	57	1.954	1.980	173	60

† Hyperfine splitting constants are in Gauss. Estimated errors are $\pm.002$ in g-values and ± 1 Gauss in splittings.

†† The spectra in toluene show isotropic hyperfine interaction with two equivalent ^{31}P nuclei. ^{31}P splittings are 33.1, 33.5, and 51.5 Gauss, respectively, for the methyl, phenyl and ethoxy complexes. $g_\perp$ and $A_\perp^V$ could not be measured directly and were determined from the relations $g_\perp = (3g_0 - g_\parallel)/2$ and $a_\perp^V = (3a - a_\parallel)/2$.

+++ The spectrum is a complicated mixture of several species and the parameters could not be measured accurately.

* The spectrum of the ethoxy complex in 5% HMP/toluene is a superposition of a spectrum showing no ^{31}P interaction, and a spectrum indicating hyperfine interaction with a single ^{31}P nucleus. The parameters in the Table are those of the doublet spectrum with $a^{P1} = 31.5$ Gauss. The parameters for the singlet species are essentially the same as those for the ethoxy complex in HMP.

** The spectrum of the ethoxy complex in 5% pyridine/toluene is predominantly a spectrum indicating hyperfine interaction with a single ^{31}P nucleus. The parameters in the Table are those of the doublet spectrum with $a^{P1} = 36.4$. The parameters for the singlet species are essentially the same as those for the ethoxy complex in pyridine.

FIGURE III-3   EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in 5% HMP/toluene at various temperatures. The experimental spectra are shown above the computer simulations in each case. Stick spectra for the two dominant vanadyl species are shown at the bottom of the figure.

splitting has decreased substantially compared to the split-
tings observed in solutions without added ligand.

The EPR spectra of 10^{-3} $\underline{M}$ solutions of the methyl com-
plex in 5% HMP/toluene solution at various temperatures are
shown in Fig. III-3. The doublet patterns are observed in
the range 0°C to 30°C. Below 0°C, the spectral lines be-
come broad and poorly resolved. As the temperature of the
solution is increased a triplet hyperfine pattern begins
to appear and the doublet pattern decreases in intensity.
See Fig. III-3b. At 120°C, the doublet structure is very
weak and the spectrum consists predominantly of triplets,
indicating that the unpaired electron is interacting with
two equivalent ^{31}P nuclei. Since the magnetic parameters
describing this spectrum are identical to those for the
vanadyl complexes in the absence of HMP, it is logical to
conclude that this high temperature spectrum in 5% HMP/
toluene solution arises from the vanadyl dithiophosphinate
complex which is uncoordinated by HMP. Cooling the sample
back to 0°C gave an EPR spectrum which was identical to the
original spectrum at 0°C.

The appearance of the spectra of the vanadyl complexes
in 5% HMP/toluene at 0°C and at 120°C suggests that the
spectra obtained at intermediate temperatures are super-
positions of doublet and triplet patterns. The doublet
phosphorus splittings in the low temperature spectra were
determined by fitting the observed spectrum at 0°C with

computer synthesized spectra. With these phosphorus split-
tings, the triplet phosphorus splittings and the line-
widths of the various hyperfine components from the corres-
ponding triplet spectra in toluene, computed spectra for a
mixture of the two species with one and two phosphorus
splittings were generated. Since the g-values of the doublet
and triplet spectra are different (see Table III-4), a field
shift between the centers of the two spectra to be super-
imposed was incorporated in the spectral computation. The
relative proportions of doublet and triplet spectra were ad-
justed until the agreement between calculated and observed
was satisfactory. The individual synthesized doublet and
triplet spectra and the weighted sum of the two spectra
that constitute the calculated spectrum in Fig. III-3b are
shown in Fig. III-4.

The linewidths of the doublet species obtained in
pyridine/CS_2 solutions of the methyl complex were studied
from -45°C to +45°C. In all cases, the linewidths of the
doublet species were larger than the linewidths of the
triplet species in CS_2 solutions of the methyl complex at
the same temperature. Since the amounts of pyridine
required for predominance of the doublet species were small
(1-5%), these differences could not be attributed to
solution viscosity differences.[59] Detailed studies of the
linewidths of the doublet species obtained in the HMP/tol-
uene and DMF/toluene systems were not carried out because

TABLE III-4

Isotropic Magnetic Parameters[†] for Vanadyl Dithiophosphin-
ates in 5% HMP/Toluene and 5% Pyridine/CS_2 at 30°C[††]

Substituent of Dithiophosphinate	5% Pyridine/CS_2			5% HMP/Toluene		
	g_o	a_o^V	a^P	g_o	a_o^V	a^P
Methyl	1.974	95.0	24.9	1.970	100.1	24.0
Phenyl	1.975	95.0	25.5	1.968	100.2	24.5
Ethoxy	1.976	94.8	36.0	1.972	99.4	31.2

[†] Hyperfine splittings are in Gauss. Estimated errors
are $\pm$ .5 Gauss for splittings and $\pm$ .001 for g-values

[††] Only the ethoxy dithiophosphinate in 5% DMF/toluene at
30°C gives a predominantly doublet spectrum with
g_o = 1.975 a_o^V = 97.5 Gauss and a^P = 35.0 Gauss. Other
dithiophosphinate complexes give only triplets in 5%
DMF/toluene.

FIGURE III-4   Computer simulated EPR spectra of bis-(di-
methyldithiophosphinato)-oxo-vanadium(IV) in 5% HMP/tolu-
ene at 60°C.   (a) Doublet spectrum; (b) triplet spectrum;
(c) sum of doublet and triplet spectrum.

the addition of large amounts of these ligands to the solutions would be required in order for the doublet species to predominate. The estimation of doublet linewidths, in solutions containing considerably less ligand, from the linewidths obtained from solutions where the doublet species predominates is difficult because the solution viscosities are often very different. Instead, it was assumed that the linewidths of the doublet species in HMP/toluene and DMF/toluene solutions can be approximated by those of the triplet species in pure toluene at the same temperature. This approximation leads to small errors in the determinations of the relative amounts of doublet and triplet species from comparison of calculated and observed spectra. The calculated spectra which agreed most closely with the observed ones are shown in Fig. III-3, and the magnetic parameters characterizing the doublet species are given in Table III-4.

Further changes occur in the ^{31}P hyperfine structure when solutions containing a small amount of Lewis base are frozen and the glass spectra recorded. The EPR spectrum of the phenyl complex in 5% HMP/toluene (see Fig. III-2b) shows no phosphorus splitting at all. However, the spectrum of the methyl complex in the same solvent showed a mixture of several species whose individual magnetic parameters could not be measured. The spectra of the ethoxy complex in 1% HMP/toluene indicated the presence of two species -

one without phosphorus hyperfine splitting, and another with splitting due to one phosphorus nucleus. See Fig. III-5. The relative intensities of the singlet and doublet patterns were altered by changes in the HMP concentration, with a 1% HMP/toluene solution yielding a spectrum composed of pre-dominantly doublets. See Fig. III-5. The a^P value determined from the glass spectrum and the average of the aniso-tropic ^{51}V hyperfine splittings computed using equation (III-16) are equal to the respective isotropic values determined from the doublet spectrum of the liquid. The glass spectrum of the phenyl complex shows a singlet pattern in both 5% DMF/toluene and 5% pyridine/toluene solutions, although the spectrum of the methyl complex shows a com-plicated mixture in both solvent systems. The ethoxy com-plex in 5% DMF/toluene has a singlet glass spectrum, while in 5% pyridine/toluene the spectrum shows two patterns - a singlet and a doublet. a^P is again equal to the a^P value determined for the doublet species in the liquid spectrum of the same sample. These results point out that vanadyl complexes in solid solutions in 5% Lewis base/toluene pro-duce two species - one giving rise to a doublet spectral pattern and a second giving rise to a singlet pattern. The magnetic parameters of the observed species in the various solvents are compiled in Table III-3.

The EPR spectra of the vanadyl dithiophosphinates in pyridine, DMF and HMP glasses all show the absence of any

FIGURE III-5 EPR spectra of 10^{-3} M solid solutions of bis-(O,O'-diethyldithiophosphinato)-oxo-vanadium(IV) at -150°C in (a) toluene; (b) 1% HMP/toluene;

phosphorus hyperfine interaction. The spectra of the phenyl complex in the three solid solutions are shown in Fig. III-6. The magnetic parameters for these singlet spectra for a given complex are equal, within experimental uncertainty, to those for the singlet spectra in 5% Lewis base/toluene solid solutions (compare the values in Table III-3). Furthermore, the spectra of the complexes in pyridine, DMF and HMP at 30°C consist predominantly of eight singlet hyperfine lines with magnetic parameters equal, within experimental error, to the average of the anisotropic parameters obtained from the glass spectrum for the same complex-solvent system. The spectra of the phenyl complex in HMP at 116°C and in DMF at 30°C are shown in Fig. III-7. The singlet hyperfine patterns remain singlets within the liquid range of HMP and DMF, but in pyridine the spectrum shows a mixture of doublet and singlet patterns at higher temperatures as shown in Fig. III-8. The behavior of the methyl and ethoxy complexes in pyridine, HMP and DMF is similar to that of the phenyl complex in pyridine except that the doublet pattern appears at lower temperatures for the methyl complex. The isotropic magnetic parameters for the singlet patterns are compiled in Table III-5.

The EPR spectra of the methyl complex in pyridine/CS_2 mixed solvents at -45°C and in neat pyridine at 30°C are shown in Fig. III-9. It is clear that the doublet spectrum observed at low concentrations of pyridine decreases in

FIGURE III-6 EPR spectra of 10^{-3} $\underline{M}$ solid solutions of bis-
(diphenyldithiophosphinato)-oxo-vanadium(IV) at
-150°C in (a) HMP; (b) pyridine; (c) DMF.

FIGURE III-7 EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of bis-(diphenyldithiophoshphinato)-oxo-vanadium(IV) in HMP at 116°C and DMF at 30°C.

FIGURE III-8 EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of
bis-(diphenyldithiophosphinato)-oxo-vanad-
ium(IV) in pyridine at 30°C and 90°C. The
stick spectra for the two dominant vanadyl
species are given at the bottom of the
figure.

FIGURE III-9   EPR spectra of 10^{-3} $\underline{M}$ liquid solutions

of bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in

pyridine/CS$_2$ mixtures of various compositions at -45°C.

The spectrum in 100% pyridine was recorded at 30°C.

The stick spectra for the two dominant vanadyl species

are given at the bottom of the figure.

62.

0.5% PYRIDINE/CS$_2$

2.0% PYRIDINE/CS$_2$

5.0% PYRIDINE/CS$_2$

100% PYRIDINE

200 G

TABLE III-5

Isotropic Magnetic Parameters[†] of Vanadyl Dithiophosphinate

Complexes in Coordinating Solvents

Complex	Pyridine at 30°C		DMF at 30°C		HMP at 116°C	
	g_o	a_o^V	g_o	a_o^V	g_o	a_o^V
Methyl	1.9740	93.5	1.9666	111.0	1.9657	113.9
Phenyl	1.9741	95.8	1.9649	112.9	1.9605	118.8
Ethoxy	1.9738	95.6	1.9652	113.0	1.9675[††]	109.8[††]

[†] Hyperfine splittings are in Gauss. Estimated errors are ± 0.5 for hyperfine splittings and ± .0005 for g-values.

[††] Spectrum is predominantly doublets. Parameters are those of the doublet species with a^P = 30.0 Gauss.

intensity as the pyridine concentration is increased and a new spectrum appears which has no ^{31}P hyperfine structure. The magnetic parameters of the singlet are equal, within the experimental error, to the magnetic parameters of the methyl complex in pure pyridine. A close examination of the spectra of the vanadyl dithiophosphinates in liquid toluene solutions with low HMP concentrations indicates the presence of peaks of low intensity which are not accounted for by the dominant doublet and triplet spectra. See Fig. III-3c. These weak lines occur at positions which are very close to those found in the singlet spectra of the complexes in solutions with high HMP concentrations. It appears that in all cases, when a Lewis base with strong electron donor properties is added to the toluene solutions of the vanadyl dithiophosphinates, three species, each with a dramatically different EPR spectrum, are present.

The preceding description of the experimental results has concentrated on the effects of the ligands HMP, DMF and pyridine on the EPR spectra of the vanadyl dithiophosphinate complexes. Experiments have also been performed with other ligands which are less strongly coordinating. In toluene solutions containing various concentrations of dimethyl sulfoxide, phosphoryl chloride, triphenylphosphine oxide or trimethyl phosphate, the EPR spectra indicated the presence of more than one species and most of the lines could be ascribed to singlet, doublet or triplet ^{31}P hyperfine patterns. See Fig. III-10. Detailed

FIGURE III-10 EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of bis-
(dimethyldithiophoshpinato)-oxo-vanadium(IV)
in 10% dimethyl sulfoxide/chloroform at 60°C
and bis-(O,O'-diethyldithiophosphinato)-oxo-
vanadium(IV) in 10% trimethyl phosphate/tolu-
ene at 40°C. The stick spectrum of the doub-
let pattern is shown below the experimental
spectrum in each case.

analyses of the behaviour of the dithiophosphinate complexes in these solvent systems were not carried out since the HMP, DMF, and pyridine systems typify the results to be expected in other cases, and a clear separation of the different species was possible in the HMP, DMF, and pyridine solutions by variations in ligand concentration and sample temperature.

It has been reported [17] that the ethoxy complex is unstable in ethanol solutions. An investigation of the EPR spectra of both phenyl and ethoxy complexes in ethanol showed that the phenyl complex gives triplet ^{31}P hyperfine splitting, while the ethoxy complex shows a mixture of doublet and triplet hyperfine patterns whose relative intensities vary with the temperature. See Fig. III-11. The behavior of ethanol is similar to that of DMF which produced a mixture of doublets and triplets only with the ethoxy complex.

3.   Analysis of Optical Spectra

The visible and near infrared spectra of the phenyl complex in several solvents are shown in Fig. III-12. The spectrum in toluene displays bands at 14.3, 17.1 and 24.4 kK which are characteristic of vanadyl complexes. In contrast to the spectra of $VO(H_2O)_5^{2+}$ [31] and $VO(acac)_2$ [60], the spectrum of the phenyl complex in toluene has a low intensity shoulder on the low energy side rather than on the high energy side of the intense band at 17.1 kK. However,

FIGURE III-11.   EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of
bis-(O,O'-diethyldithiophosphinato)-oxo-
vanadium(IV) in ethanol at 25°C and at 60°C.
The stick spectrum of the doublet pattern
is shown below the experimental spectrum at
25°C.

FIGURE III-12   Electronic absorption spectra of bis-(diphenyldithiophosphinato)-oxo-
vanadium(IV) in various solvents. ———, toluene; — — —, 5% HMP/toluene,
· · · ·, HMP; — · — · —, DMF; — — —, pyridine.

the spectrum in toluene does parallel the spectra of van-
adyl dithiocarbamates in non-coordinating solvents reported
by McCormick.[10] McCormick assigned the most intense band
to the $b_1 \rightarrow e^*$ transition since this band experienced sig-
nificant shifts when a ligand coordinated to the sixth
position. The $e^*(d_{zx}, d_{zy})$ level is expected to be changed
by coordination at the axial site while the $b_2^*(d_{xy})$ level
is expected to be nearly independent of coordination at
the sixth position. Since the ligand field produced by
the dithiocarbamates should approximate that of the dithio-
phosphinates, it is reasonable to assign the electronic
transitions as proposed by McCormick.[10] Then, with increas-
ing energy, the three transitions are $b_1 \rightarrow b_2^*$, $b_1 \rightarrow e^*$ and
$b_1 \rightarrow a_1^*$. The spectra for the methyl and ethoxy complexes
are very similar to the spectrum of the phenyl complex
and the transitions are assigned equivalently as shown in
Table III-6. The spectra in the other non-coordinating
solvent, CS_2, are similar to those in toluene.

The visible spectrum of the phenyl complex in the
Lewis bases DMF and pyridine resembles the spectrum of
$VO(H_2O)_5^{2+}$.[31] One expects the phenyl complex to be six-
coordinate in Lewis base solvents. The presence of an
additional ligand could shift the $e^*(d_{zx}, d_{zy})$ level to
lower energy while the b_2^* level remains relatively constant.
With this inversion of levels, the transitions in order of
increasing energy would be $b_1 \rightarrow e^*$, $b_1 \rightarrow b_2^*$ and $b_1 \rightarrow a_1^*$,

TABLE III-6

Electronic Spectra of Dithiophosphinate Complexes [†]

Complex	Solvent [††]	a_2^*	b_1^*, b_2^*	a_1^*
			Assignment	
Methyl	A	14.3	16.7	24.7 sh
	B	12.2	13.5	26.0 sh
	C	11.9	13.2	[†††]
	D	15.4	12.6	[†††]
	E	14.7	12.0	[†††]
Phenyl	A	14.3	17.1	24.4 sh
	B	12.0	13.7	25.6 sh
	C	11.2	13.2	24.4 sh
	D	15.4	12.7	[†††]
	E	15.9	12.7	[†††]
Ethoxy	A	14.9	17.5	24.4 sh
	B	12.8	13.7	25.3 sh
	C	11.1	13.3	25.0 sh
	D	15.4	12.7	[†††]
	E	16.4	12.7	22.2 sh

[†]   Absorption maxima in kK.

[††] A, toluene; B, 5% HMP/toluene; C, HMP; D, DMF:
      E, pyridine. CS_2 and toluene spectra are equivalent.

[†††] No shoulder is observed.

71.

which is the assignment Ballhausen and Gray [31] have pro-
posed for the pentaquo vanadyl cation. The two energy
level schemes are shown in Fig. III-13.

In both pure HMP and 5% HMP/toluene solutions, it
appears that both the e^* and b_2^* levels are shifted to
lower energy by the addition of an HMP ligand to the van-
adyl complex. The energy levels are assumed to have the
same relative order as in toluene. However, the species
in 5% HMP/toluene is different from the species in pure
HMP because vanadyl complexes in 5% HMP/toluene give rise
to a doublet pattern in the EPR spectrum and in pure HMP
they give rise to a singlet pattern. Shifts of the optical
bands of vanadyl complexes resulting from addition of
Lewis bases have also been observed by other workers.[10,22,60]
The shifts observed for the vanadyl dithiophosphinates
support the EPR results in that new species are formed in
the presence of a Lewis base and one anticipates the new
species are a result of differences in the coordination
to the vanadyl ion.

The spectral results discussed above for the phenyl
complex are also observed for the methyl and ethoxy com-
plexes. The absorption maxima and band assignments are
given explicitly in Table III-6.

4.   Analysis of Infrared Spectra

The frequency of the vanadyl vanadium-oxygen stretch

a_1^* ———— d_{z^2} ————————————————— d_{z^2} ———— a_1^*

b_2^* ———— d_{xy} d_{xz}, d_{yz} ———— e^*

e^* ———— d_{xz}, d_{yz} d_{xy} ———— b_2^*

b_1 ———— $d_{x^2-y^2}$ ————————————————— $d_{x^2-y^2}$ ———— b_1

a   b

FIGURE III-13   Energy level schemes for oxo-vanadium(IV) complexes. (a), Ballhausen-Gray scheme [31]; (b), inverted level scheme.[2] The closely spaced lines represent filled bonding levels. The splittings are not drawn to scale.

is often used to infer information about the coordination
at the axial position of five coordinate vanadyl compounds.
[8,36,61] The V-O stretch in the phenyl complex was observed
to change from 1000 cm^{-1} in CS_2 to 976 cm^{-1} in 5% pyridine/
CS_2 and the V-O stretch in the methyl complex changed from
996 cm^{-1} in CS_2 to 972 cm^{-1} in 5% pyridine/CS_2. In both
cases the shift is 24 cm^{-1} and EPR spectra of the samples
in 5% pyridine/CS_2 showed predominantly doublet hyperfine
patterns. This evidence suggests that the species giving
rise to the doublet EPR spectrum has the position _trans_ to
the vanadyl oxygen occupied.

The infrared spectra of dithiophosphinates in the
region 500-700 cm^{-1} show absorptions due to the P-S
stretching vibrations. The position of the symmetric P-S
stretch, ν_{sym}, is sensitive to the nature of the bonding
of the sulfur atoms in the dithiophosphinate moiety.[13,15]
See Table III-7. ν_{sym} decreases progressively as the bond-
ing at the sulfur atoms changes from bidentate to ionic
to monodentate. The infrared absorption of the bis-(di-
phenyldithiophosphinato)-oxo-vanadium(IV) complex in CS_2
solutions with various amounts of pyridine added has been
studied, and the results are shown in Fig. III-14. In the
absence of pyridine, a single ν_{sym} absorption is observed
at 570 cm^{-1}. Upon the addition of pyridine, additional
absorptions at 560 cm^{-1} and 538 cm^{-1} appear. As the con-
centration of pyridine is increased, the intensity of the

TABLE III-7

Frequencies of Symmetric P-S Stretching Vibrations in Diphenyl-dithiophosphinate Compounds[†]

Compound	Bonding at Sulfur	$\nu_{sym}(cm^{-1})$	Medium
Bis-(diphenyldithio-phosphinato)-oxo-vanadium(IV)		570	CS_2
Sodium diphenyldithio-phosphinate		565	Nujol mull
Ammonium diphenyldi-thiophosphinate		561	Nujol mull
Diphenyldithiophosphinic acid		530	Nujol mull

[†] Infrared frequencies from ref. 13 and 15.

<u>FIGURE III-14</u> Infrared spectra of bis-(diphenyldithiophos-
phinato)-oxo-vanadium(IV) in pyridine/CS$_2$
solutions of various compositions.

absorption at 570 cm^{-1} decreases, while the intensities of the peaks at 538 and 560 cm^{-1} increase. The absorption at 538 cm^{-1} is maximum at a pyridine concentration of 10%, and decreases in intensity at higher pyridine concentrations. It is clear from Fig. III-14, that three distinct absorptions are present in the symmetrical P-S stretching region in 100% pyridine solutions of the phenyl complex. Spectral studies of the methyl complex were hampered by the low solubility of the complex in CS_2, and the air sensitivity of the ethoxy complex prevented study of its infrared spectrum. Infrared studies with other mixed solvent systems were not feasible due to the presence of interfering absorptions in the regions of interest. The conclusions formed on the basis of the infrared spectra of the phenyl complex in the pyridine-CS_2 mixed solvent should be applicable to the other mixed solvent systems since the EPR results in the pyridine-CS_2 mixed solvent are similar to the EPR results in the HMP-toluene and DMF-toluene solvent systems.

5.   Conductance Results

Conductance measurements were performed to establish the presence or absence of ionic species in solutions. The conductance was measured as a function of the concentration of bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) in several solvents. Since the experiments were carried out under bench conditions, only the most stable phenyl complex was

investigated. The numerical results are given in Appendix
B and the summary of those results is shown in Table III-8.

TABLE III-8

Dependence of Conductance on Concentration of Bis-(diphenyl-
dithiophosphinato)-oxo-vanadium(IV) in Several Solvents.

Solvent	Concentration Dependence
1% HMP/toluene	independent
5% pyridine/CS_2	independent
10% HMP/toluene	linear
HMP	linear
Pyridine	linear
DMF	linear

E.   Discussion

1.   Discussion of Equilibria Between Different Vanadyl
      Species.

The EPR, infrared and electronic spectral results
presented in the previous section indicate the presence of
at least three distinct vanadyl species in solutions con-
taining a low concentration of a vanadyl dithiophosphinate

complex and varying concentrations of a strongly coordin-
ating ligand. The species which dominates at the highest
temperatures with low concentrations of coordinating ligand,
and gives rise to a triplet ^{31}P hyperfine pattern in the
EPR spectrum, indicating the presence of two equivalent
phosphorus atoms, has been identified as the 5-coordinate
vanadyl dithiophosphinate itself and will be referred to
as species T.

A second vanadyl species, to be referred to as
species D, is characterized by a doublet hyperfine structure
in the EPR spectrum, which indicates that the unpaired
electron is interacting with only one ^{31}P nucleus. This
vanadyl species may contain a single phosphorus atom or
it may contain two non-equivalent phosphorus atoms, only
one of which gives rise to an observable hyperfine splitting.
The former possibility would require dissociation of the
vanadyl dithiophosphinate to form a species with a single
dithiophosphinato chelating moiety. Since the only possible
ligands which can replace the chelating ligand are the un-
charged Lewis bases in relatively low concentration in the
solution, any vanadyl species containing a single dithio-
phosphinate chelate would be charged - a most unlikely species
in non-polar solvents such as toluene and CS_2.

A simple procedure for detecting the presence of
charged species in solution is to measure the conductance
of the solution. For a solute that ionizes completely, the

conductance of the solution increases linearly with increas-
ing solute concentration up to approximately 10^{-1} $\underline{M}$.[62] The
conductivities of solutions containing the phenyl complex
in concentrations ranging from zero to 7 x 10^{-3} $\underline{M}$ in the
solvents 1% HMP/toluene and 5% pyridine/CS_2 were determined.
In both solvent systems, the conductance was unaffected by
the presence of the phenyl complex. The EPR spectra of the
same solutions exhibited a predominantly doublet hyperfine
pattern. One concludes that species D is not charged. How-
ever, the conductance experiments do not rule out the possib-
ility that species D is a solvent separated ion pair in
which the solvent (in this case the Lewis base present in
the solution) occupies the first coordination sphere and the
dithiophosphinate counterion resides in the second coordin-
ation sphere. The formation of such ion pairs is favorable
when there is a strong interaction between the ion and the
solvent and the counterion is relatively large.[63] These
conditions are certainly the case for the phenyl complex
in 1% HMP/toluene or in 5% pyridine/CS_2.

The infrared spectrum of the phenyl complex in 5%
pyridine/CS_2 solution indicates the presence of three dithio-
phosphinate species in addition to species T, the five-
coordinate vanadyl complex (see Fig. III-14). A small
shoulder at 560 cm^{-1} suggests that the solution contains
an ionic diphenyldithiophosphinate species (see Table III-
7), which, on the basis of the conductance measurements,

could be either an ion pair (see structure I) or a free

dithiophosphinate ion at a concentration below the detec-

tion level of the conductance apparatus ($<10^{-4}$ M). The

infrared absorption at 538 cm^{-1} indicates the presence

of a species containing a monodentate dithiophophinate

moiety [15], for which structure II is suggested. In

this structure, one phosphorous nucleus is sufficiently

far removed from the vanadium atom that it will not experi-

ence significant hyperfine interaction with the unpaired

electron. The presence of a third species, for which is

suggested a possible structure III, is indicated by a

broadening of the band at 570 cm^{-1} due to overlapping with

a new absorption at lower frequency. (See Fig. III-14).

This second band could arise from a structure with one of

the diphenyldithiophosphinate ligands arranged so that one

of its sulfur atoms occupies the axial coordination site,

and a pyridine ligand is coordinated at the equatorial site

(structure III). Similar arrangements are known for adducts

of VO(acac)$_2$.[8,36] The axial sulfur-vanadium bonding is

expected to be weaker than the equatorial sulfur-vanadium

bonding, and the non-equivalence of the sulfur atoms should

cause the P-S stretching frequency to shift towards that of

monodentate dithiophosphinates. In structure III, the two

phosphorus nuclei are non-equivalent and it is conceivable

that the hyperfine interaction of the phosphorus nucleus

in the cross-coordinated chelate would be too small to be

observed in the EPR spectrum.

On the basis of the intensities of the infrared absorptions, the concentration of the species which gives rise to the absorption at 560 cm^{-1} (structure I) is small in solutions containing 5% pyridine or less, and need not be considered further in the discussion of species D. The EPR spectra of solutions where the doublet hyperfine pattern predominates provide no evidence for the existence of two distinct species, structures II and III, as suggested by the infrared spectra. The magnetic parameters, particularly the ^{31}P hyperfine interactions, of structure II and III are likely to be similar since the axial sulfur-vanadium bonding is expected to be very weak. It is shown above that the coordination of a pyridine molecule at the axial position either does not occur, or that the effect of such coordination on the magnetic parameters of the complex is insignificant, because the EPR spectra of the

vanadyl species T in 1% pyridine/CS_2 and in pure CS_2 solutions are identical. Furthermore, the rate of exchange between structures II and III is probably fast on the EPR time scale so that any small differences in the EPR spectra of structures II and III would be averaged out and undetectable. It is therefore concluded that species D is in fact two distinct species with structures II and III, but that EPR measurements can detect only the composite spectrum of these structures.

The number x of Lewis base molecules L involved in the equilibrium

$$T + xL \rightleftharpoons D$$

was determined for the vanadyl dithiophosphinates by analyzing the EPR spectra of solutions containing different Lewis base and complex concentrations. The appropriate equilibrium constant is written as

$$K_{T-D} = \frac{[D]}{[T][L]^x} \qquad (III-21)$$

The relative concentrations of species D and species T were obtained from computer-synthesized EPR spectra which resembled most closely the observed EPR spectra. Knowing the ratio of the concentration of these species, $R = [D]/[T]$, one can express K_{T-D} in terms of the known quantities R, $[L]^\circ$, the total Lewis base concentration, and $[T]^\circ$, the total vanadyl concentration.

$$K_{T-D} = \frac{R(R + 1)^X}{([L]^\circ + R[L]^\circ - xR[T]^\circ)^X}$$

(III-22)

Examples of the calculated values of K_{T-D} for integral values of x are shown in Table III-9. Consistent values of K_{T-D} were obtained only for the case x = 1, which is compatible with structures II and III for species D. The equilibrium constant K_{T-D} was determined at several temperatures, for the three complexes in various solvent systems and the results are shown in Fig. III-15. The values of K_{T-D} at 298K, and the enthalpies of adduct formation ΔH_{T-D}° calculated from the slopes of the lines in Fig. III-15 are given in Table III-10. These heats of adduct formation are similar in magnitude to those for the vanadyl acetylacetonate adducts with HMP, DMF and various amines. [4,5] The VO(acac)$_2$ adducts were assumed to arise from Lewis base coordination at the axial position whereas the adducts of the vanadyl dithiophosphinates have been shown to arise from ligand coordination at an equatorial site.

The room temperature equilibrium constants obtained from spectrophotometric measurements of the vanadyl dithiophosphinate complexes in toluene solutions containing different amounts of HMP and DMF are also shown in Fig. III-15. The equilibrium constants obtained from the spectrophotometric measurements were consistently higher than expected from an extrapolation of the equilibrium constants obtained from the EPR studies. This discrepancy can be attributed

TABLE III-9

Calculated K_{T-D} Values for Integral Values of x, the Number of
Lewis Base Molecules in Triplet-Doublet Equilibrium

a. Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) in HMP-
    Toluene Mixed Solvents

	1% HMP/Toluene			5% HMP/Toluene		
x	75°	90°C	105°C	75°C	90°C	105°C
1	11	6.6	4.5	11	6.6	5.1
2	210	120	82	39	24	18
3	4,400	2,500	1,600	160	89	68
4	99,000	52,000	31,000	560	340	230

b. Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) in Pyri-
    dine-CS_2 Mixed Solvents at 45°C

x	0.5% Pyridine/CS_2	1.0% Pyridine/CS_2	2.0% Pyridine/CS_2
1	13	16	14
2	240	140	59
3	4,600	1,300	260
4	97,000	14,000	1,200

c. Bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in Pyridine-
    CS_2 Mixed Solvents at 45°C

x	1.0% Pyridine/CS_2	2.0% Pyridine/CS_2
1	9.3	8.0
2	77	33

TABLE III-9 (continued)

x	1.0% Pyridine/CS_2	2.0% Pyridine/CS_2
3	670	140
4	6,200	630

d. Bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in Pyridine-CS_2 Mixed Solvents at 0°C

x	0.10% Pyridine/CS_2	0.20% Pyridine/CS_2
1	110	84
2	23,000	5,200
3	23×10^6	47,000
4	27×10^{12}	71×10^6

TABLE III-10

Equilibrium Constants at 298K and Enthalpies of Adduct

Formation[†]

Complex	Ligand	K_{T-D} (1/mole)	$-\Delta H^O_{T-D}$ (kcal/mole)
Methyl	HMP	42	5.7 $\pm$ .9
	Pyridine	23	9.3 $\pm$ .2
Phenyl	HMP	63	7.7 $\pm$ 1.2
	Pyridine	31	7.7 $\pm$ .4
Ethoxy	HMP	160	7.5 $\pm$ 1.1
	DMF	1	7.2 $\pm$ 1.1

[†] Experimental K_{T-D} values were least squares fitted to
$K_{T-D} = Ae^{-\Delta H^O_{T-D}/RT}$ and errors given are the standard
errors from the least squares routine. K_{T-D} at 298K is
calculated using the least squares parameters.

FIGURE III-15   Temperature dependence of the equilibrium
constants, K_{T-D} for the formation of adducts of the vanadyl
dithiophosphinates with pyridine, HMP and DMF. K_{T-D} values
are calculated from EPR results except for values at
$10^3/T = 3.35 \ K^{-1}$ which are calculated from visible spectrum
results. $\triangle$, bis-(O,O'-diethyldithiophosphato)-oxo-vanadium
(IV) in HMP/toluene; $\blacktriangle$, bis-(O,O'-diethyldithiophosphato)-
oxo-vanadium(IV) in DMF/toluene; $\square$, bis-(diphenyldithio-
phosphinato)-oxo-vanadium(IV) in HMP/toluene; $\blacksquare$, bis-(di-
phenyldithiophosphinato)-oxo-vanadium(IV) in pyridine/CS_2;
O, bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in
HMP/toluene; $\bullet$, bis-(dimethyldithiophosphinato)-oxo-
vanadium(IV) in pyridine/CS_2. For clarity, the values
of K_{T-D} shown on the Figure for bis-(dimethyldithiophos-
phinato)-oxo-vanadium(IV) in pyridine/CS_2 are the observed
values divided by 10. The bars indicate estimated uncer-
tainties in the values of K_{T-D}.

to the presence of a third vanadyl species (which gives the singlet hyperfine structure in the EPR) in low concentrations. In the EPR measurements, the ratio [D]/[T] was determined from the observed spectra, but this ratio could not be measured spectrophotometrically since a solution containing only D could not be prepared and the extinction coefficients of this adduct could not be determined. Instead, the concentration of T was measured spectrophotometrically and the concentration of species D obtained by difference from the known total vanadyl concentration in the solution. The spectrophotometric equilibrium data is, therefore, less reliable than the EPR data, but does substantiate the conclusions based on the analysis of the EPR data. Furthermore, the ratio [D]/[T] calculated from the best fit EPR spectra for the HMP/toluene and DMF/toluene systems will be lower than the true value because the D and T linewidths were assumed to be equal. The EPR spectra of the methyl complex in .1 - 5% pyridine/CS_2 show that the doublet pattern has slightly larger linewidths than the triplet pattern. If one broadens the doublet spectrum in the computer synthesis of the spectra, a larger [D]/[T] ratio would be required to produce a spectrum with relative intensities similar to those obtained if triplets and doublets are assumed to have the same widths. See Fig III-16. Thus the K_{T-D} values calculated from EPR spectra in the HMP/ toluene and DMF/toluene systems are lower limits for the

FIGURE III-16 Computer synthesized EPR solution spectra
of bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in 5%
HMP/toluene at 60°C for a 1:1 ratio of doublet:triplet
pattern at various linewidths of the doublet pattern rel-
ative to the triplet pattern. (a), equal linewidths for
doublet and triplet pattern; (b), doublet linewidths 25%
broader than corresponding triplet linewidths; (c), doub-
let linewidths 50% broader than triplet linewidths.

equilibrium constants. This accounts for some of the dis-
crepancy between K_{T-D} values determined from spectrophoto-
metric and EPR measurements.

The two structures postulated to give rise to the
doublet pattern in the EPR spectrum, namely structures II
and III, are expected to have slightly larger molecular
dimensions in solution than species T. Since the reorient-
ational correlation time depends on the cube of the molecu-
lar radius (see equation III-20), a small increase in r
will result in a larger τ_r and hence broader EPR lines.
However, the lines of the doublet spectrum could also be
effectively broadened by a second ^{31}P hyperfine interaction.
This coupling could be large enough to split each line of
the observed doublet into an unresolved doublet and thus
effectively broaden the line. Computer synthesized spectra
for species D of the methyl complex in the pyridine/CS_2
solvent, incorporating a second small ^{31}P hyperfine inter-
action, showed that the second ^{31}P splitting was resolved
before the lines became as broad as the experimental lines.
Furthermore, the lineshape on an expanded sweep was
Lorentzian, which is not expected if the broadening results
from the overlapping of two lines. On this basis, it is
concluded the broader lines for the doublet pattern result
from species D having a slightly larger radius than species
T rather than from an unresolved hyperfine interaction.

A third vanadyl species, henceforth referred to as

species S, gives rise to an EPR spectrum which shows no hyper-fine interactions between the unpaired electron and the phos-phorus nuclei. The absence of ^{31}P hyperfine interactions indicates that species S has no chelating dithiophosphinate moieties. This species predominates under conditions of low temperature and high Lewis base concentration. The conduct-ance of a solution of the phenyl complex in 10% HMP/toluene varies approximately linearly with the concentration of the vanadyl complex. This implies that the vanadyl dithio-phosphinate complex dissociates under these conditions. The infrared spectrum of the phenyl complex in 10% pyridine/CS_2 solution (Fig. III-14) indicates that dithiophosphinate species with bidentate and monodentate coordination are present in addition to the ionic species. The structures IV are suggested as possible molecular arrangements which are consistent with the EPR spectrum and with monodentate dithiophosphinate coordination. The cis and trans isomers of IV are possible and could give rise to different EPR spectra if the magnetic parameters of the two isomers were sufficiently different. It is expected however that the differences in the magnetic parameters of the cis and trans isomers of IV would be very small.

IV

The relative concentrations of the D and S species involved in the equilibrium

$$D + x'L \rightleftharpoons S$$

in 1-5% pyridine/CS_2 solutions were determined by comparing the observed EPR spectra with computed spectra. The equilibrium constant

$$K_{D-S} = \frac{[S]}{[D][L]^{x'}} \qquad (III-23)$$

was calculated for integral values of x', and the values obtained were consistent with x' = 1 only. At -45°C, K_{D-S} has the value 3.1 l/mole for the methyl complex. This result indicates that the formation of species S from species D involves displacement of one of the sulfur atoms from vanadyl coordination by a ligand molecule. The species S involved in this equilibrium is assumed to have structure IV since the species must result from the addition of a single

ligand to structure II or III which represent species D,
and the simplest way for this to occur is for a second
ligand to displace one of the sulfur atoms of the bidentate
dithiophosphinate of structure II or III to make it a mono-
dentate ligand in structure IV. However, to explain the
conductance of the 10% HMP/toluene solution, the structure
IV species must be in equilibrium with ionized species in
which one or both dithiophosphinates are displaced from the
first coordination sphere of the vanadyl ion and ionized.
All species giving rise to a singlet EPR spectrum apparently
have very similar magnetic parameters since only one sing-
let species was resolved in the EPR spectrum.

The temperature dependence of the equilibrium between
species S and D warrants some comments since the EPR spectra
of the vanadyl dithiophosphinate complexes in pyridine,
HMP or DMF solution exhibit a temperature dependence. At
+30°C, the spectrum of the phenyl complex in pyridine (see
Fig. III-8) consists of eight well resolved lines with no
evidence of phosphorus hyperfine splittings. At higher
temperatures, doublets appear in the EPR spectrum. This
result is consistent with the decrease in the dielectric
constant [64] of pyridine as the temperature increases. The
lower dielectric constant destabilizes the dissociated form
and drives the equilibrium to the D side. Similar EPR
results were obtained for the ethoxy and methyl complexes
with the doublets appearing at lower temperatures in the

methyl and ethoxy complexes than in the phenyl complexes.
This may result from the greater stabilization of the di-
phenyldithiophosphinate anion due to charge delocalization
to the phenyl groups. Obviously there are numerous struc-
tures possible for the vanadyl species containing two or
more ligand molecules and yielding singlet hyperfine EPR
patterns. However, their magnetic parameters would be
similar and separate EPR lines for each would not be resol-
ved.

In DMF, the methyl complex shows EPR spectra above
40°C which are mixtures of triplets and singlets and a
relatively small amount of doublet. The spectra, shown in
Fig. III-17, indicate that the species giving rise to a
doublet pattern (structures I, II and III) are not pre-
dominant in pure DMF. This is in contrast to the results
of the methyl complex in 5% HMP/toluene and 5% pyridine/CS_2
where there was clearly a doublet-triplet equilibrium. The
phenyl and ethoxy complexes show singlet EPR spectra over
the complete temperature range of the liquid DMF. The
ethoxy spectra are shown in Fig. III-18. Attempts to gain
further insight into the coordination of DMF in the vanadyl
species that gives a singlet EPR spectrum were made by
studying the paramagnetic broadening of the NMR lines of
the DMF solvent. The temperature dependence of the line
broadening results for the phenyl complex in DMF was
similar to that for $VO(DMF)_5(ClO_4)_2$ in DMF but the magni-

FIGURE III-17.   EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of
bis-(dimethyldithiophosphinato)-oxo-vanadium(IV) in DMF at
various temperatures. The stick spectra for the predomin-
ant vanadyl species at 40°C and 120°C are given below the
corresponding experimental spectra.

40°C

200 Gauss

80°C

120°C

FIGURE III-18. EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of
bis-(O,O'-diethyldithiophosphinato)-oxo-
vanadium(IV) in DMF at various temperatures.

tude of the line broadening was greater for the phenyl

complex in DMF. (See Chapter IV). This indicated that the

rate of exchange of DMF from the vanadyl coordination

sphere was faster for the phenyl complex than for

$VO(DMF)_5(ClO_4)_2$. Furthermore, the conductance of the DMF

solution was linear in the concentration of phenyl complex.

It was therefore concluded that the predominant species

in a DMF solution of the phenyl complex is a singly charged

vanadyl complex with a monodentate dithiophosphinate ligand

occupying one coordination position and DMF occupying the

other positions. The lower charge of this species compared

to $VO(DMF)_5^{2+}$ is expected to weaken the vanadium-DMF bond

and consequently increase the rate of exchange. The per-

sistence of this dissociated form for the phenyl complex

is attributed to the high dielectric constant [64] of DMF

(36.1) relative to that of pyridine (12.3). The EPR

spectra of the complexes in HMP solution are similar to

those in DMF. This is expected since the dielectric con-

stants of HMP (30.0) and DMF are similar.

The EPR spectra of the phenyl and methyl complexes

in 5% DMF/toluene solution at 25°C are predominantly trip-

lets, while the spectra of the complexes in 5% pyridine/CS_2

or 5% HMP/toluene solutions are predominantly doublets.

This difference in the solvent systems is due primarily to

the differences in the electron donor properties of the

ligands.[65] The observation of adduct formation of the

ethoxy complex at lower ligand concentrations than those
required for formation of analogous adducts with the methyl
or phenyl complex indicates that the ethoxy complex is a
stronger Lewis acid than the methyl or phenyl complexes.

2.   Interpretation of g-values and Hyperfine Splitting
      Constants.

     The g-values and hyperfine splittings combined with
the energies of the electronic transitions form a basis for
the discussion of the molecular orbitals describing the
bonding in the vanadyl dithiophosphinates. Before the mag-
netic parameters can be related to molecular orbital co-
efficients, it is necessary to ascertain the ground elect-
ronic state of the complexes. Kivelson and Lee [25] have con-
cluded that the unpaired electron resides in a $b_1(d_{x^2-y^2})$
orbital in VO(acac)$_2$ and vanadyl tetraphenylporphyrin. If
the electron were in a $b_2(d_{xy})$ orbital, the coupling to the
nitrogen nuclei in vanadyl tetraphenylporphyrin would be
larger than the observed value of 2.8 Gauss. Furthermore,
residence in an $e(d_{xz}, d_{yz})$ orbital would result in a short
spin-lattice relaxation time due to a slight splitting of
the degeneracy by ligand field distortions away from C_{4v}
symmetry and would lead to much broader EPR lines than are
observed.

     The unpaired electron in vanadyl dithiophosphinates
and their Lewis base adducts is also believed to occupy a

molecular orbital of b_1 symmetry which is primarily the $d_{x^2-y^2}$ atomic orbital on the vanadium atom. If the electron were in the $b_2(d_{xy})$ orbital, then hyperfine interactions with the phosphorus atoms would occur _via_ the sulphur linkage; and the ^{31}P coupling would be expected to decrease by approximately one-half if the dithiophosphinate chelate became monodentate. On the other hand, if the unpaired electron resides in a $b_1(d_{x^2-y^2})$ orbital, coupling to ^{31}P nuclei can occur _via_ direct overlap of the vanadium $d_{x^2-y^2}$ orbital and the P 3s orbital. Then removing the phosphorus atom from the region of high probability of the $d_{x^2-y^2}$ orbital, as is the case for the species giving rise to the doublet spectrum, destroys the coupling to one P atom. The other ^{31}P atom is still in a region of high $d_{x^2-y^2}$ probability and of course interaction with this phosphorus atom is still observed. Residence in an $e(d_{xz}, d_{yz})$ level is unacceptable for the reasons given above for vanadyl tetraphenylporphyrin. Furthermore, the assignment of the unpaired electron to the $b_1(d_{x^2-y^2})$ orbital agrees with McCormick's [10] assignment for the vanadyl dithiocarbomates and their pyridine and dimethyl sulfoxide adducts.

The methods by which the magnetic parameters can be related to the molecular orbital coefficients and the energies of the excited electronic states in metal ions are described in detail by McGarvey.[66] In the LCAO

approximation, the molecular orbital occupied by the un-
paired electron in the ground electronic state of the
vanadyl complex having C_{2v} symmetry is assumed to be

$$\psi_1 = \alpha\{a \mid x^2-y^2 > + b \mid 3z^2-r^2 >\} - \alpha' \mid L_1 >$$

$$(\text{Symmetry } A_1) ,$$

and the lowest lying unoccupied molecular orbitals to be

$$\psi_2 = \beta \mid xy > - \beta' \mid L_2 > \qquad (\text{Symmetry } A_2) ,$$

$$\psi_3 = \gamma \mid zx > - \gamma' \mid L_3 > \qquad (\text{Symmetry } B_1) ,$$

$$\psi_4 = \delta \mid yz > - \delta' \mid L_4 > \qquad (\text{Symmetry } B_2) ,$$

and $\qquad \psi_5 = \eta\{a \mid 3z^2-r^2 > - b \mid x^2-y^2 >\} - \eta' \mid L_5 >$

$$(\text{Symmetry } A_1) .$$

where $\mid x^2-y^2 >$, $\mid 3z^2-r^2 >$, $\mid zx >$, $\mid yz >$ and $\mid xy >$ are
the vanadium atomic orbitals, $\mid L_1>$, $\mid L_2>$ ...., $\mid L_5>$ are
linear combinations of ligand orbitals of appropriate sym-
metry, and α, α', β, β', ..., η, η', are the normalized MO
coefficients. The mixing coefficients a and b describe
the mixing of the vanadium $\mid x^2-y^2>$ and $\mid 3z^2-r^2>$ orbitals
in forming the MO's. It is expected that b<<a since the
mixing is brought about by the C_{2v} perturbation upon a
strong C_{4v} ligand field. The spin orbit coupling, $\xi \hat{\vec{L}} \cdot \hat{\vec{S}}$,
where ξ is the spin orbit coupling constant and $\vec{L}$ is the
orbital angular momentum operator, mixes some excited state

character into the ground state wavefunction ψ_1. The first
order perturbed wavefunction, ψ_1, for the ground state MO is
then given by

$$\psi_1' = \psi_1 - i\alpha\gamma^2 \frac{(a-\sqrt{3}b)\xi|zx>}{E_3} - i\alpha\delta^2 \frac{(a+\sqrt{3}b)\xi|yz>}{E_3}$$

$$+ \frac{2i\alpha\beta^2 a\xi|xy>}{E_2} \ .$$

Combining ψ_1' with the two possible spin functions for a
single electron, one obtains a pair of molecular spin
orbitals. The representation of the spin Hamiltonian in
this basis set requires the following relationships between
the elements of the g and A^V tensors and the MO coefficients
and the energies of the electronic transitions.

$$g_{||} - 2.0023 = -8a^2\alpha^2\beta^2\xi/E_2 \qquad\qquad (III-24)$$

$$g_\perp - 2.0023 = -2a^2\alpha^2\gamma^2\xi/E_3 \qquad\qquad (III-25)$$

$$a^V_{||} = P \left\{ -K - \frac{4}{7} a^2\alpha^2 + (g_{||} - 2.0023) \right.$$

$$\left. + \frac{3}{7}(g_\perp - 2.0023) \right\} \qquad\qquad (III-26)$$

$$a^V_\perp = P \left\{ -K + \frac{2}{7}a^2\alpha^2 + \frac{11}{14}(g_\perp - 2.0023) \right\} \quad (III-27)$$

where K is the isotropic hyperfine contribution and P =
2.0023 $\beta_\circ g_N\beta_N<r^{-3}>$ where g_N is the g-value of the nucleus
and β_N is the nuclear magneton. The excitation energies
of the states described by ψ_2 and ψ_3 relative to the

state ψ_1, are designated E_2 and E_3.

In the equations (III-24) to (III-27) orbital overlap corrections have not been included, and the effects of the admixture of some $|3z^2-r^2>$ into the orbital ψ_1, have been ignored because the observed EPR spectra are adequately described in terms of axial symmetry. The assumption of approximate axial symmetry implies the near degernacy of the states ψ_3 and ψ_4. The neglect of contributions from the spin-orbit interactions of the sulfur nuclei is justified since the unpaired electron is highly localized on the vanadium atom.

In order to interpret the observed magnetic parameters in terms of MO coefficients and thereby obtain information about the bonding in the vanadyl complexes, an assignment of the electronic spectrum must be made. The basis for this assignment has been discussed in the previous section for the various solvent systems and the assignments given in Table III-6.

The MO coefficients α, β and γ were determined from the observed g-values and vanadium hyperfine splitting components using equations (III-24 to III-27) and[27] $P = 133$ Gauss and $\xi = 168$ cm^{-1}. The MO coefficients are tabulated in Table III-11. The magnitudes of the coefficients cannot be considered accurate because of the uncertainties in the spin-orbit coupling ξ and the dipolar hyperfine factor P.

TABLE III-11

Molecular Orbital Coefficients

Complex	Solvent	Species	α^2	β^2	γ^2	K	K/α^2
Phenyl	Toluene	T	.892	.642	.742	.696	.780
Ethoxy	Toluene	T	.914	.412	.798	.694	.759
Ethoxy	5% HMP/Toluene	D	.866	.538	1.04	.730	.843
Ethoxy	HMP	S	1.04	.635	1.06	.862	.829
Ethoxy	DMF	S	1.02	.752	.962	.812	.796
Ethoxy	Pyridine	S	.928	.631	.896	.703	.758

As Hitchman and Belford [27] have indicated, α is close to 1 in all cases, indicating that the electron is essentially localized on the vanadium atom. α is lower for species T than for the S species which suggests the d_{zx} and d_{zy} orbitals contribute more to π bonding with sulfur than with oxygen or nitrogen ligands. In all cases, β is smaller than unity due to the strong σ-interactions between the vanadium d_{xy} orbital and ligand p orbitals.[67] The relative β values suggest that σ bonding with S is more covalent than with N or O.

The variations in the ^{51}V isotropic hyperfine parameter, a_o^V indicate that one of the factors which affects the isotropic splitting is the amount of delocalization of the $b_1(3d_{x^2-y^2})$ orbital onto the ligands. The largest α values correspond to species which also have the largest observed a_o^V. As Kivelson and Lee [25] have indicated, the variations in K/α^2 are probably due to changes in coordination at the vanadium atom. The amount of s-character in the b_1 orbital, containing the unpaired electron, and the effectiveness of spin polarization contributions to the isotropic ^{51}V interaction will certainly differ in species with different coordination.

3.   Hyperfine Interactions

The mechanism of the hyperfine interaction between the ^{31}P nuclei in the dithiophosphinate chelates with the unpaired electron on the vanadium atom is believed to be

through a σ-interaction between the vanadium $d_{x^2-y^2}$ orbital and an appropriate linear combination cf the two P-S σ-bonding orbitals.[16] The hyperfine splittings will be influenced by the amount of phosphorus 3s character in the P-S σ-bonds. The coefficient c_{3s}^P, of the phosphorus 3s atomic orbital in the molecular orbital containing the unpaired electron, is related to the phosphorus hyperfine splitting by [68]

$$a^P = 3636|c_{3s}^P|^2 \quad .$$

The values of c_{3s}^P calculated from the observed ^{31}P hyperfine splittings in the phenyl and ethoxy complexes in toluene solutions are 0.095 and 0.117 respectively. The large difference in the coefficients and phosphorus splittings in these two complexes can be attributed to the difference in the amount of phosphorus s-character in the P-S bonds of the dithiophosphinate and dithiophosphate moieties. In the dithiophosphate complex, the P-S bonds are shorter and have more s-character than in the dithiophosphinate complexes. Infrared [69] and X-ray [70] evidence for differences in P-S bonding in these complexes have been reported.

When a Lewis base displaces one of the sulfur atoms of the dithiophosphinate or dithiophosphate from its coordination to the vanadium atom, the ^{31}P nucleus of this chelate no longer experiences significant hyperfine interactions because the spatial arrangement leads to a sub-

stantial decrease in the interaction between the vanadium

$d_{x^2-y^2}$ orbital and the P-S σ-orbitals. The hyperfine

splitting of the ^{31}P nucleus of the dithiophosphinate chel-

ate which has not been displaced is altered because the

bonding in the $V\overset{\displaystyle S}{\underset{\displaystyle S}{<}}P$ grouping will be modified by the

asymmetry of the coordination at the other equatorial sites

In the species D which result from the phenyl and ethoxy

complexes in solutions containing low concentrations of

pyridine, c_{3s}^P has the values 0.084 and 0.100 respectively.

It would appear that the destruction of the symmetry of the

coordination <u>trans</u> to the dithiophosphinate chelate leads

to lengthening of one or both of the P-S bonds and a

decrease in the amount of phosphorus s-character in the

P-S σ-bonds. The HMP adducts of the phenyl and ethoxy

complexes show smaller ^{31}P hyperfine splittings than the

pyridine adducts. This may be attributable to the differ-

ence in the effects of oxygen and nitrogen ligands coordin-

ation on the V-S and hence P-S bonding .

E.   Comparisons With Other Systems

    Since the vanadyl dithiophosphinates are structurally

similar to $VO(acac)_2$, both having the vanadium atom within

a square pyramidal arrangement of other atoms, a comparison

of the effect of Lewis base addition in the two systems

should be useful. The EPR results in both systems show

that a_o^V is changed by adduct formation. a_o^V for $VO(acac)_2$ in toluene is 108 Gauss but decreases to 105 Gauss in the pyridine adduct and 103 Gauss in the HMP adduct.[39] a_o^V for the vanadyl dithiophosphinates is 95 Gauss in toluene, remains unchanged in the pyridine adduct and increases to 100 Gauss in the HMP adduct. The adducts of the vanadyl dithiophosphinates being discussed here are those giving rise to a doublet pattern in the EPR spectrum (species D), a species which has been shown to contain one Lewis base molecule per vanadyl complex molecule. The decrease in a_o^V observed upon adduct formation in $VO(acac)_2$ is in contrast to the unchanged or increased a_o^V values observed for adduct formation of the vanadyl dithiophosphinates. The difference may be a result of the coordination by the Lewis base at different sites in the two vanadyl systems. Studies of $VO(acac)_2$ in 10% pyridine/benzene [39] assumed the pyridine coordinated at the axial site. Subsequent infrared studies have shown this to be the case for pyridine.[8] In contrast, previous sections of this Chapter showed that pyridine and HMP coordinated at the equatorial site of the vanadyl dithiophosphinates. It has also been pointed out that the EPR spectrum of $VO(acac)_2$ in 10% HMP/benzene at room temperature is composed of two species [39], one species having a_o^V equal to 103 Gauss and one species having a_o^V equal to 112 Gauss. Fig. III-19 shows that the relative amounts of the two species are nearly independent of temperature.

111.

FIGURE III-19 EPR spectra of 10^{-3} $\underline{M}$ liquid solutions of VO(acac)$_2$ in HMP at various temperatures.

The increase in the a_o^V value for one of the HMP adduct species, compared to a_o^V of $VO(acac)_2$ in benzene, parallels the increase in a_o^V observed when HMP coordinates at an equatorial site in the vanadyl dithiophosphinates. On this basis, the $VO(acac)_2 \cdot HMP$ species with the larger a_o^V value might be attributed to a complex in which HMP is coordinated at an equatorial site and the species with the smaller a_o^V value might be attributed to a complex in which HMP is attached to the axial site. Infrared studies of solutions of 2-methyl pyridine containing $VO(acac)_2$ have indicated the simultaneous existence of two isomers.[36] These isomers were also assigned as the 2-methyl pyridine adducts of $VO(acac)_2$; one isomer having 2-methyl pyridine axially coordinated and one isomer having 2-methyl pyridine equatorially coordinated. Other substituted pyridines have been shown to coordinate only at the equatorial position [8], which parallels the results presented here for the vanadyl dithiophosphinates.

Removal of the excess mixed solvent under vacuum from the EPR sample used to produce the spectra in Fig. III-19 left behind a green solid. This compound gave a microanalysis and a thermograph corresponding to a compound with the molecular formula $VO(acac)_2 \cdot HMP$. The isolation of this compound suggests that HMP does not displace the acetylacetonate from the first coordination sphere.

The conclusions reached from the study of Lewis base

coordination to vanadyl dithiophospinates suggest that the results of studies with vanadyl dithiocarbamates should be re-examined. One expects the V-S bonds of dithiophosphinates and dithiocarbamates to have similar properties. Adduct formation of vanadyl dithiocarbamates was assumed to involve coordination of Lewis bases such as pyridine and dimethyl-sulfoxide at the axial position.[9,10] This was concluded on the basis of changes in the vanadyl V-O stretching frequency and the ^{51}V hyperfine couplings, but the work reported in this thesis indicates that these probes are not sensitive enough to determine the changes in coordination about the vanadium atom that occur in the presence of Lewis base ligands. On the basis of the vanadyl dithiophosphinate results, one might expect coordination at the equatorial site at low Lewis base concentrations and displacement of the sulphur atoms from the first coordination sphere at higher concentrations.

CHAPTER IV

EQUATORIAL AND AXIAL SOLVENT EXCHANGE RATES OF VANADYL COMPLEXES

A.   Introduction

The rates of solvent exchange from the first coordina-
tion sphere of a metal ion are an important aspect of in-
organic solution kinetics. The general exchange reaction
can be represented by

$$MS_n + S^* \rightleftharpoons MS_{n-1}S^* + S \qquad (IV-1)$$

where S and S* are chemically identical and n is the number
of solvent molecules coordinated to the metal. On the left
hand side in equation (IV-1), S* is a bulk solvent molecule,
while on the right hand side S* is in the first coordination
sphere of the metal ion. The kinetic parameters for these
types of reactions can often be determined by the nuclear
magnetic resonance line broadening technique. In the fol-
lowing section the relevant magnetic relaxation theory is
presented and it is shown that under certain conditions [71],
the line broadening of the solvent resonance by a paramag-
netic ion is related to the solvent exchange rate, and the
temperature dependence of the line broadening can give the
activation parameters of the exchange process. The magni-
tude of the line broadening can also be used to calculate
the nuclear relaxation times of nuclei on solvent molecules
coordinated to the metal ion. These relaxation times are

interpreted in terms of the mechanisms causing the relaxation. Ultimately the relaxation times are controlled by the rotational correlation time of the metal complex which can be determined from the EPR linewidths of the metal complex.

The complexes $VO(DMF)_5(ClO_4)_2$ and $VO(DMA)_5(ClO_4)_2$ dissolved in DMF and DMA respectively can undergo the reaction represented by equation (IV-1). Since the vanadium atomic orbitals in these complexes which participate in the bonding of the axial ligand to the metal ion are different from those involved in the bonding of the equatorial ligands [31,32], the chemical properties of the two coordination sites should be quite different. Previous studies were not able to distinguish the exchange from the axial site to bulk solvent from the exchange of solvent molecules from the second coordination sphere into the bulk solvent. The results in section D show that the axial exchange has a special effect on the line broadening of DMF by vanadyl ion from which the kinetic parameters for both equatorial and axial exchange can be determined. Section D also contains line broadening studies of DMF solutions of $VO(acac)_2$ and bis-(o-phenanthroline)-oxo-vanadium(IV) perchlorate, both of which are expected to accept a DMF ligand at the vacant site.

The EPR and infrared data presented in Chapter III showed that Lewis bases in low concentrations coordinated

at the equatorial site of the vanadyl dithiophosphinates.
At higher Lewis base concentrations, several coordination
positions are occupied by the base molecules, but it was
not firmly established that the dithiophosphinate ligands
had been completely displaced from the first coordination
sphere of the vanadyl ion. To define the species in a sol-
ution of Lewis base, the DMF and DMA line broadening data
of the phenyl complex was collected and compared to the data
for the vanadyl perchlorates where the five inner sphere
coordination positions are known to be occupied by solvent
molecules. These results are given in section D-6.

A discussion of the solvent line broadening data is
presented in section E as well as some comparisons with
kinetic data from previous studies of vanadyl systems.

B.   Theory of NMR Line Broadening by Paramagnetic Complexes
1.   General Theory
The time dependence of the magnetization $\vec{M}$ for an
ensemble of free spins in a homogeneous magnetic field of
flux $\vec{B}$ is given by

$$\frac{d\vec{M}}{dt} = \gamma \vec{M} \times \vec{B} , \qquad (IV-2)$$

where γ is the gyromagnetic ratio of the spins. Upon the
application of a static magnetic field $\vec{B} = (0,0,B_0)$,
Bloch [72] assumed that the magnetization relaxed to its
equilibrium value M° with exponential time-dependence char-
acterized by a time constant T_1, the longitudinal or spin-

117.

lattice relaxation time. If the magnetization receives a

component in the plane perpendicular to B_0, this magnetiz-

ation is assumed to decay with a time constant T_2, the

transverse or spin-spin relaxation time. In a conventional

NMR experiment, the nuclear spins experience both a large

static field B_0 and a small field B_1 perpendicular to B_0

oscillating with a frequency ω; i.e. $\vec{B} = (B_1 \cos\omega t_1, - B_1 \sin\omega t,$

$B_0)$. Under these conditions the motion of the magnetization

is a superposition of the relaxation processes on the motion

of the free spins as indicated by the equation

$$\frac{d\vec{M}}{dt} = \gamma(\vec{M} \times \vec{B}) - \frac{(\vec{x}M_x + \vec{y}M_y)}{T_2} - \frac{(M_z - M_0)\vec{z}}{T_1}, \quad (IV-3)$$

where $\vec{x}$, $\vec{y}$ and $\vec{z}$ are unit vectors in a laboratory system in

which B_0 lies along the $\vec{z}$ direction. The three equations,

one for each component of the magnetization, represented

by equation (IV-3) are the well known phenomenological

Bloch equations. For mathematical convenience, the Bloch

equations are usually expressed in a rotating coordinate

system in which the x and y axes are rotating at frequency

ω about the z axis and the rotating component of $\vec{B}_1$ lies

along the x-axis of this rotating coordinate system. This

transformation is performed by defining the components

of the magnetization in the rotating coordinate system as

$$u = M_x \cos\omega t - M_y \sin\omega t,$$

$$v = M_x \sin\omega t - M_y \cos\omega t .$$

The component u is in phase with the magnetic field B_1 while v is the out-of-phase component. In the rotating coordinate system the Bloch equations take the form

$$\frac{du}{dt} = (\omega_o - \omega) v - u/T_2 , \qquad (IV-4)$$

$$\frac{dv}{dt} = -(\omega_o - \omega) u + \gamma B_1 M_z - v/T_2 , \qquad (IV-5)$$

$$\frac{dM_z}{dt} = -\gamma B_1 v - (M_z - M_o)/T_1 , \qquad (IV-6)$$

where $\omega_o = \gamma B_o$. By defining a complex magnetization, G, as the complex sum of the in-phase and out-of-phase components of the magnetization,

$$G = u + iv, \qquad (IV-7)$$

equations (IV-4) and (IV-5) may be combined into the single equation

$$\frac{dG}{dt} = -i\gamma B_1 M_z - (\frac{1}{T_2} - i\Delta\omega) G , \qquad (IV-8)$$

where $\Delta\omega = \omega_o - \omega$.

McConnell [73] has modified the Bloch equations to include the transfer of magnetization between different sites

by the chemical exchange of nuclei. For the simple case
of two sites, a solvent site S and a metal site M, the
Bloch equations for the nuclei in site S are written as

$$\frac{dG_S}{dt} = -i\gamma B_1 M_z^S - \left(\frac{1}{T_{2S}} + \frac{1}{\tau_S} - i\Delta\omega_S\right)G_S + \frac{G_M}{\tau_M} \quad , \qquad \text{(IV-9)}$$

where $\Delta\omega_S = \omega_S - \omega$, $\omega_S = \gamma_S B_o$, T_{2S} is the relaxation time
for nuclei in site S, τ_S is the lifetime of the spins in
site S and τ_M is the lifetime of the spins in site M. The
corresponding expression for the magnetization in site M is

$$\frac{dG_M}{dt} = -i\gamma B_1 M_z^M - \left(\frac{1}{T_{2M}} + \frac{1}{\tau_N} - i\Delta\omega_M\right)G_M + \frac{G_S}{\tau_S} \quad , \qquad \text{(IV-10)}$$

where $\Delta\omega_M = \omega_M - \omega$, $\omega_M = \gamma_M B_o$ and T_{2M} is the relaxation
time for nuclei in site M. In NMR experiments, the out-of-
phase component v is monitored as the field B_o or the fre-
quency ω is swept through the resonance at a rate which is
generally long compared to the intrinsic relaxation times
so that the spin system is always in equilibrium. This
condition is equivalent to setting $\dfrac{dM_z^S}{dt} = \dfrac{dM_z^M}{dt} = dG_S/dt =$
$dG_M/dt = 0$. Furthermore $M_z^S = M_o^S$ and $M_z^M = M_o^M$ since the
field B_1 is kept small enough to avoid saturation effects.
With these considerations, equations (IV-9) and (IV-10)
can be solved for the complex magnetization in the solvent
site, G_S. The resulting complicated expression can be

simplified by considering the special conditions used in studies of solvent linebroadening by paramagnetic species. First of all, the concentration of the solvent (site S) is much larger than that of the paramagnetic species (site M) and one is justified in dropping terms involving M_o^M compared to M_o^S terms. Also, the total magnetization, $G = G_S + G_M$, to a good approximation is equal to G_S since the signal being observed is that of nuclei in S sites. With these approximations, G can be written

$$G = \frac{-i\gamma B_1 M_o^S}{\left(\dfrac{1}{T_{2S}} + \dfrac{1}{\tau_S} - i\Delta\omega_S\right) - \dfrac{1}{\tau_S \tau_M}\left(\dfrac{1}{\dfrac{1}{T_{2M}} + \dfrac{1}{\tau_M} - i\Delta\omega_M}\right)}$$

(IV-11)

with imaginary part

$$v = \gamma B_1 M_o^S T_2 / [1 + \Delta\omega^2 T_2^2] , \qquad \text{(IV-12)}$$

where

$$\frac{1}{T_2} = \frac{1}{T_{2S}} + \frac{1}{\tau_S}\left\{\frac{\dfrac{1}{T_{2M}^2} + \dfrac{1}{T_{2M}\tau_M} + \Delta\omega_M^2}{\left(\dfrac{1}{T_{2M}} + \dfrac{1}{\tau_M}\right)^2 + \Delta\omega_M^2}\right\} , \qquad \text{(IV-13)}$$

and

$$\Delta\omega = \Delta\omega_S - \frac{\Delta\omega_M}{\tau_S \tau_M\left[\left(\dfrac{1}{T_{2M}} + \dfrac{1}{\tau_M}\right)^2 + \Delta\omega_M^2\right]} .$$

(IV-14)

This implies that the solvent NMR will be a Lorentzian line of width $\Delta\nu_{obs}$ (Hz) at half-height

$$\Delta\nu_{obs} = 1/\pi T_2 \quad , \tag{IV-15}$$

centred at

$$\omega_{obs} = \omega_S - \Delta\omega_M/\tau_M\tau_S\left[\left(\frac{1}{T_{2M}} + \frac{1}{\tau_M}\right)^2 + \Delta\omega_M^2\right], \tag{IV-16}$$

where $\Delta\omega_M$ in this last equation is the difference between the resonance frequencies of the nuclei in sites M and S. Furthermore,

$$\frac{1}{\tau_S} = n\frac{[M]}{[S]}\frac{1}{\tau_M} \quad , \tag{IV-17}$$

where n is the number of equivalent sites per paramagnetic species whose molal concentration, [M], is low compared to the solvent molality, [S].[74]

The paramagnetic line broadening

$$\Delta\nu_P = \pi^{-1}\left(\frac{1}{T_2} - \frac{1}{T_{2S}}\right)$$

$$= \pi^{-1}\frac{n[M]}{[S]\tau_M}\left\{\frac{\dfrac{1}{T_{2M}^2} + \dfrac{1}{T_{2M}\tau_M} + \Delta\omega_M^2}{\left(\dfrac{1}{T_{2M}} + \dfrac{1}{\tau_M}\right)^2 + \Delta\omega_M^2}\right\}, \tag{IV-18}$$

and resonance shift

$$\Delta\omega_{obs} = \omega_{obs} - \omega_S$$

$$= \frac{-n[M]\Delta\omega_M}{[S]\{(1 + \tau_M/T_{2M})^2 + \tau_M^2\Delta\omega_M^2\}}, \qquad (IV-19)$$

therefore vary linearly with concentration of paramagnetic ion.

Swift and Connick [71] have presented the analogous derivation for the three site problem and their result can be generalized to describe the situation for any number of sites. The resulting expressions for the line broadening and resonance shift are

$$\Delta\nu_p = \pi^{-1}\frac{[M]}{[S]}\sum_j \frac{n_j}{\tau_{M_j}} \cdot \frac{1/T_{2M_j}{}^2 + 1/T_{2M_j}\tau_{M_j} + \Delta\omega_j^2}{\left(1/T_{2M_j} + 1/\tau_{M_j}\right)^2 + \Delta\omega_j^2}, $$

$$ (IV-20)$$

$$\Delta\omega_{obs} = -\frac{[M]}{[S]}\sum_j \frac{n_j\Delta\omega_j}{(1 + \tau_{M_j}/T_{2M_j})^2 + (\tau_{M_j}\Delta\omega_j)^2}, $$

$$ (IV-21)$$

where n_j is the number of solvent molecules coordinated at sites of type j, τ_{M_j} is the average lifetime of a molecule coordinated at the j-th site, $1/T_{2M_j}$ is the nuclear relaxation time in the j-th site and $\Delta\omega_j$ is the difference between the resonance frequency for a nucleus in site j

and the observing frequency. The derivation of equations (IV-20) and (IV-21) neglects any exchanges among the different coordination sites since only bulk solvent to coordinated site exchange is included.

In the experimental NMR measurements of solutions containing vanadyl complexes, no paramagnetic shifts of the resonance frequencies were observed nor did the linewidths exhibit a frequency dependence. Therefore it was assumed that the $\Delta\omega_j^2$ terms in equation (IV-20) and (IV-21) were small compared to the other terms in the sum and could be neglected. This simplifies the expressions for $\Delta\nu_P$ and $\Delta\omega_{obs}$ to

$$\Delta\nu_P = \pi^{-1} \frac{[M]}{[S]} \sum_j n_j / (\tau_{M_j} + T_{2M_j}) \quad , \qquad (IV-22)$$

$$\Delta\omega_{obs} = \frac{[M]}{[S]} \sum_j n_j \Delta\omega_j / (1 + \tau_{M_j}/T_{2M_j})^2 \quad . \quad (IV-23)$$

The analysis of the linewidth data was performed using the reduced paramagnetic contribution, $1/T_{2P}$, defined by

$$\frac{1}{T_{2P}} = \pi \; \Delta\nu_P \; [S]/[M] \qquad , \qquad (IV-24)$$

which, from equation (IV-22), is given by

$$\frac{1}{T_{2P}} = \sum_j n_j / (\tau_{M_j} + T_{2M_j}) \quad . \qquad (IV-25)$$

$1/T_{2P}$ values are then independent of the properties of a particular sample and depend only on the relaxation times, T_{2M_j}, and the exchange rates, $1/\tau_{M_j}$, of the chemical system.

The paramagnetic line broadening produced by exchange between a coordinated site j and the bulk solvent exhibits two limiting conditions which are of interest in the present study. When $\tau_{M_j} >> T_{2M_j}$, the contribution to $1/T_{2P}$ from exchange at the j-th site is n_j/τ_{M_J}. In this limit, often referred to as the exchange controlled region, the nuclei are coordinated at site j for times which are long compared to the nuclear relaxation time at this site so that the rate of relaxation of molecules in the bulk solvent due to exchange with coordinated molecules is controlled by τ_{M_j}. When $\tau_{M_j} << T_{2M_j}$, the nuclei spend only a short time in coordination site j before reentering the bulk solvent and they may exchange many times before being relaxed at the coordinated site. In this limit, therefore, the contribution to $1/T_{2P}$ from exchange between bulk solvent and coordination site j is n_j/T_{2M_j}. This limiting condition is referred to as the T_{2M} region.

2. Temperature Dependence of Exchange Rates, Nuclear Relaxation Times and Chemical Shifts.

The temperature dependence of $1/T_{2P}$ is determined by the temperature dependence of the individual terms τ_{M_j}

and T_{2M_j}. The solvent exchange rates, $\tau_{M_j}^{-1}$, are of the form

$$\tau_{M_j}^{-1} = \frac{kT}{h} \exp \left(- \frac{\Delta H_j^{\ddagger}}{RT} + \frac{\Delta S_j^{\ddagger}}{R} \right) \qquad \text{(IV-26)}$$

on the basis of the transition state theory.[75] In equation (IV-26), k is Boltzmann's constant, h is Planck's constant, R the gas constant, T the absolute temperature and $\Delta H_j^{\ddagger}$ and $\Delta S_j^{\ddagger}$ are the enthalpy and entropy of activation for the exchange of molecules from the j-th coordination site into the bulk solvent. T_{2M_j} is determined by intimate details of the interaction of the nuclear spin with the unpaired electrons in the paramagnetic ion and the electron relaxation time. Ultimately, the nuclear relaxation rates for all coordination sites are related to the tumbling time τ_r for the complex ion. One therefore assumes that the temperature dependence of all T_{2M_j} is determined by the temperature dependence of τ_r and one writes

$$T_{2M_j}^{-1} = C_{M_j} \exp E_M/RT \quad , \qquad \text{(IV-27)}$$

where E_M is the activation energy for molecular tumbling and C_{M_j} are constants to be determined from the NMR line broadening data.

The rate of nuclear relaxation of a nucleus near a paramagnetic ion is dominated by the fluctuations of the dipolar and hyperfine interactions of the nuclear and

electron spins. A detailed analysis of the time-dependence of these interactions predicts that [76,77]

$$\frac{1}{T_{2M}} = \frac{7\gamma_I^2 g_o^2 \beta_o^2 S(S+1)\,\tau_r}{15 r_i^6} + \frac{S(S+1)}{3} A_o^2\, T_{1e} \qquad \text{(IV-28)}$$

where r_i is the average electron-nuclear separation, γ_I is the nuclear gyromagnetic ratio, S the electron spin angular momentum (S = 1/2 in the present studies), A_o is the nuclear-electronic hyperfine interaction and T_{1e} is the longitudinal electron relaxation time. The first term in equation (IV-28) represents the dipolar relaxation and the second is the relaxation rate due to modulation of hyperfine interactions. τ_r may be calculated from the EPR linewidth parameters α, β, γ and δ defined in equation (III-18) and measured values of the anisotropic magnetic parameters. The dependence of τ_r on these parameters is given explicitly by Wilson and Kivelson.[28] Angerman and Jordan [78] have indicated that the linewidth parameter γ is less sensitive to experimental errors than the other parameters and the values of γ obtained from an analysis of the EPR spectra can be used to calculate reliable values for the tumbling times τ_r of the vanadyl complexes. γ and τ_r are related by the equation [28]

127.

$$\gamma = \tau_r \left\{ \frac{b^2}{8} - \frac{7b(g_{||}-g_{\perp})A_o^V}{30g_o} + \frac{1}{1+\omega_o^2\tau_r^2}\left[-\frac{b^2}{40} - \frac{b(g_{||}-g_o)A_o^V}{6g_o} \right.\right.$$

$$\left.\left. - \frac{2b(g_{||}-g_{\perp})A_o^V\omega_o^2\tau_r^2}{5(1+\omega_o^2\tau_r^2)g_o} + \frac{b^2A_o^V\omega_o\tau_r^2}{8(1+\omega_o^2\tau_r^2)} \right] \right\} \quad , \qquad \text{(IV-29)}$$

where

$$b = \frac{2}{3}(A_{||}^V - A_{\perp}^V) , \qquad \text{(IV-30)}$$

ω_o is here the resonance frequency of the electron and other symbols are as defined earlier. Since equation (IV-29) results in a cubic equation for τ_r, τ_r was determined by an iterative procedure.

Another quantity which must be determined is the longitudinal electron relaxation time T_{1e}. The dominant contributions to T_{1e}^{-1} are the rotational modulation of anisotropic magnetic interactions [28] and collisional modulation of spin-rotational interactions.[57] The theory of relaxation by these mechanisms leads to the expression

$$\frac{1}{T_{1e}} \simeq \frac{2\tau_r}{1+\omega_o^2\tau_r^2}\left[\left(\frac{g_{||}-g_{\perp}}{g_o}\right)^2\frac{\omega_o^2}{15} + \frac{7b^2I(I+1)}{40} + \frac{b(g_{||}-g_{\perp})\omega_o M_V}{5g_o} \right.$$

$$\left. - \frac{b^2M_V^2}{40} \right] + \frac{(g_{||}-g_{e1})^2 + 2(g_{\perp}-g_{e1})^2}{9\tau_r} \quad , \qquad \text{(IV-31)}$$

where $g_{el} = 2.0023$ is the g-value of a free electron.

The temperature dependence of the contact shift of the NMR resonance $\Delta\omega_M$ and its dependence on the hyperfine coupling has been given by Bloembergen [79] as

$$\Delta\omega_M/\omega_I = \frac{S(S+1)g_\circ\beta_\circ A_\circ}{3\gamma_I kT} \qquad (IV-32)$$

where ω_I is the frequency of the NMR resonance of the solvent. Then if $1/T_{2M}$ results predominantly from a hyperfine interaction, one can calculate the expected contact shift and compare it with the experimental values.

The following analyses of the line broadening in DMA and DMF are concerned with three types of coordination sites: equatorial, axial and outer sphere. The exchange between outer solvation sphere and bulk solvent is fast compared to the relaxation of nuclei in the outer coordination sphere in the temperature regions investigated. Thus no outer sphere-bulk solvent exchange-controlled region for $1/T_{2P}$ is observed and the outer sphere contribution to $1/T_{2P}$ is described only by the relaxation time n/T_{2Mos} for the nuclei in the outer coordination sphere.

C.   Experimental

The investigation of the solvent exchange kinetics of the vanadyl complexes required measurement of the NMR spectra of the solvent alone and of solutions containing the para-

magnetic ion over the liquid range of the solvent. The
concentration of the paramagnetic species was adjusted to
maximize $\Delta\nu_p$ while maintaining a resonance narrow enough
to produce adequate intensities. From the recorded spectra
were measured the widths at half height and the chemical
shift relative to an internal reference. The raw line-
width data were converted to $1/T_{2P}$ as defined by equation
(IV-24) and plotted versus reciprocal temperature for
subsequent analysis. These experiments were carried out
for $VO(DMF)_5(ClO_4)_2$ in DMF, $VO(DMA)_5(ClO_4)_2$ in DMA, and
bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) in DMF,
DMA and in N,N-diethylformamide (DEF).

The EPR spectra of these systems were also studied
as a function of temperature and the linewidths of the
individual lines determined. In addition, the spectra of
the solid solutions were recorded and the anisotropic
magnetic parameters for the complexes were determined.

Infrared spectra in the 1600 - 1700 cm^{-1} containing
the carbonyl stretch absorption [80] were recorded for mulls
of the vanadyl perchlorates and liquid films of the
amides. Changes in the carbonyl absorption band upon co-
ordination are related to the type of coordination of the
amides to the vanadyl ion. The visible spectra of the
vanadyl perchlorates in DMF and DMA were also recorded and
compared with the optical absorption spectra of other
vanadyl systems.

D.   Results

1.   Analysis of Infrared, Visible and EPR Spectra

The characteristic feature of the infrared spectra of DMA, DMF and coordination compounds containing these molecules as ligands, is the carbonyl absorption in the region 1600 - 1700 cm^{-1}. The carbonyl band of $VO(DMF)_5(ClO_4)_2$ is shifted 30 cm^{-1} to lower frequency compared to uncoordinated DMF.[81] In addition, the carbonyl absorption for the complex is considerably broader than that in the free solvent. This indicates that there may be a number of nonequivalent coordinated DMF molecules. A similar broadening and a shift of 40 cm^{-1}, relative to liquid DMA, occurs in $VO(DMA)_5(ClO_4)_2$.

The visible spectrum of $VO(DMF)_5(ClO_4)_2$ in DMF solution has an absorption maximum at 12,600 cm^{-1}, and that of $VO(DMA)_5(ClO_4)_2$ in DMA occurs at 12,300 cm^{-1}. See Fig. IV-1. The absorption spectra of both complexes show distinct shoulders on the high energy side of the absorption maximum just as the absorption spectrum of $VOSO_4 \cdot 5H_2O$ does.[31] The similarity between the visible spectra of the vanadyl amide complex ions and the spectrum of the aquo vanadyl ion indicates that the molecular orbital description of the bonding in $VO(H_2O)_5^{2+}$ given by Ballhausen and Gray [31] should be valid for the amide complexes. The unpaired electron in the $VO(DMA)_5^{2+}$ and $VO(DMF)_5^{2+}$ ions is

FIGURE IV-1. Electronic absorption spectra of VO(DMA)$_5$(ClO$_4$)$_2$ in DMA, ———; and VO(DMF)$_5$(ClO$_4$)$_2$ in DMF, ----.

expected to be in an orbital of b_1 symmetry which is essentially the vanadium $d_{x^2-y^2}$ atomic orbital. This orbital has regions of high electron density along axes which bisect the equatorial ligand-vanadium bond axes.

The EPR spectra of solutions of $VO(DMF)_5(ClO_4)_2$ and $VO(DMA)_5(ClO_4)_2$ show the eight line pattern characteristic of an isotropic hyperfine interaction between the unpaired electron and the ^{51}V nucleus of spin 7/2. See Fig. IV-2. Each spectrum can be described by the isotropic g-value, g_0, and the isotropic hyperfine splitting constant A_0^V. A_0^V and g_0 were determined from the positions of the pairs of lines with ^{51}V nuclear spin quantum numbers $+M_V$ and $-M_V$ as described by equations (III-14) and (III-15), and the results of the four calculations were averaged. The magnetic parameters for $VO(DMF)_5^{2+}$ and $VO(DMA)_5^{2+}$ were found to be temperature dependent. The temperature dependence of these parameters is shown in Fig. IV-3 and indicates that no changes in molecular structure are occurring as a function of temperature.

The peak to peak derivative linewidths of the hyperfine lines ΔB_{M_V} follow equation (III-18) and the values of α, β, γ and δ determined from a least squares analysis of the measured linewidths to equation (III-18) are given in Table IV-1. In order to extract τ_r, the rotational tumbling time from the linewidth parameters, the anisotropic magnetic parameters were determined by studying the EPR

FIGURE IV-2. EPR spectra of 5×10^{-3} $\underline{M}$ liquid solutions of $VO(DMF)_5(ClO_4)_2$ in DMF at various temperatures.

FIGURE IV-3. Temperature dependence of isotropic ^{51}V hyperfine interactions and g-values of $VO(DMA)_5(ClO_4)_2$ in DMA (☐) and $VO(DMF)_5$ $(ClO_4)_2$ in DMF (O).

TABLE IV-1

a.   EPR Linewidth Parameters of $VO(DMA)_5(ClO_4)_2$ in DMA

Temperature (K)	α(Gauss)	β(Gauss)	γ(Gauss)	δ(Gauss)
275	23.02	5.47	2.29	-.054
293	16.54	3.56	1.57	-.002
313	13.76	3.10	1.07	-.060
333	11.78	2.50	.869	-.039
353	10.80	2.24	.750	-.033

b.   EPR Linewidth Parameters of $VO(DMF)_5(ClO_4)_2$ in DMF

Temperature (K)	α(Gauss)	β(Gauss)	γ(Gauss)	δ(Gauss)
275	20.89	4.41	2.15	.003
293	16.31	3.39	1.45	-.030
313	13.30	2.51	1.08	-.025
333	11.29	1.94	.798	-.018
353	10.31	1.73	.642	-.027
373	9.469	1.47	.542	-.016
393	9.217	1.23	.436	-.011
413	9.197	1.11	.410	-.004

c.   EPR Linewidth Parameters of Bis-(diphenyldithiophosphin-ato)-oxo-vanadium(IV) in DMF

Temperature (K)	α(Gauss)	β(Gauss)	γ(Gauss)	δ(Gauss)
273	26.22	6.22	2.85	-.040
293	18.81	3.76	1.51	-.067
313	14.78	2.80	1.05	-.053
333	12.73	2.33	.799	-.048
353	11.42	1.97	.649	-.034
373	10.61	1.64	.534	-.021

spectra of the vanadyl complexes in solid solutions at low temperature. The glass spectra indicated that the complexes were of axial symmetry and allowed direct determination of the components of the g-value and hyperfine tensors along the symmetry axis of the molecule; $g_{||}$ and $A_{||}^V$ respectively. The components of the tensors along axes perpendicular to the axis of symmetry were determined from the isotropic and parallel components using equations (III-16) and (III-17). In these calculations, the values of g_o and A_o^V at 25°C were used. The values of $g_\perp$ and $A_\perp^V$ obtained in this way are subject to some error since g_o and A_o^V are temperature dependent, but this error is not larger than the estimated errors in the values of $g_\perp$ and $A_\perp^V$ measured directly from the glass spectrum. The magnetic parameters for the vanadyl perchlorates are given in Table IV-2.

The experimental values of γ and the magnetic para-meters allow one to solve equation (IV-29) for τ_r by an iterative procedure. The values of τ_r for solutions of VO(DMF)$_5$(ClO$_4$)$_2$ and VO(DMA)$_5$(ClO$_4$)$_2$ are shown as a function of temperature in Fig. IV-4. The activation energies for molecular tumbling in liquid DMF and DMA obtained from the data in Fig. IV-4 are 2.7 $\pm$ 0.1 and 2.8 $\pm$ 0.2 kcal/mole respectively. The activation energy for DMF is in excellent agreement with the value 2.8 kcal/mole predicted from the viscosity of the liquid.[82] The correlation times τ_r were required for detailed interpretation of the NMR line broad-

TABLE IV-2

Magnetic Parameters of Vanadyl Perchlorate in DMF and DMA[†]

Parameter	DMF	DMA
g_o	1.966	1.963
$g_{||}$	1.934	1.931
$g_{\perp}$	1.982	1.979
A_o^V (10^9 sec^{-1})	1.945	1.977
$A_{||}^V$ (10^9 sec^{-1})	3.343	3.405
$A_{\perp}^V$ (10^9 sec^{-1})	1.229	1.245

[†]

Estimated error $\pm$ 0.5%

FIGURE IV-4. Temperature dependence of rotational tumbling time of VO(DMA)$_5$(ClO$_4$)$_2$ in DMA (□) and VO(DMF)$_5$(ClO$_4$)$_2$ in DMF (O).

ening results as shown in a later section.

The EPR spectrum of $VO(DMA)_5(ClO_4)_2$ in liquid DMA indicates the presence of two vanadyl species at temperatures above 120°C. See Fig. IV-5. This species may be $VO(DMA)_4^{2+}$ although the vanadium hyperfine splitting in this second species is smaller than that for the $VO(DMA)_5^{2+}$ ion and it has been observed that loss of axial coordination increases the hyperfine splitting in vanadyl acetylacetonate complexes.[39] The presence of this second vanadyl species will have little effect on the interpretation of the NMR line broadening results because the abundance of this species is small compared to that of $VO(DMA)_5^{2+}$ in the temperature range used in the NMR experiments. The EPR spectrum of $VO(DMF)_5(ClO_4)_2$ in liquid DMF did not reveal the presence of any species other than $VO(DMF)_5^{2+}$ over the liquid range of DMF.

2. $VO(DMA)_5(ClO_4)_2$ in DMA

The 60 MHz NMR spectrum of DMA[83] at 25°C is shown in Fig. IV-6 and the temperature dependence of the linewidths of the solvent resonances is shown in Fig. IV-7. In the 40-90°C temperature range the resonances corresponding to the N-methyl protons change dramatically. At 40°C the rotation about the C-N bond in DMA is rapid enough to broaden the individual N-methyl peaks while at 90°C the two resonances have completely coalesced to a sharp singlet.

FIGURE IV-5.   EPR spectrum of 5×10^{-3} $\underline{M}$ liquid solution of VO(DMA)$_5$(ClO$_4$)$_2$

in DMA at 120°C.

200 Gauss

141.

FIGURE III-6. 60 MHz NMR spectrum at 25°C of DMA containing 5% by volume hexamethyldisilane as the internal reference.

FIGURE IV-7. Temperature dependence of the methyl proton linewidths of DMA. $\bullet$, C-CH$_3$ protons; $\square$, cis-N-methyl protons; O, trans-N-methyl protons; $\blacksquare$, N-methyl protons for the temperature range in which the two N-methyl proton groups show a single resonance.

This large temperature dependence of $\Delta\nu_{obs}$ results in large errors in measurements of $1/T_{2P}$ and thus data for the N-methyl resonance line broadening in this temperature range were not used for analysis. The observed values of $1/T_{2P}$ for the three methyl groups of DMA are shown in Fig. IV-8. The curves indicate that two definite limiting cases of equation (IV-25) are realized in different temperature regions: the exchanged controlled region with its negative slope, and the T_{2M} region at higher temperatures. The activation energies of the exchange controlled regions are similar for all three types of protons, but the values of T_{2M} for each group are quite different. The slight curvature of the $1/T_{2P}$ vs T^{-1} curve at low temperatures is indicative of outer sphere and/or axial ligand exchange.

The exchange reaction which dominates the line broadening is undoubtedly the equatorial ligand-bulk solvent exchange as observed in $VO(H_2O)_5(ClO_4)_2$ in water. The line broadenings were analyzed using the equation

$$1/T_{2P} = 4/(\tau_{Meq} + T_{2Meq}) + n/T_{2Mos} \qquad \text{(IV-33)}$$

where τ_{Meq} and T_{2Meq} are the lifetime and nuclear relaxation time of a group of protons on a DMA molecule coordinated to the vanadyl ion at one of the four equatorial sites, and n/T_{2Mos} represents the contributions due to outer sphere

FIGURE IV-8. Temperature dependence of $1/T_{2P}$ for the methyl protons in DMA solutions of $VO(DMA)_5(ClO_4)_2$. ●, $C-CH_3$ protons; □ , cis-N-methyl protons; O, trans-N-methyl protons; ■ , N-methyl protons for the temperature range in which the pure solvent spectrum shows a single resonance for the two N-methyl proton groups. The solid lines represent the least squares fits to the experimental points.

and/or axial ligand exchange. In this analysis E_{Meq} and E_{Mos} (see equation (IV-27))were taken to be equal, and the preexponential factors C_{Meq} and C_{Mos} were determined for all three methyl groups. The determination of these parameters and the exchange rate parameters $\Delta H^{\ddagger}$ and $\Delta S^{\ddagger}$ (see equation (IV-26))was performed by a non-linear least squares analysis [84] of the $1/T_{2P}$ data for all three types of protons simultaneously. The parameters which give the best agreement between calculated and observed values of $1/T_{2P}$ as well as calculated relaxation rates are given in Table IV-3. The criterion for the best fit is the minimization of the sum of squares of the relative residuals between experimental and predicted values. The calculated curves are shown in Fig. IV-8 together with the experimental points.

The chemical exchange rate and the enthalpy and entropy of activation are similar to those observed in the solvent exchange of the vanadyl ion in water [42,43] and in alcohols [48] which supports the assignment to equatorial-bulk solvent exchange. It should be noted that the values of T_{2Meq}^{-1} for the N-methyl protons are about four times as large as T_{2Meq}^{-1} for the C-methyl protons. The nuclear relaxation rates T_{2Meq}^{-1} are due to a dipolar and/or a hyperfine mechanism as detailed in equation (IV-28). If one assumes that the values of T_{2Meq}^{-1} for all types of methyl protons in DMA are determined completely by the

TABLE IV-3

Least Square Parameters[†] and Calculated Nuclear Relaxation and Exchange Rates[††] of

DMA Protons in Solutions Containing $VO(DMA)_5(ClO_4)_2$

Protons	E_M(kcal/mole)	C_{Meq}(sec⁻¹)	C_{Mos}(sec⁻¹)	$1/T_{2Meq}$(sec⁻¹)	n/T_{2Mos}(sec⁻¹)
C-CH₃	$3.6 \pm .3$	$3.8 \pm 1.6 \times 10^1$	2.3 ± 1.5	1.8×10^4	1.1×10^3
cis-N-CH₃	$3.6 \pm .3$	$1.9 \pm .7 \times 10^2$	1.9 ± 1.2	8.9×10^4	9.0×10^2
trans-N-CH₃	$3.6 \pm .3$	$2.0 \pm .7 \times 10^2$	1.5 ± 1.0	9.1×10^4	6.9×10^2

Equatorial exchange parameters:

$\Delta H^{\ddagger}_{eq} = 10.1 \pm .5$ kcal/mole $\Delta S^{\ddagger}_{eq} = -7.9 \pm 1.6$ e.u. $1/\tau_{Meq} = 4.73 \times 10^3$ sec⁻¹

† Errors quoted are the standard errors obtained from the least squares analysis.

†† Relaxation rates and exchange rates are calculated at 25°C from least squares parameters.

dipolar mechanism, the values of r_i calculated from $1/T_{2P}$ and τ_r determined from the EPR measurements are 2.7 Å for the C-methyl protons and 2.0 Å for the N-methyl protons. r_i represents an average distance between nuclear and electronic magnetic dipoles. The value of r_i for the C-methyl protons is reasonable since DMA is bonded to the vanadium ion by the oxygen. The small values of r_i calculated for the N-methyl protons are inconsistent with oxygen coordination to the vanadyl ion and the origin of T_{2Meq}^{-1} for the N-methyl protons cannot be ascribed to dipolar interactions.

The alternative interpretation, that the N-methyl protons are relaxed only by hyperfine interactions, requires some justification since one might expect to observe significant contact shifts [79] and frequency-dependent linewidths [71] in this case. It must be ascertained if the magnitude of the hyperfine interaction is large enough to produce the observed line broadening, but too small to give observable contact shifts and frequency dependent widths. In order to determine the magnitudes of A_o^V required to give the observed values of $1/T_{2P}$, one must estimate T_{1e} using equation (IV-31). In this expression $1/T_{1e}$ is a function of M_V and one calculates $1/T_{1e}$ for the average of the possible M_V values. At 25°C, the average value of T_{1e} is 6.5×10^{-8} sec in a 14.1 kG field. With this value for T_{1e}, and the observed $1/T_{2P}$

values for the N-methyl protons, one obtains a value of 2.4×10^6 sec^{-1} for the hyperfine splitting constant A_o^V. The corresponding contact shift of the NMR resonance $\Delta\omega_M$ can be calculated from equation (IV-32) with the result 590 Hz at 25°C in a 60 MHz NMR experiment. Comparison of this $\Delta\omega_M$ value with the magnitudes of T_{2Meq} and τ_{Meq} under these conditions confirms the insignificance of the $\Delta\omega_M^2$ terms in equation (IV-20).

The most favorable conditions for the observation of a shift in the NMR resonance will occur at high temperature where T_{2Meq} dominates the relaxation. Under these conditions, the observed shift, $\Delta\omega_{obs}$, will be given by

$$\Delta\omega_{obs} = \frac{4[M]}{[S]} \Delta\omega_M \ . \qquad\qquad \text{(IV-34)}$$

For a sample containing 0.020 molal $VO(DMA)_5(ClO_4)_2$ in DMA at 130°C, the width of the N-methyl resonance is 41 ± 4 Hz, while $\Delta\omega_{obs}$ would be 3.0 Hz since $\Delta\omega_M = 439$ Hz at 130°C. This shift in the resonance frequency is clearly within the experimental error in determining the centre of a peak 40 Hz wide.

In order to pursue the search for an observable shift, 100 MHz measurements were performed. One would expect a shift of 5.0 Hz for the N-methyl resonances in a 0.020 molal $VO(DMA)_5(ClO_4)_2$ solution at 130°C. The observed shifts were 4 ± 2 Hz for the N-methyl resonance and 2 ± 2 Hz for the C-methyl resonance. These observations

are consistent with the hypothesis that the relaxation of
the N-methyl protons is governed by a hyperfine mechanism
while the C-methyl protons relax via the dipolar mechanism.
They do not preclude the possibility that both mechanisms
contribute to the relaxation of all protons, with the major
contribution for C-methyl protons being dipolar, and the
major contribution for N-methyl protons being hyperfine
interactions.

A further point which must be considered, is the
frequency dependence of the N-methyl proton resonance line-
widths. Since $1/T_{1e}$ contains terms which depend on the
electronic Larmor frequency, ω_o, (see equation (IV-31)), a
difference in the widths of the N-methyl proton resonances
at 60 MHz and 100 MHz is expected if the hyperfine con-
tribution to $1/T_{2Meq}$ is dominant. At 130°C, the values of
T_{1e}, for $VO(DMA)_5^{2+}$ in DMA calculated using equation (IV-
31) are 6.5×10^{-8} and 7.1×10^{-8} sec at 60 MHz and 100
MHz respectively. One would therefore expect the line-
widths at 100 MHz to be 10% broader than those at 60 MHz.
Since our estimated errors in the linewidth measurements
are at least as large as this, the frequency dependence
of the linewidths was not observed.

The least squares analysis of the $VO(DMA)_5(ClO_4)_2$
line broadening data indicated significant outer sphere
contributions at room temperature and below (see Fig. IV-
8 and Table IV-3). On the basis of a simple model developed

by Luz and Meiboom [85], the average distance, d_o, of clos-
est approach of the solvent molecules, beyond the first
coordination sphere, can be estimated from

$$\frac{1}{T_{2Mos}} = \frac{4\pi}{45} \cdot \frac{\rho N [M]}{1000} \cdot \frac{S(S+1)\gamma_I^2 g_o^2 \beta_o^2}{d_o^3} \cdot 7\tau_r \quad (IV-35)$$

where ρ is the density of the solution, N is Avogadro's
number and the other symbols have been defined earlier. The
values for d_o obtained from the values of n/T_{2Mos} given in
Table IV-3, are 5.4 Å for the C-methyl protons, 5.8 Å for
the cis-N-methyl protons and 6.3 Å for the trans-N-methyl
protons. These values seem to be smaller than one would
expect on the basis of molecular models, but some of the
broadening ascribed to outer sphere effects may be due to
exchange of solvent molecules with DMA molecules coordin-
ated at the axial position of the vanadyl. If the axial-
solvent exchange rate were rapid, the contribution to the
linewidth from axial exchange would be T_{2Max}^{-1}, and it
would have a temperature dependence which would be indistin-
guishable from the outer sphere broadening. This problem
will be discussed further after an analysis of the line
broadening of DMF by $VO(DMF)_5(ClO_4)_2$ is presented.

3. $\underline{VO(DMF)_5(ClO_4)_2 \text{ in DMF}}$

The 60 MHz NMR spectrum of DMF [83,86] at 25°C is shown

in Figure IV-9. The linewidths of the resonances as a function of temperature are given in Fig. IV-10. In the temperature range 100-135°C, internal rotation about the C-N bond has an appreciable affect on the widths and shape of the N-methyl resonances of the solvent. Therefore $1/T_{2P}$ data in this region was not used in the analysis. The experimental paramagnetic broadenings of the formyl proton and methyl proton resonances are plotted against T^{-1} in Fig. IV-11. The magnitude and temperature dependence of the line broadening of the methyl resonances is similar to that observed for the N-methyl protons in DMA (see Fig. IV-8), and, at high temperatures, the methyl resonances are broader than the formyl resonance just as the N-methyl resonances of DMA are broader than the C-methyl resonance. The T_{2M} (high temperature) region in DMF is less well defined than the corresponding region in DMA, but the outer sphere effects in DMF are very clearly defined.

In contrast to the line broadening of the methyl resonances in DMF and those in DMA, the temperature dependence of the broadening of the formyl resonance in DMF is much less pronounced in the region where chemical exchange effects are dominant. Since all bonds in DMF are expected to remain intact when it coordinates with the vanadyl ion, the slopes of the $\log(1/T_{2P})$ vs T^{-1} lines in the exchange controlled region should be the same

FIGURE IV-9. 60 MHz NMR spectrum at 25°C of DMF containing 5% by volume cyclopentane as the internal reference.

153.

FIGURE IV-10. Temperature dependence of the proton linewidths of DMF. ●, formyl proton; □ , cis-N-methyl protons; O, trans-N-methyl protons; ■ , N-methyl protons for the temperature range in which the two N-methyl proton groups show a single resonance.

FIGURE IV-11. Temperature dependence of $1/T_{2P}$ for the
formyl and methyl protons in DMF solutions
of $VO(DMF)_5(ClO_4)_2$. ●, formyl proton;
□ , cis-N-methyl protons; O, trans-N-methyl
protons; ◼ , N-methyl protons for the
temperature range in which the pure solvent
spectrum shows a single resonance for the
two N-methyl groups. The solid lines represent
the least squares fits to the experimental
points.

for the formyl resonance and both methyl resonances. Clearly the formyl broadening indicates the presence of an exchange reaction which does not appear in the methyl proton line broadening.

Careful examination of the formyl $1/T_{2P}$ data indicates that a single straight line does not give a good fit of the exchange-controlled region. Indeed, the results are better described by two linear portions with a levelling off between them near $10^3/T = 3.4 \, K^{-1}$. This observation suggests that two exchange processes, with different rates and temperature dependence, are controlling the formyl proton line broadening in this region. One postulates that the broadening of the formyl proton in the low temperature part of the exchange-controlled region is due to exchange of a DMF molecule coordinated at the axial position, and that the rate of this process is different from equatorial exchange and distinguishable from outer sphere broadening. This hypothesis requires that the broadening of the methyl resonances by axial exchange is insignificant, while providing an adequate explanation of the formyl proton broadening.

The unpaired electron in vanadyl complexes is localized in the vanadium $3d_{x^2-y^2}$ atomic orbital [25,31], and the unpaired electron density at the protons in an axially coordinated DMF molecule is expected to be very small. One expects, therefore, that the relaxation times, T_{2Max},

of the protons in the axially coordinated molecule will be determined by dipolar interactions between the electron and nuclear moments, not by hyperfine interactions. The dipolar relaxation time for the formyl proton in an axially coordinated DMF molecule is expected to be about 50 times shorter than that of the methyl protons because the interaction distance for the methyl protons is about twice as large as that for the formyl proton and the dipolar line-width varies as the sixth power of the interaction distance (see equation (IV-28)). One expects, therefore, that $(T_{2Max})^{-1}$ for the methyl protons is small, but $(T_{2Max})^{-1}$ for the formyl proton is comparable in magnitude to τ_{Meq}^{-1} in the low temperature portion of the exchange-controlled region. Since the line broadenings of the methyl resonances in the exchange-controlled region show no significant deviation from a single straight line, it was assumed that $(T_{2Max})^{-1}$ for the methyl protons is negligible compared to either $(\tau_{Meq})^{-1}$ or T_{2Meq}^{-1}.

The line broadening data was analyzed by a least squares method in terms of the model postulated above which describes the formyl proton widths as arising from the exchange between bulk solvent and three distinct coordination sites (axial, equatorial and outer sphere), and the methyl proton broadening arising from exchange between solvent and two distinct sites (equatorial and outer sphere). The $1/T_{2P}$ data for both methyl resonances

was analyzed first in order to determine $\Delta H^{\ddagger}_{eq}$, $\Delta S^{\ddagger}_{eq}$, E_M and the preexponential factors C_{Meq} and C_{Mos} for each methyl group. Next, the formyl line broadening data was fit holding $\Delta H^{\ddagger}_{eq}$, $\Delta S^{\ddagger}_{eq}$ and E_M constant at the values determined from the analysis of the methyl proton data, and the parameters $\Delta H^{\ddagger}_{ax}$, $\Delta S^{\ddagger}_{ax}$, C_{Max}, C_{Meq} and C_{Mos} for the formyl protons were varied until convergence of the least squares procedure was achieved. The solid curves in Fig. IV-11 are calculated using the parameters obtained from these least squares analyses. The parameters and calculated relaxation rates are given in Table IV-4.

The relaxation rates for the methyl protons in DMF at high temperatures are considerably higher than that for the formyl proton. If one assumes that T_{2M}^{-1} for all types of protons is dominated by dipolar interactions, interaction distances of 2.6, 3.2 and 2.0 Å for equatorial formyl protons, axial formyl protons and equatorial methyl protons respectively are obtained. Arguments analogous to those given in the analysis of T_{2Meq} for the N-methyl protons in DMA lead to the conclusion that the methyl protons in DMF are relaxed predominantly by hyperfine interactions modulated by the relaxation of the unpaired electron of the vanadyl complex, while dipolar interactions modulated by molecular tumbling account satisfactorily for the magnitudes of $(T_{2Meq})^{-1}$ and $(T_{2Max})^{-1}$ for the formyl protons.

TABLE IV-4

Least Squares Parameters[†] and Calculated Nuclear Relaxation and Exchange Rates[††] of DMF Protons in Solutions Containing $VO(DMF)_5(ClO_4)_2$

Protons	$C_M (sec^{-1})$	$C_{Mos} (sec^{-1})$	$E_M (kcal/mole)$	$1/T_{2M} (sec^{-1})$	$n/T_{2Mos} (sec^{-1})$
axial C-H	$3.5 \pm .2 \times 10^1$	–	$3.0 \pm .2$	5.8×10^3	–
equatorial C-H	$1.1 \pm .1 \times 10^2$	$8.7 \pm .3$	$3.0 \pm .2$	1.9×10^4	1.5×10^3
equatorial cis N-CH₃	$4.3 \pm .9 \times 10^2$	7.9 ± 2.8	$3.0 \pm .2$	7.2×10^4	1.3×10^3
equatorial trans N-CH₃	$4.6 \pm 1.0 \times 10^2$	6.5 ± 2.3	$3.0 \pm .2$	7.8×10^4	1.1×10^3

Equatorial and axial exchange parameters:

$$\Delta H^{\ddagger}_{eq} = 13.1 \pm .6 \text{ kcal/mole} \qquad \Delta S^{\ddagger}_{eq} = -4.1 \pm 1.8 \text{ e.u.} \qquad 1/\tau_{Meq} = 2.0 \times 10^2 \text{ sec}^{-1}$$

$$\Delta H^{\ddagger}_{ax} = 15.3 \pm 2.5 \text{ kcal/mole} \qquad \Delta S^{\ddagger}_{ax} = 13.9 \pm 9.0 \text{ e.u.} \qquad 1/\tau_{Max} = 4.6 \times 10^4 \text{ sec}^{-1}$$

† Errors quoted are the standard errors given by the least squares analysis.

†† Relaxation rates and exchange rates are calculated at 25°C from least squares parameters.

The interaction distance between the unpaired electron and the formyl proton in axial coordination is significantly larger than the interaction distance for the formyl proton in equatorial coordination. This is in agreement with the weaker bond between the axial ligand and the vanadium atom, and is supported by crystallographic studies of other 6-coordinate vanadyl complexes.[6]

The interaction distance between the unpaired electron and the methyl protons of an axially-coordinated DMF molecule will be at least 5 Å if the interaction distance for the formyl proton in axial coordination is 3.2 Å. The relaxation rate $(T_{2Max})^{-1}$ for methyl protons is therefore insignificant (410 sec^{-1} at 25°C) compared with $(T_{2Meq})^{-1}$ or $(\tau_{Meq})^{-1}$. As indicated above, no hyperfine contribution to the methyl $(T_{2Max})^{-1}$ is expected since the unpaired electron density is very small at the axial methyl protons. The neglect of broadening of methyl resonance by axial exchange was therefore justified.

The hyperfine interaction for the equatorial methyl protons must be 2.0×10^6 sec^{-1} if $(T_{2Meq})^{-1}$ is determined only by hyperfine interactions. This interaction is slightly smaller than the value determined for the N-methyl protons of DMA, and arguments, analogous to those presented previously for the DMA N-methyl data, can be given to account for the unobservability of frequency shifts or frequency-dependent line broadening.

The outer sphere interaction distances for the pro-
tons in DMF were calculated using Luz and Meiboom's theory
[85] and the values of n/T_{2Mos} given in Table IV-4. The
distances are 5.2, 5.4 and 5.8 $\overset{o}{A}$ respectively for the
formyl, cis-methyl and trans-methyl protons. These values
are smaller than those determined above for DMA molecules
in the second coordination sphere of $VO(DMA)_5^{2+}$, and the
effects of axial exchange have been included explicitly
here. It would appear that the outer sphere interaction
distances obtained from n/T_{2Mos} are smaller than one would
expect on the basis of molecular models and that this is
due to the naïvity of the model for outer sphere inter-
actions, not the neglect of the axial exchange process.
The observation that the n/T_{2Mos} values are approximately
equal for all three types of protons suggests the molecular
arrangement in the second coordination sphere is not highly
structured. Then orientations of the amides may be such
that on the average the methyl protons are nearly as close
as the formyl proton to the vanadyl ion. Another possib-
ility is that outer sphere relaxation results from a hyper-
fine interaction which may be more effective for the methyl
protons than the formyl protons.

4.   Bis-(o-phenanthroline)-oxo-vanadium(IV) Perchlorate
      in DMF

The results presented in the previous section indicate

that the effect of axial exchange on the solvent line
broadening could be separated from the effects of equator-
ial exchange in certain circumstances. A simple chemical
method of accomplishing this separation is to choose a
system where the equatorial sites are blocked and only
the axial site can accept the solvent molecules. Further-
more, the species should have a formal charge of +2 for
a meaningful comparison of the results with the vanadyl
ion studies in sections 2 and 3. The neutral bidentate
ligand, o-phenanthroline, is believed to coordinate at
the equatorial positions of the vanadyl ion and the re-
sulting complex has a +2 charge.[50] Solvent line broadening
studies of DMF solutions of the bis-(o-phenanthroline)-oxo-
vanadium(IV) complex were performed and the results are
shown in Fig. IV-12. The $1/T_{2P}$ data indicate an exchange
controlled region above 60°C, but the EPR spectrum at the
same temperature, shown in Fig. IV-13, indicates the
presence of two species in solution. Presumably, the
o-phenanthroline ligand is being replaced by DMF at the
equatorial position in the first coordination sphere
above 60°C. The exchange of these DMF molecules can then
contribute to $1/T_{2P}$. Calculations showed that the $1/T_{2P}$
values given in Fig. III-12 are compatible with 10% con-
version of the bis-(o-phenanthroline)-oxo-vanadium(IV)
to $VO(DMF)_5^{2+}$. The lower values of $1/T_{2P}$ observed in the
outer sphere T_{2M} region for bis-(o-phenanthroline)-oxo-

FIGURE IV-12. Temperature dependence of $1/T_{2P}$ for the formyl and methyl protons in DMF solutions of bis-(o-phenanthroline)-oxo-vanadium(IV) perchlorate. ●, formyl proton; □, cis-N-methyl protons; ○, trans-N-methyl protons.

162.

163.

FIGURE IV-13.   EPR spectra of 10^{-2} $\underline{M}$ liquid solutions of
bis-(o-phenanthroline)-oxo-vanadium(IV)
perchlorate in DMF at 60°C and 120°C. The
stick spectra for the two vanadyl species at
120°C are given at the bottom of the figure.

vanadium(IV) in DMF compared to $VO(DMF)_5^{2+}$ in DMF (see Fig. IV-11) reflect the bulkiness of the o-phenanthroline ligands; i.e., the outer sphere interaction distances are considerably larger for bis-(o-phenanthroline)-oxo-vanadium(IV) than for $VO(DMF)_5^{2+}$.

5. $VO(acac)_2$ in DMF

The $VO(acac)_2$ complex is another system in which only one position is available for coordination by the solvent. In contrast to the systems already described $VO(acac)_2$ is neutral and one expects the rates of exchange of electron donating solvent molecules from the axial position to be faster than in $VO(DMF)_5(ClO_4)_2$.[47] The NMR solvent line broadening of DMF caused by $VO(acac)_2$ is shown in Fig. IV-14 and shows no indication of an exchange controlled region. Apparently, the exchange is too fast to control the $1/T_{2P}$ values. The $1/T_{2P}$ values are described by the equation $1/T_{2P} = 4.5 \exp(1,800/T)$ which is the equation of the solid line in Fig. IV-14.

6.   Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) in DMF, DMA and DEF.

The NMR line broadening of DMF, DMA and DEF by the vanadyl dithiophosphinate was investigated to gain more information about the nature of the vanadyl species in solutions containing the dithiophosphinates and Lewis

FIGURE IV-14. Temperature dependence of $1/T_{2P}$ for the formyl protons in DMF solutions of $VO(acac)_2$. The solid line represents the least squares fit to the experimental points.

bases. Complete replacement of the dithiophosphinate groups in the first coordination sphere by the solvent molecules DMF or DMA would result in the species $VO(DMF)_5^{2+}$ and $VO(DMA)_5^{2+}$. The line broadening for the perchlorates of these ions have already been presented in section 2 and 3.

The $1/T_{2P}$ data for DMA solutions of the phenyl complex is shown in Fig. IV-15. The plot of this data is almost superimposable on that for $VO(DMA)_5(ClO_4)_2$ in DMA shown in Fig. IV-8 except for the high temperature region. The equivalent line broadening results for the two systems below 100°C indicate that the diphenyldithiophosphinate chelates are completely displaced from the first coordination sphere of the vanadyl ion. At higher temperatures, the diphenyldithiophosphinate presumably becomes coordinated to the vanadyl ion and this effectively reduces the line broadening in the T_{2M} region. This is supported by the EPR spectrum of the DMA solution of the phenyl complex at 145°C which shows patterns of low intensity that arise from coupling of the electron spin with other nuclei, namely ^{31}P of the diphenyldithiophosphinate. The least squares fit of the dithiophosphinate line broadening data to the model proposed in section 2 for the vanadyl perchlorates in DMA gave the parameters given in Table IV-5a. The least squares curves are shown in Fig. IV-15 together with the experimental data. A comparison of the parameters

167.

FIGURE IV-15. Temperature dependence of $1/T_{2P}$ for the methyl protons in DMA solutions of bis-(diphenyldithio-phosphinato)-oxo-vanadium(IV). ●, C-CH$_3$ protons; □, cis-N-methyl protons; O, trans-N-methyl protons; ■, N-methyl protons for the temperature range in which the pure solvent spectrum shows a single resonance line for the two N-methyl proton groups. The solid lines represent the least squares fits to the experimental points.

TABLE IV-5

a. Least Squares Parameters† and Calculated Nuclear Relaxation and Exchange Rates†† of DMA Protons in Solutions Containing Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)

Protons	E_M(kcal/mole)	C_{Meq}(sec^{-1})	C_{Mos}(sec^{-1})	$1/T_{2Meq}$(sec^{-1})	n/T_{2Mos}(sec^{-1})
C-CH$_3$	4.7 ± .3	8.3 ± 3.5	4.5 ± 3.0 x 10^{-1}	2.2 x 10^4	1.2 x 10^3
cis-N-CH$_3$	4.7 ± .3	3.8 ± 1.5 x 10^1	4.1 ± 2.7 x 10^{-1}	1.0 x 10^5	1.1 x 10^3
trans-N-CH$_3$	4.7 ± .3	3.9 ± 1.5 x 10^1	3.3 ± 2.2 x 10^{-1}	1.0 x 10^5	8.6 x 10^2

Equatorial exchange parameters:

$\Delta H^{\ddagger}_{eq}$ = 11.7 ± .9 kcal/mole $\Delta S^{\ddagger}_{eq}$ = -2.5 ± 3.2 e.u. $1/\tau_{Meq}$ = 4.7 x 10^3 sec^{-1}

b. Least Squares Parameters† and Calculated Nuclear Relaxation and Exchange Rates†† of DMA Protons in Solutions Containing Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV) for Data at Temperatures Below 10^3/T = 2.4 K^{-1}

Protons	E_M(kcal/mole)	C_{Meq}(sec^{-1})	C_{Mos}(sec^{-1})	$1/T_{2Meq}$(sec^{-1})	n/T_{2Mos}(sec^{-1})
C-CH$_3$	3.1 ± .4	7.1 ± 3.6 x 10^1	9.6 ± 7.0	1.4 x 10^4	1.9 x 10^3
cis-N-CH$_3$	3.1 ± .4	3.0 ± 1.4 x 10^2	8.8 ± 6.5	5.9 x 10^4	1.7 x 10^3
trans-N-CH$_3$	3.1 ± .4	3.1 ± 1.4 x 10^2	7.4 ± 5.4	6.0 x 10^4	1.4 x 10^3

Equatorial exchange parameters

$\Delta H^{\ddagger}_{eq}$ = 13.5 ± .9 kcal/mole $\Delta S^{\ddagger}_{eq}$ = 3.7 ± 3.2 e.u. $1/\tau_{Meq}$ = 4.7 x 10^3 sec^{-1}

† Errors quoted are the standard errors obtained from the least squares analysis.

†† Relaxation rates and exchange rates are calculated at 25°C from least squares parameters.

in Table IV-5a with the corresponding parameters for the

$VO(DMA)_5(ClO_4)_2$ system given in Table IV-3, indicates that

the parameters for the two systems are equal if one con-

siders the error limits for the parameters to be twice the

standard errors. The larger value of E_M for the dithio-

phosphinate system compared to the perchlorate system

reflects the difference between the systems in the high

temperature T_{2M} region. If one considers the $1/T_{2P}$ data

in Fig. IV-15 for temperatures below $10^3/T = 2.4$ K^{-1} only,

then the value of E_M is decreased from 4.7 to 3.1 kcal/

mole. The parameters determined from the least squares

analysis for the data below $10^3/T = 2.4$ K^{-1} are shown in

Table IV-5b and are in good agreement with the parameters

for $VO(DMA)_5(ClO_4)_2$ in Table IV-3.

Fig. IV-16 shows the $1/T_{2P}$ data for DMF solutions

containing bis-(diphenyldithiophosphinato)-oxo-vanadium

(IV). The measured line broadenings above 100°C were

found to vary with the length of time a sample remained

at these elevated temperatures, and therefore are not

considered in the following analysis. A comparison of the

data in Fig. IV-16 with the corresponding data for

$VO(DMF)_5(ClO_4)_2$ in DMF shown in Fig. IV-11 shows that the

$1/T_{2P}$ values, for both the formyl and N-methyl protons,

at a given temperature in the exchange controlled region

are significantly larger for the phenyl complex than for

$VO(DMF)_5(ClO_4)_2$. This result indicates that the diphenyl-

FIGURE IV-16. Temperature dependence of $1/T_{2P}$ for the formyl and methyl protons in DMF solutions of bis-(diphenyldithiophosphinato)-oxo-vanadium(IV). ●, formyl proton; ☐, cis-N-methyl protons; O, trans-N-methyl protons. The solid lines represent the least squares fits to the experimental points.

dithiophosphinate ligand is not completely displaced from
the first coordination sphere of the vanadyl ion when the
phenyl complex is dissolved in DMF. The EPR spectrum of
the phenyl complex in DMF shows broader lines than the EPR
spectrum of $VO(DMF)_5^{2+}$ at a given temperature as can be
seen from a comparison of the linewidth parameters in Table
IV-1. This suggests that the complex formed in DMF solu-
tions containing the phenyl complex has a larger hydrodyn-
amic radius than $VO(DMF)_5^{2+}$. Also, the EPR spectrum of the
phenyl complex in DMF shows no hyperfine coupling with the
phosphorus nucleus which suggests the diphenyldithiophos-
phinate coordinates as a monodentate ligand. Furthermore,
the conductance of the DMF solution is linear in the con-
centration of the phenyl complex which indicates that
there exists a dissociated species in solution. These
results require that the predominant vanadyl species in a
DMF solution of the phenyl complex at room temperature
has one equatorial coordination site occupied by a mono-
dentate diphenyldithiophosphinate and the remaining coor-
dination positions occupied by DMF. The methyl proton
broadening data was then fit to this model and the para-
meters $\Delta H^{\ddagger}_{eq}$, $\Delta S^{\ddagger}_{eq}$, E_M and the prexponential factor C_{Mos}
were determined for each of the methyl groups. Values
of C_{Meq} were not determined since the T_{2M} region is not
defined by the data for the methyl protons in Fig. IV-16.
Next the formyl proton data was fit holding $\Delta H^{\ddagger}_{eq}$, $\Delta S^{\ddagger}_{eq}$

and E_M constant at the values obtained from the methyl data and varying the axial parameters as was done for the case of $VO(DMF)_5(ClO_4)_2$. The parameters and calculated relaxation rates are shown in Table IV-6. A comparison of the parameters in Table IV-6 with those for $VO(DMF)_5(ClO_4)_2$ in Table IV-4 indicates that the rate of equatorial exchange is five times faster in the dithio-phosphinate system.

The line broadening in DEF by the phenyl complex was investigated in order to determine whether the formyl proton broadening in DMF was typical of other formamides. Fig. IV-17 shows the $1/T_{2P}$ results for the formyl proton of DEF solutions of bis-(diphenyldithiophosphinato)-oxo-vanadium(IV). The temperature dependence of the line-width of the formyl proton resonance of the pure solvent DEF is shown in Fig. IV-18. The $1/T_{2P}$ data shown in Fig. IV-17 has a temperature dependence similar to that for the formyl proton of DMF solutions of bis-(diphenyl-dithiophosphinato)-oxo-vanadium(IV) shown in Fig. IV-11. In the exchange controlled region, the $1/T_{2P}$ values at a given temperature are equal within experimental error for the two systems. However, $1/T_{2P}$ values in both the inner sphere and outer sphere T_{2M} region are larger in the DEF solvent. One would expect the $1/T_{2Mos}$ values in DEF to be smaller than in DMF since the vanadyl complex in DMF which has one monodentate diphenyldithiophosphinate ligand

TABLE IV-6

Least Squares Parameters[†] and Calculated Nuclear Relaxation and Exchange Rates[††] of DMF Protons in Solutions Containing Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)

Protons	C_M (sec^{-1})	C_{Mos} (sec^{-1})	E_M (kcal/mole)	$1/T_{2M}$ (sec^{-1})	n/T_{2Mos} (sec^{-1})
axial C-H	$6.7 \pm .6$	-	$3.9 \pm .2$	5.4×10^3	-
equatorial C-H	$1.4 \pm .1 \times 10^1$	$1.3 \pm .1$	$3.9 \pm .2$	1.1×10^4	1.1×10^3
equatorial cis N-CH$_3$	-	$1.3 \pm .6$	$3.9 \pm .2$	-	1.1×10^3
equatorial trans N-CH$_3$	-	$1.1 \pm .5$	$3.9 \pm .2$	-	9.0×10^2

Equatorial and axial exchange parameters:

$\Delta H^{\ddagger}_{eq} = 10.0 \pm .4$ kcal/mole $\Delta S^{\ddagger}_{eq} = -11.3 \pm 1.1$ e.u. $1/\tau_{Meq} = 9.5 \times 10^2$ sec^{-1}

$\Delta H^{\ddagger}_{ax} = 10.8 \pm 1.6$ kcal/mole $\Delta S^{\ddagger}_{ax} = -1.7 \pm 5.9$ e.u. $1/\tau_{Max} = 3.4 \times 10^4$ sec^{-1}

†   Errors quoted are the standard errors given by the least squares analysis.

†† Relaxation rates and exchange rates are calculated at 25°C from least squares parameters.

FIGURE IV-17. Temperature dependence of $1/T_{2P}$ for the formyl proton in DEF solutions

FIGURE IV-18. Temperature dependence of the formyl proton linewidths of DEF.

and four DMF ligands coordinated to the vanadyl ion is
expected to have a smaller effective radius than the
corresponding vanadyl complex in which the DMF ligands are
replaced by DEF. On the other hand, the viscosity of DEF
may be large enough to increase τ_r sufficiently to yield
the higher values of $1/T_{2Mos}$ in DEF than in DMF. This
would also account for the higher $1/T_{2M}$ values observed
in DEF compared to DMF. An analysis of the DEF system
in terms of axial and equatorial exchange is not feasible
since the component of the formyl proton line broadening
due to equatorial exchange is not known and cannot be
determined from the CH_3 or CH_2 proton resonances since
linewidth measurements for these resonances are hampered
by the spin-spin splitting of these resonances and were
therefore not undertaken.

E.   Discussion

1.   Vanadyl Perchlorates

The ^{17}O line broadening by $VO(H_2O)_5(ClO_4)_2$ at low
temperatures has been attributed to the exchange of water
molecules coordinated to the vanadyl ion with lifetimes
which are much shorter than those of the water molecules
coordinated at equatorial sites in the first coordination
sphere of the ion.[42,43] Either the exchange of an axially-
coordinated water molecule or molecules in the outer sol-
vation sphere could account for the experimental observa-

tions. Line broadening by vanadyl complexes in other sol-

vents [44-48] gives similar results with no resolution of

the two processes which can conceivably explain the slow

exchange region broadening. The $VO(DMF)_5(ClO_4)_2$ line

broadening data presented in this thesis constitute an

example where the outer sphere effects can be separated

from line broadening due to axial exchange. The large

difference in the dipolar relaxation times for the formyl

and methyl protons in axially-coordinated DMF molecules

makes the formyl proton linewidth sensitive to axial ex-

change while the methyl linewidths are not appreciably

affected. In an attempt to substantiate the assertions

in the $VO(DMF)_5(ClO_4)_2$ system, one can study the line

broadening of the DMF resonances by bis-(o-phenanthroline)-

oxo-vanadium(IV) perchlorate, a molecule in which the

equatorial coordination sites of the vanadyl ion are

occupied by the bidentate o-phenanthroline ligands.[50]

The NMR data shown in Fig. IV-14 indicated an exchange-

controlled region above 60°C, but EPR studies indicated

the presence of a second vanadyl species at this tempera-

ture. See Fig. IV-15. Presumably, the o-phenanthroline

ligands are not bound strongly and may be displaced by

DMF solvent molecules and the equatorially-coordinated

DMF molecules account for the exchange-controlled line

broadening.

The uncharged vanadyl acetylacetonate complex and

its effects on the linewidths of the proton resonances of DMF were investigated also. In this case, no exchange-controlled region was observed. See Fig. IV-16. The rate of exchange between bulk solvent and axially-coordinated DMF molecules must be too fast to control the line broadening. The vanadium-DMF bond is probably weaker in the vanadyl acetonate-DMF adduct than the axial vanadium-DMF bond in $VO(DMF)_5^{2+}$ because the acetylacetonate is uncharged, and this would result in a more rapid ligand exchange. Wüthrich and Connick [47] have shown that the equatorial ligand exchange rate in uncharged complexes is approximately 10^3 times faster than the exchange in charged complexes. One might expect therefore the rate of axial exchange in the acetylacetonate to be of the order of 10^7 sec^{-1}, since the axial exchange rate in $VO(DMF_5)^{2+}$ is $10^4\ sec^{-1}$. EPR studies [39] of the axial exchange rate in amine adducts of vanadyl acetylacetonate indicate that a rate of $10^7\ sec^{-1}$ is eminently reasonable.

The axial exchange rate in $VO(DMA)_5^{2+}$ is probably too fast, over the accessible temperature range, to contribute to the line broadening. The solvent freezes before axial exchange becomes slow enough to control the linewidth of the C-methyl resonance. The rate of equatorial exchange in $VO(DMA)_5^{2+}$ is 25 times faster than in $VO(DMF)_5^{2+}$ at 25°C, and has a lower enthalpy of activation. This reflects a weaker vanadium-ligand bond in the DMA

complex ion as one might expect on steric grounds. Steric

factors would also increase the interaction distances

between the unpaired electron and the protons of an axially

coordinated DMA molecule. This would decrease $(T_{2Max})^{-1}$

and lower the axial contribution to the linewidths as

compared to the VO(DMF)$_5^{2+}$ case.

The plots of log $(1/T_{2P})$ vs T^{-1} for all three types of

protons in DMA in Fig. IV-8 show a slight curvature at low

temperature. It was assumed that this curvature was due

to outer sphere effects since an axial exchange contribu-

tion, at least on the basis of the DMF results, should have

produced a broadening of the C-methyl resonances while the

N-methyl proton widths should have remained unaffected.

The distances of closest approach by outer sphere mole-

cules in DMF and DMA studies are comparable. However, in

both cases, the N-methyl interaction distances for outer

sphere molecules appear to be smaller than molecular models

would predict. This may result from orientation of the

molecules in the second solvation sphere in positions

where the N-methyl protons are close to the paramagnetic

center. Another explanation of the small outer sphere

interaction distances invokes small hyperfine interactions

to molecules in the second coordination sphere. Such a

mechanism has been postulated for other systems [47,89], but

the cause of the small outer sphere distances in the pre-

sent case is unclear.

The coordination of oxygen donors to metals is generally via two modes: linear coordination and angular coordination. In linear coordination the metal occupies a position between the two lone pairs of the oxygen atom, while in angular coordination the metal bonds to one of the lone pairs. Line broadening studies with $Co(DMF)_6$ $(ClO_4)_2$ [88] indicate that the Co-O-C bond is bent, signifying angular coordination. The crystal structure of $Fe(DMF)_6^{3+}$ also supports the angular model.[19] Coordination of the planar DMF molecules in the xy plane results in steric crowding and orientations parallel to the xz and yz planes or slightly pitched from these planes is likely. Two possible coordination arrangements are illustrated in Fig. IV-19. Structure I is favored because of less steric hindrance with the axial solvent molecule. Furthermore, tilting of the DMF molecule would make the two CH_3 groups more equivalent with respect to the $d_{x^2-y^2}$ orbital. Structure I also keeps the C-H proton well removed from regions of high $d_{x^2-y^2}$ probability which supports the observation of only dipolar coupling to the C-H proton. On the other hand, scalar coupling through space may be less favorable than scalar coupling through the π bonding systems of DMF and DMA. There are many sterically reasonable conformations of the complex ions in which the overlap between the vanadium $3d_{x^2-y^2}$ atomic orbital and the amide π-molecular orbitals is favorable.

FIGURE IV-19. Stereochemistry of DMF coordinated to the vanadyl ion.
The x' and y' axes are rotated 45° about the z axis of the xyz coordinate
system defined in Fig. I-1.

Since the vanadium $3d_{x^2-y^2}$ orbital energy [31] is similar to
the energies of the highest occupied π-orbital of the
amide ligand [89], the molecular orbital containing the un-
paired electron should have some of the character of this
filled π-orbital of the free amide ligands. The highest
occupied π-orbital of the amide moiety has large ampli-
tudes at the nitrogen and oxygen atoms, but has smaller
amplitude at the carbon atom.[89] The unpaired electron
density at the nitrogen atom should be greater than that
at the carbon atom, and hyperfine interactions with the N-
methyl protons should therefore be more significant than
those with formyl or C-methyl protons.

2.   Vanadyl Dithiophosphinates

The EPR, infrared and conductance measurements re-
ported in Chapter III supported the existence of ionic
species when vanadyl dithiophosphinates were dissolved in
Lewis bases. The same types of experiments in mixed sol-
vents suggested equilibria between species with various
numbers of coordination positions of the vanadyl ion
occupied by Lewis base molecules. The NMR line broadening
data presented in this Chapter confirm that DMA completely
displaces the diphenyldithiophosphinate groups from the
first coordination sphere of the vanadyl ion when bis-(
diphenyldithiophosphinato)-oxo-vanadium(IV) is dissolved
in DMA at room temperature. At higher temperatures the

diphenyldithiophosphinate again coordinates to the vanadyl ion which parallels the observations in Chapter III for the vanadyl dithiophosphinates in the mixed solvents HMP-toluene, DMF-toluene and pyridine-CS_2. The prominence of uncharged species at high temperatures is presumably due to the decrease of the dielectric constant of the solvent with increasing temperature.

In contrast to the DMA line broadening results, the $1/T_{2P}$ data for DMF solutions containing bis-(diphenyldi-thiophosphinato)-oxo-vanadium(IV) indicated that one equatorial coordination site of the vanadyl ion is occupied by a monodentate diphenyldithiophosphinate ligand. The exchange rate for the DMF molecules coordinated at the remaining three equatorial sites was greatly enhanced compared to equatorial exchange rates for VO(DMF)$_5^{2+}$. This is expected since the coordination of the diphenyldithio-phosphinate anion to the vanadyl ion reduces the charge on vanadium and weakens the electrostatic V-DMF inter-action. Wüthrich and Connick [47] have presented similar evidence which shows that the ligand exchange rate in-creases when the formal charge on vanadium is reduced.

Since conductivity measurements were undertaken only at room temperature, it is not known whether the species at high temperatures has one or two diphenyldi-thiophosphinate groups coordinated to the vanadyl ion. If coordination by the monodentate diphenyldithiophosphin-

ate occurs at two equatorial sites, then the number of equatorial sites for DMF coordination is reduced to two which could account for the small $1/T_{2M}$ values observed for the formyl proton for the phenyl complex compared to $VO(DMF)_5(ClO_4)_2$. Coordination of two diphenyldithiophosphinates to the vanadyl ion produces a neutral complex which further decreases the strength of the vanadium-DMF bond. This effectively increases the vanadium-formyl proton interaction distance and consequently decreases the values of $1/T_{2M}$. If different species do indeed exist in DMF solutions containing the phenyl complex, they must have similar magnetic parameters because the EPR spectra of the DMF solutions showed no evidence of more than one species.

186.

CHAPTER V

C O N C L U S I O N

A.   Vanadyl Coordination

        Several conclusions can be drawn from the results
presented in this thesis which improve the understanding of
the chemistry of vanadyl complexes in solution. Hopefully,
these conclusions will be useful in the planning and inter-
pretation of further studies of five and six coordinate
vanadyl complexes.

        A popular assumption in studies of the chemistry of
vanadyl complexes has been that five coordinate vanadyl
complexes take up a Lewis base type molecule at the vacant
axial position. In contrast, the primary conclusion drawn
from the investigation of the reactions of the five coordin-
ate vanadyl dithiophosphinates with Lewis bases reported
in this thesis is that these complexes form six coordinate
complexes by coordination of Lewis bases at an equatorial
position with the simultaneous rearrangement of one dithio-
phosphinate chelate to occupy the axial and one equatorial
site. No evidence for axial coordination was obtained.
These observations are complemented by the recently pub-
lished work of Caira, Haigh and Nassimbeni[8] who found
that some Lewis base adducts of $VO(acac)_2$ also exhibit this
stereochemistry. Other Lewis bases have been shown to
coordinate preferentially at the axial position of $VO(acac)_2$.

Unfortunately, neither $VO(acac)_2$ nor the vanadyl dithiophos-
phinates have been studied in a large enough variety of
Lewis bases to establish any correlations from which pre-
dictions about the site of coordination could be made.

A second conclusion of the studies with the vanadyl
dithiophosphinates is that the dithiophosphinate chelate can
behave as a monodentate ligand coordinated to the vanadyl
ion. In such a complex, the site vacated by the dithio-
phosphinate sulphur is occupied by a Lewis base. Mondentate
coordination has also been postulated for metal complexes
of the difluorodithiophosphate ligand on the basis of in-
frared and NMR P-F coupling constants.[90]

The displacement of the dithiophosphinate moiety
from the first coordination sphere of the vanadyl ion by
DMF molecules in contrast to the observed stability of
$VO(acac)_2$ in DMF indicates that the V-S bond is consider-
ably weaker than the V-O bond in $VO(acac)_2$. This can
probably be attributed to the stronger electrostatic inter-
action between the positive vanadium and electronegative
oxygen.

The observation of the [31]P hyperfine splitting in
the EPR spectra of the five coordinate vanadyl dithio-
phosphinates and their six coordinate Lewis base adducts
supports the conclusion that the unpaired electron
occupies the vanadium $d_{x^2-y^2}$ orbital. This same conclusion

was reached by Kivelson and Lee's study of vanadyl tetra-phenylporphyrin.[25] This conclusion seems to be applicable to all vanadyl complexes since no evidence has been presented to support occupation of a different orbital by the unpaired electron.

B.   Vanadyl Exchange Kinetics

Kinetic studies are a useful method for investigating the details of reaction mechanisms. In particular, the kinetic studies of the vanadyl perchlorates undertaken in this thesis elucidated the differences in the properties of the equatorial and axial coordination sites of vanadyl complexes.

The most interesting conclusion from the NMR line broadening studies is that the lifetime of DMF in the axial coordination position in $VO(DMF)_5(ClO_4)_2$ is as long as 2×10^{-5} seconds at room temperature. This is surprising since it has been believed that the coordination at this site is very weak and that lifetimes of ligands in the axial site would be of the order of $10^{-7} - 10^{-8}$ sec as reported for the lifetime of the pyridine adduct of $VO(acac)_2$ by Walker, Carlin and Rieger.[39] The large difference in lifetimes in the two systems is due to the stronger axial bonding in $VO(DMF)_5(ClO_4)_2$ in which the vanadyl ion has a positive charge. Undoubtedly, the lifetimes of molecules coordinated at the axial site in other cationic vanadyl complexes have magnitudes similar

to that in $VO(DMF)_5(ClO_4)_2$ but the combination of chemical systems studied and experimental measurement methods used could not isolate the axial exchange effects. Indeed, this was found in the study of $VO(DMA)_5(ClO_4)_2$ from which no conclusions about axial exchange can be drawn.

A comparison of the exchange parameters for the vanadyl ion in a number of solvents is given in Table V-1. Although DMA and DMF have nearly identical electron donor properties on the basis of the classification proposed by Gutmann [65], DMA exchanges about 25 times faster than DMF. This difference is attributed to the steric interaction caused by the $C-CH_3$ group in the $VO(DMA)_5^{2+}$ complex. The slower exchange rate of DMF compared to H_2O is due to the significantly smaller electron donor strength of water. Similarily, CH_3CN has a weaker electron donor strength than H_2O and CH_3CN exchanges about six times as fast as H_2O. The large error limits for $\Delta H^{\ddagger}$ and $\Delta S^{\ddagger}$ in the earlier study of the solvent line broadening of vanadyl perchlorate in DMF [44], result from the attempt to fit the formyl proton line broadening data to a single exchange process. As shown in this thesis, the line broadening is determined by both axial and equatorial exchange and the data do not correlate well with a single exchange mechanism. The significantly larger value for $\Delta H^{\ddagger}$ obtained in this thesis is in much better agreement with the $\Delta H^{\ddagger}$ of H_2O as expected

TABLE V-1

Kinetic Parameters for Solvent Exchange from the Solvated

Vanadyl Ion

Solvent	Donor[65] Number	$1/\tau_{Meq}$ (10^3 sec^{-1}) at 25°C	$\Delta H^{\ddagger}$ kcal/mole	$\Delta S^{\ddagger}$ cal/deg mole
DMA	27.8	4.7	$10.1 \pm .5$	-7.9 ± 1.6
CH_3CN [44]	14.1	2.97	6.65 ± 29	$-20.3 \pm .9$
CH_3OH [44]	-	.55	$9.46 \pm .68$	$-14.2 \pm .2$
H_2O [43]	18.0	.50	13.7	$- 0.6$
DMF	26.6	.20	$13.1 \pm .6$	-4.1 ± 1.8
DMF [44]	26.6	.76	6.77 ± 1.94	-22.6 ± 5.7

on the basis of electron donor properties. From Table V-1 one then concludes that the lifetime of the solvent molecule in an equatorial site depends on the electron donor properties of the solvent and its steric characteristics.

Another interesting feature of the vanadyl-amide studies is the assertion that the N-methyl proton relaxation times result from modulation of hyperfine interactions between the protons and the unpaired electron. Previous proton NMR studies of the vanadyl systems have consistently explained relaxation times by postulating only a dipolar interaction between the protons and the unpaired electron. Often the magnitude of the electron nuclear interactions was not considered since the $1/T_{2M}$ limit was not observed in the line broadening data. This was the case for the study in CH_3OH and CH_3CN. However, a re-examination of the results for CH_3CN shows that a hyperfine contribution to $1/T_{2M}$ must be postulated in order to produce the line broadenings observed and still be in the exchange controlled limit. The transfer of unpaired spin density to nuclei far removed from the site of coordination via the π system of the ligand is observed in DMF, DMA and CH_3CN, and can be expected in other coordinating ligands with delocalized molecular orbitals.

R E F E R E N C E S

1. J. Selbin, Chem. Rev., 65, 153 (1965).

2. J. Selbin, Coord. Chem. Rev., 1, 293 (1966).

3. R. P. Dodge, D. H. Templeton and A. Zalkin, J. Chem. Phys., 35, 55 (1961).

4. R. T. Claunch, T. W. Martin and M. M. Jones, J. Amer. Chem. Soc., 83, 1073 (1961).

5. R. L. Carlin and F. A. Walker, ibid., 87, 2128 (1965).

6. K. Dickmann, G. Hamer, S. C. Nyburg and W. F. Reynolds, Chem. Commun., 1295 (1970).

7. M. R. Caira, J. M. Haigh and L. R. Nassimbeni, Inorg. Nucl. Chem. Letters, 8, 109 (1972).

8. M. R. Caira, J. M. Haigh and L. R. Nassimbeni, J. Inorg. Nucl. Chem., 34, 3171 (1972).

9. R. A. Bozis and B. J. McCormick, Inorg. Chem., 9, 1541 (1970); B. J. McCormick and R. A. Bozis, ibid., 10, 2806 (1971).

10. B. J. McCormick, ibid., 7, 1965 (1968).

11. B. J. McCormick, Can. J. Chem., 47, 4283 (1969); B. J. McCormick, Inorg. Chem., 9, 1779 (1970).

12. N. M. Atherton and C. J. Winscom, ibid., 12, 383 (1973).

13. E. D. Day, Ph.D. Thesis, University of Alberta, 1972.

14. R. G. Cavell, E. D. Day, W. Byers and P. W. Watkins, Inorg. Chem., 11, 1591 (1972).

15. A. Müller, V. V. K. Rao and E. Deimann, Chem. Ber.,

<u>104</u>, 461 (1971); H. Hertel and W. Kuchen, <u>Chem. Ber.</u>, <u>104</u>, 1740 (1971).

16. I. V. Ovchinnikov, I. F. Gainulin, N. S. Garif'yanov and B. M. Kozyrev, <u>Dokl. Akad. Nauk. SSSR.</u>, <u>191</u>, 395 (1970).

17. N. S. Garif'yanov and B. M. Kozyrev, <u>Theor. Eksp. Khim.</u> <u>1</u>, 525 (1965).

18. J. R. Wasson, <u>Inorg. Chem.</u>, <u>10</u>, 1531 (1971).

19. R. H. Sumner, Ph.D. Thesis, University of Alberta, (1971).

20. G. W. Pake, Paramagnetic Resonance, W. A. Benjamin, New York, 1972.

21. I. Bernal and P. H. Rieger, <u>Inorg. Chem.</u>, <u>2</u>, 256 (1963).

22. C. M. Guzy, J. B. Raynor and M. C. R. Symons, <u>J. Chem. Soc. A</u>, 2791 (1969).

23. K. Wüthrich, <u>Helvetica Chimica Acta</u>, <u>48</u>, 779 (1965); K. Wüthrich, <u>ibid.</u>, <u>48</u>, 1012 (1965).

24. B. McGarvey, <u>Transition Metal Chem.</u>, <u>3</u>, 89 (1966).

25. D. Kivelson and S. K. Lee, <u>J. Chem. Phys.</u>, <u>41</u>, 1896 (1964).

26. M. A. Hitchman, C. D. Olson and R. L. Belford, <u>ibid.</u>, <u>50</u>, 1195 (1969).

27. M. A. Hitchman and R. L. Belford, <u>Inorg. Chem.</u>, <u>8</u>, 958 (1969).

28. R. Wilson and D. Kivelson, <u>J. Chem. Phys.</u>, <u>44</u>, 154 (1966).

29. C. K. Jorgensen, Acta Chem. Scand., 11, 73 (1957); C. Furlani, Ricerca Sci., 27, 1141 (1957).

30. M. B. Palma-Vittorelli, M. V. Palma, D. Palumbo and F. Sgarlata, Nuovo Cimento, 3, 718 (1956).

31. C. J. Ballhausen and H. B. Gray, Inorg. Chem., 1, 111 (1962).

32. L. G. Vanquickenborne and S. P. McGlynn, Theor. Chim. Acta (Berl.), 9, 390 (1968).

33. C. J. Ballhausen, B. F. Djurinskij and K. I. Watson, J. Amer. Chem. Soc., 90, 3305 (1968).

34. M. H. Valek, W. A. Yeranos, G. Basu, P. K. Hon and R. L. Belford, J. Mol. Spectrosc., 37, 228 (1971).

35. K. Nakamoto, Y. Morimoto and A. E. Martel, J. Amer. Chem. Soc., 83, 4533 (1961).

36. J. J. R. Fraústo da Silva and R. Wooton, Chem. Commun., 421 (1969).

37. W. E. Bull, S. K. Madan and J. E. Willis, Inorg. Chem., 2, 303 (1963).

38. R. S. Drago, D. W. Meek, M. D. Joesten and L. LaRoche, ibid., 2, 124 (1963).

39. F. A. Walker, R. L. Carlin and P. H. Rieger, J. Chem. Phys., 45, 4181 (1966).

40. J. A. Pople, W. G. Schneider and H. J. Bernstein, High Resolution Nuclear Magnetic Resonance, McGraw-Hill, New York, 1959, Chap. 10.

41. A. Carrington and A. McLachlan, Introduction to Magnetic
     Resonance, Harper and Row, New York, 1967.

42. J. Reuben and D. Fiat, Inorg. Chem., 6, 579 (1967).

43. K. Wüthrich and R. E. Connick, ibid., 6, 583 (1967).

44. N. S. Angerman, Ph. D. Thesis, University of Alberta
     (1968).

45. R. B. Jordan and N. S. Angerman, J. Chem. Phys., 48,
     3983 (1968).

46. N. S. Angerman and R. B. Jordan, Inorg. Chem., 8, 65
     (1969).

47. K. Wüthrich and R. E. Connick, ibid., 7, 1377 (1968).

48. R. B. Jordan and N. S. Angerman, ibid., 8, 1824 (1969).

49. Handbook of Chemistry and Physics, edited by R. C. Weast,
     Chemical Rubber Co., Cleveland, Ohio, 50th Ed., pp.
     C-429 (1969).

50. J. Selbin and L. H. Holmes Jr., J. Inorg. Nucl. Chem.,
     24, 1111 (1962).

51. S. H. Glarum and J. H. Marshall, J. Chem. Phys., 41,
     2182 (1964).

52. Publication No. 87-100-110, Varian Associates, Palo
     Alto, Calif., pp.29,32.

53. M. Bersohn and J. C. Baird, An Introduction to Electron
     Paramagnetic Resonance, W. A. Benjamin, New York, 1966,
     pp.8.

54. R. Rogers and G. Pake, J. Chem. Phys., 33, 1107 (1960).

55.   B. Bleany, Phil. Mag., 42, 441 (1951).

56.   A. Abragam, J. Horowitz and M. H. L. Pryce, Proc. Roy. Soc. (London), A230, 169 (1955).

57.   P. W. Atkins and D. Kivelson, J. Chem. Phys., 44, 169 (1966).

58.   N. Bloembergen, E. M. Purcell and R. V. Pound, Phys. Rev., 73, 679 (1948).

59.   R. J. Fort and W. R. Moore, Trans. Faraday Soc., 62 112 (1966).

60.   J. Selbin and T. R. Ortolano, J. Inorg. Nucl. Chem., 26, 37 (1964).

61.   J. Selbin, H. R. Manning and G. Cessac, ibid., 25, 1253 (1963).

62.   E. B. Millard, Physical Chemistry for Colleges, McGraw-Hill, New York, 1953, Chap. 8.

63.   M. Szwarc, Accounts Chem. Research, 2, 87 (1969).

64.   Handbook of Chemistry and Physics, edited by R. C. Weast, Chemical Rubber Co., Cleveland, Ohio, 50th Ed., pp.E61-65 (1969).

65.   V. Gutmann, Record of Chemical Progress, 30, 169 (1969).

66.   B. R. McGarvey, Transition Metal Chem., 3, 89 (1966).

67.   N. D. Yordanov and D. Shopov, Inorg. Nucl. Chem. Letters, 9, 19 (1973).

68.   P. B. Ayscough, Electron Spin Resonance in Chemistry, Methuen and Co. Ltd., London, 1967, pp.438-439.

69. R. A. Chittenden and L. S. Thomas, Spectrochim. Acta, 20, 1679 (1964).

70. P. Porta, A. Scamellotti and N. Vinciguerra, Inorg. Chem., 7, 2625 (1968).

71. T. J. Swift and R. E. Connick, J. Chem. Phys., 37, 307 (1962).

72. R. K. Wangsness and F. Bloch, Phys. Rev., 89, 728 (1953); F. Bloch, Phys. Rev., 102, 104 (1956).

73. H. M. McConnell, J. Chem. Phys., 28, 430 (1958).

74. T. R. Stengle and C. H. Langford, Coord. Chem. Rev., 2, 349 (1967).

75. S. Glasstone, K. J. Laidler and H. Eyring, The Theory of Rate Processes, McGraw-Hill Book Co., New York, 1941.

76. I. Solomon, Phys. Rev., 99, 559 (1955).

77. I. Solomon and N. Bloembergen, J. Chem. Phys., 25, 261 (1956); N. Bloembergen, ibid., 27, 572 (1957).

78. N. S. Angerman and R. B. Jordan, ibid., 54, 837 (1970).

79. N. Bloembergen, J. Chem. Phys., 27, 595 (1957).

80. R. S. Drago, Physical Methods in Inorganic Chemistry, Reinhold Publishing Corp., New York, 1965, Chapter 7.

81. G. Durgaprasad and D. N. Sathyanarayana and C. C. Patel, Bull. Chem. Soc. Japan, 44, 316 (1971).

82. Dupont Product Information Bulletin (DMF), E. I. Dupont de Nemours and Co. Inc., Wilmington, Del. (1967).

83. M. Frucht and A. Lewin, Tet. Lett., 42, 3707 (1970).

84. D. W. Marquardt, J. Soc. Indust. Appl. Math., 11, 431

(1963).

85.   L. Luz and S. Meiboom, J. Chem. Phys., 40, 2686 (1964).

86.   J. V. Hatton and R. E. Richards, Mol. Phys., 3, 253 (1960).

87.   M. Alei, Inorg. Chem., 3, 44 (1964).

88.   N. Matwiyoff, ibid., 5, 788 (1966).

89.   M. A. Robb and I. G. Csizmadia, Theor. Chim. Acta
      (Berl.), 10, 269 (1968).

90.   F. N. Tebbe and E. L. Muetterties, Inorg. Chem., 9,
      629 (1970).

A P P E N D I X   A

The Tables in Appendix A give the observed proton magnetic resonance linewidths at half height and the calculated values of $1/T_{2P}$ for the systems described in Chapter IV.

TABLE A-1

Proton Line Broadening of DMA Solutions Containing Various Concentrations of $VO(DMA)_5(ClO_4)_2$

$10^3/T$ (K^{-1})	C-methyl		trans-N-methyl		cis-N-methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})
0.0414 molal						
3.89	6.1	3.9	4.3	2.8	5.4	3.3
3.83	6.2	4.0	4.7	3.2	5.9	3.8
3.79			5.0†	3.4†	6.7	4.4†
3.75	6.6	4.4	4.9	3.3	6.5	4.3
3.68	7.7	5.3	6.7	4.8	8.0	6.3
3.61	9.3	6.7	8.2	6.2	11.0	8.0
3.54	11.6	8.6				
3.47	13.8	10.4				
3.41	16.6	12.8				
3.41			17.4†	14.0†	15.3†	11.6†
0.0196 molal						
2.54††	10.7	17.6	45.0	80.2		
2.54††	11.7†	19.4†	49.0†	85.1†		
2.48††	10.7†	17.6†	44.4†	78.9†		
2.47††	9.2	14.8	41.0	72.9		

(continued........)

$10^3/T$ (K^{-1})	C-methyl		trans-N-methyl		cis-N-methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})
0.0196 molal (continued)						
2.42††	8.4	13.4	37.3	66.1		
2.42††	9.3	14.8†	42.1	76.3†		
0.0195 molal						
3.61			3.3	4.7	3.9	4.6
3.54			4.7	7.3	4.9	6.4
3.48			5.7	9.2	6.1	8.6
3.42	7.1	10.6	7.8	13.0	8.3	12.6
3.37	8.8	13.9				
3.31	10.7	17.3				
3.26	12.9	21.3				
3.20	14.4	24.1				
3.14	15.3	25.8				
0.0134 molal						
3.15	10.6	25.2				
3.10	11.4	27.4				
3.05	11.8	28.5				
3.00	12.0	29.0				
2.91	11.5	27.7				
2.83	10.5	22.0				

202.

$10^3/T$ (K⁻¹)	C-methyl Δν_obs (Hz)	1/T_2P (10³sec⁻¹)	trans-N-methyl Δν_obs (Hz)	1/T_2P (10³sec⁻¹)	cis-N-methyl Δν_obs (Hz)	1/T_2P (10³sec⁻¹)
0.0134 molal (continued)						
2.75	9.7	20.0				
2.67††	9.0	21.5	39.2	100		
2.61††	8.1	19.0	33.6	87		
2.54††	7.6	17.4	30.8	80		
2.48††	6.7	15.0	28.3	73		
2.42††	6.1	13.4	25.1	64		
2.36††	5.4	11.5	21.1	53		
0.00494 molal						
3.49			3.0	16.8	2.7	9.9
3.42			3.8	22.7	3.3	13.9
3.35			4.6	28.6	4.0	19.0
3.29			5.7	35.1	4.8	24.9
3.23			6.6	48.3	5.9	33.0
3.16			8.5	52.0	6.9	37.4
3.15			7.5	49.1	6.2	36.6
3.10			11.0	66.0	8.5	46.2
2.79††			17.1	102		
2.71††			15.1	99		
2.64††			13.7	91		

(continued........)

$10^3/T$ (K^{-1})	C-methyl		trans-N-methyl		cis-N-methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})
0.00494 molal (continued)						
2.57††			12.3	81		
2.51††			11.0	72		
2.45††			9.8	63		
2.39††			9.3	59		

† Spectra recorded at 100 MHz. All other data from spectra recorded at 60 MHz.

†† N-methyl resonances are collapsed to a single line.

TABLE A-2

Proton Line Broadening of DMF Solutions Containing Various Concentrations

of VO(DMF)$_5$(ClO$_4$)$_2$

$10^3/T$ (K^{-1})	Formyl		trans-N-methyl		cis-N-methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3sec^{-1})
0.0573 molal						
4.54	16.5	10.3				
4.44	13.8	8.4				
4.33	12.6	7.4	7.0	4.2	10.4	6.5
4.23	10.1	5.6	7.2	4.3	10.3	6.5
4.15	9.2	4.9	6.4	3.7	7.3	4.3
4.06	8.6	4.4	5.6	3.2	6.7	3.9
3.98	8.4	4.2	5.1	2.8	6.0	3.3
3.89	8.3	4.1	4.8	2.6	5.7	3.1
3.80	8.4	4.2	4.3	2.1	5.1	2.6
3.72	9.1	4.6	3.9	1.8	4.7	2.3
3.68	10.0	5.2	4.1	1.9	4.8	2.3
3.64	10.0	5.2	3.7	1.6	4.4	2.0
3.56	11.1	6.0	3.5	1.5	4.3	1.9
3.48	12.1	6.7	4.0	1.9	4.3	1.9
3.41	13.2	7.4	3.8	1.7	4.4	2.1
3.40	13.1	7.3	4.3	2.2	4.8	2.5
3.35	13.2	7.3	4.2	2.1	4.7	2.4

$10^3/T$ (K^{-1})	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})
0.0573 (continued)						
3.34	13.2	7.3	4.8	2.6	5.2	2.7
3.27	13.6	7.6	5.0	2.7	5.3	2.8
3.22	14.5	8.1	5.7	3.2	6.2	3.4
3.15	15.7	8.9	6.9	4.2	7.6	4.4
3.10	16.5	9.3	9.8	6.2	9.8	6.0
3.04	17.8	10.1				
3.00	18.9	10.8				
2.91	22.4	13.1				
2.83	26.6	16.0				
2.75	30.8	18.9				
2.67	32.3	19.7				
2.61	35.0	21.5				
2.54	39.0	24.3				
2.48††	36.8	22.2	77.0	53.6		
2.42††	37.8	22.8	74.5	52.8		
0.0246 molal						
4.54	7.8	9.5	5.7	7.5	6.7	8.7
4.44	6.2	6.6	4.7	5.8	5.5	6.8
4.39†	6.9†	7.9†	5.3†	5.8†	6.2†	6.9†
4.33	5.8	5.8	4.1	4.9	4.7	5.6

(continued.....)

$10^3/T(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0246 molal (continued)						
4.11	5.2†	4.5†	3.7†	3.7†	4.3†	4.4†
3.86	4.8†	3.5†	3.0†	2.5†	3.5†	2.7†
3.66	6.0†	5.3†	2.8†	2.2†	3.1†	2.0†
3.47	7.1†	6.6†	2.5†	1.7†	2.8†	1.7†
3.47	7.5	7.7				
3.41	7.8	8.2				
3.34	8.3	8.8				
3.28	8.3	8.8				
3.10	9.2	9.4	4.0	4.7	4.2	6.0
3.00	10.7	11.3	7.0	9.9	7.2	9.7
2.91	13.0	14.7				
2.83	15.1	17.9				
2.75	16.6	19.3				
2.67	18.6	22.8				
2.61	19.5	24.0				
2.54	20.9	26.0				
2.48††	21.8	26.8	42.6	67.1		
2.42††	22.0	26.6	41.0	66.9		
0.0101 molal						
3.10	6.1	29.6				
3.05	6.2	9.6	2.5	5.2	2.6	4.6

$10^3/T(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0101 molal (continued)						
3.00	6.7	10.8	3.2	8.1	3.4	7.7
2.96	7.2	12.2	4.1	11.3	4.4	11.9
2.91	7.6	13.0	5.1	15.2	5.7	17.2
2.87	8.2	15.1	6.8	22.4	6.9	21.7
2.84	8.8	18.8	8.5	29.2	8.6	28.6
2.83	8.8	16.8	7.9	26.8	7.7	24.9
2.79	9.3	18.5				
2.75	9.6	19.4				
0.00442 molal						
3.00			2.1	7.4	2.3	6.5
2.91			3.3	17	3.3	14
2.83			4.9	31	4.9	29
2.75			6.9	50	6.8	42
2.67			9.2	67	8.6	58
2.61	8.1†	22.8†	10.1†	73†	8.4†	53†
2.48††			10.5	63		
2.42††			9.0	61		

†   Spectra recorded at 100 MHz. All other data from spectra recorded at 60 MHz.

†† N-methyl resonances are collapsed to a single line.

TABLE A-3

Proton Line Broadening[†] of DMF Solutions Containing Various Concentrations of Bis-(o-phenanthroline)-oxo-vanadium(IV) Perchlorate

$10^3/T (K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.1175 molal						
3.18	6.2	10.0	3.1	6.6	3.5	7.4
3.12	6.5	10.6	3.2	6.9	3.6	7.9
3.02	6.3	8.2	2.7	5.1	3.1	5.5
2.93	6.5	7.7	2.7	4.6	3.1	5.5
2.84	7.0	8.0	3.3	6.4	3.7	6.6
2.76	7.7	9.7	4.5	9.5	4.9	10.2
2.68	9.1	13.7	7.5	19	8.0	20
2.60	11.1	19.4				
0.0538 molal						
4.31	9.9	6.0	7.8	5.2	8.7	5.6
4.13	7.6	4.1	5.5	3.4	6.3	3.9
4.05	6.6	3.2	4.5	2.6	5.2	3.0
3.97	6.2	2.9	4.4	2.5	4.9	2.7
3.89	5.6	2.3	3.6	1.8	4.2	2.1
3.83	5.5	2.3	3.5	1.6	4.0	2.0

(continued.....)

$10^3/T(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0538 (continued)						
3.66	4.8	1.6	2.9	1.1	3.4	1.4
3.54	4.7	1.4				
3.41	4.3	1.0				
3.32	4.8	1.3				
3.21	4.6	0.9				
3.11	4.7	0.8				
0.0306 molal						
4.50	8.2	8.1	6.0	6.2	6.9	7.8
4.40	7.0	6.4	5.2	5.5	5.6	5.7
4.22	5.3	3.9	3.7	3.4	4.3	4.0

† Spectra recorded at 60 MHz.

TABLE A-4

Formyl Proton Line Broadening[†] of DMF Solutions Containing

VO(acac)$_2$

$10^3/T(K^{-1})$	Formyl $\Delta\nu_{obs}(Hz)$	$1/T_{2P}(10^3 sec^{-1})$
0.0449 molal		
4.69	35.8	34.2
4.57	26.1	25.0
4.47	20.4	19.6
4.40	16.4	15.7
4.32	13.0	12.4
4.24	10.6	10.1
4.14	8.9	8.5
4.07	7.6	7.3
3.99	6.6	6.3
3.91	5.8	5.6
3.84	4.9	4.7
3.79	5.3	5.1
3.71	4.5	4.3
3.54	3.5	3.3
3.39	2.7	2.5
3.26	2.2	2.1
3.16	1.8	1.7

[†] Spectra recorded at 60 MHz.

TABLE A-5

Proton Line Broadening[†] of DMA Solutions Containing Various Concentrations of Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)

$10^3/T(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0248 molal						
3.91	4.9	5.1	3.2	3.4	4.6	4.6
3.79	4.7	4.8	3.5	3.7	4.6	4.7
3.71	4.9	5.2	4.0	4.3	4.9	5.1
3.62	5.4	6.0	5.3	6.5	5.8	6.5
3.54	6.5	7.5	6.8	8.7	7.2	9.9
3.46	8.1	9.9	9.6	13.0	9.6	10.5
3.39	10.6	13.6				
3.33	13.8	18.2				
3.26	17.5	23.7				
3.20	18	25				
3.14	20	28				
3.09	22	31				
3.04	21	29				
2.94	20.7	28.4				
2.85[††]	20.2	27.8	70	120		
2.76[††]	19.3	26.5	67	118		
2.69[††]	17.2	23.6	57	·102		

$10^3/T (K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0248 (continued)						
2.61††	15.2	20.7	52	95		
2.55††	13.5	18.2	43	61		
2.49††	11.5	15.3	36	51		
2.43††	9.4	12.2	29	41		
2.37††	7.5	9.8	24	33		
2.28††	4.9	5.6	19	26		
0.0104 molal						
3.88	2.9	5.2	1.9	3.5	2.6	4.2
3.79	2.7	4.4	1.9	3.6	2.6	4.2
3.71	2.7	4.6	2.1	4.1	2.6	4.3
3.62	2.8	5.0	2.5	5.5	3.0	5.6
3.54	3.0	5.8	3.3	6.5	2.8	7.3
3.46	3.5	7.4	4.0	11.3	4.0	9.0
3.39	4.3	10.6	5.5	16.8	5.5	14.2
3.33	5.2	13.8	7.0	19.5	7.6	23.7
3.26	6.3	17.5				
3.20	7.6	21.9				
3.14	8.3	24.4				
3.09	8.9	26.7				
3.04	9.0	26.9				

(continued......)

$10^3/T\,(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$	$1/T_{2}P$ $(10^3\,sec^{-1})$	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ $(10^3\,sec^{-1})$	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ $(10^3\,sec^{-1})$
0.0104 (continued)						
3.02	9.0	27.1				
2.99	9.1	27.4				
2.94	9.2	27.7				
2.89	9.2	28.1				
2.85††	8.9	27.1	31.7	92.9		
2.76††	8.5	25.7	31.8	102		
2.69††	7.8	23.6	27.2	89.2		
2.61††	7.0	20.8	23.0	75.7		
2.55††	6.4	18.9	21.0	68.7		
2.49††	6.1	17.8	17.4	56.3		
2.43††	5.4	15.1	14.3	45.5		
2.37††	4.3	11.3	12.1	37.9		
2.32††	3.7	9.2	10.5	32.2		
0.00667 molal						
3.54	2.4	6.1	2.0	6.9	2.6	6.4
3.46	2.8	8.4	3.0	12.6	3.5	11.5
3.39	3.5	12.0	4.3	19.3	4.2	15.2
3.33	4.2	15.7	6.0	28.2	5.8	23.8
3.26	5.0	20.2	9.0	43.9	7.4	32.5
3.20	5.6	23.8	11.2	54.7	10.2	47.1
3.14	6.1	26.5	12.8	59.0	(continued....)	

Footnotes to Table A-5

†   Spectra recorded at 60 MHz

†† N-methyl resonances are collapsed to a single line.

TABLE A-6

Proton Line Broadening[†] of DMF Solutions Containing Various Concentrations of Bis-(di-phenyldithiophosphinato)-oxo-vanadium(IV)

$10^3/T(K^{-1})$	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ ($10^3 sec^{-1}$)
0.0596 molal						
4.35	13.8	8.2	9.6	5.8	11.7	7.5
4.15	10.8	5.9	7.4	4.3	9.2	5.7
3.97	10.2	5.4	5.6	3.0	6.2	3.5
3.77	10.5	5.6	4.9	2.4	5.2	2.8
3.64	11.2	6.1	4.6	2.2	4.6	2.4
2.75	19.2	10.5				
0.0505 molal						
3.80	8.6	5.0	4.5	2.7	5.0	3.0
3.72	9.6	5.9	9.1	2.3	4.8	2.8
3.56	11.7	7.5	3.9	2.1	4.6	2.6
3.41	13.1	8.5	5.1	2.7	5.5	3.4
3.27	13.9	9.0	7.1	4.9	7.8	5.4
3.15	16.5	11.0				
0.0474 molal						
4.40	12.6	9.2	9.4	7.3	11.6	9.2

$10^3/T$ (K^{-1})	Formyl		trans-N-Methyl		cis-N-Methyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}$ (10^3 sec^{-1})
0.0474 (continued)						
4.32	11.0	7.7	8.6	6.6	9.6	7.3
4.24	9.3	6.2	7.0	5.2	8.0	5.9
4.14	8.4	5.3	6.2	4.5	7.4	5.4
4.07	8.0	4.9	5.4	3.7	6.8	4.9
3.99	7.6	4.5	5.0	3.4	5.8	4.0
3.91	8.0	4.8	4.9	3.3	5.3	3.5
3.84	8.2	5.0	4.0	2.4	4.5	2.7
0.0204 molal						
3.11	8.3	9.7	5.6	8.6	5.6	9.1
3.05	9.9	12.7	10.9	19.8	10.8	20.0
0.0116 molal						
2.94	8.0	13.7	9.6	29.6	9.0	28.1
0.0088 molal						
2.84			11.4	47	10.0	41

† Spectra recorded at 60 MHz

TABLE A-7

Formyl Proton Line Broadening[†] of DEF Solutions Containing

Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV)

$10^3/T(K^{-1})$	Formyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}(10^3 sec^{-1})$
0.00995 molal		
4.74	25.7	75.2
4.61	17.9	51.1
4.50	12.5	34.2
4.39	9.0	23.6
4.29	7.0	17.4
4.19	6.0	14.3
4.10	5.1	11.0
4.01	4.4	9.0
3.92	4.1	7.8
3.84	3.9	7.2
3.82	3.9	7.2
3.77	3.8	6.7
3.71	3.8	6.5
3.62	3.8	6.3
3.54	4.0	6.9
3.46	4.2	7.5
3.39	4.6	8.4
3.33	5.0	9.5
3.26	5.3	10.1
3.20	6.0	12.0
3.14	6.4	13.2
3.09	6.7	13.9
3.05	7.4	15.5
3.02	7.5	15.9
2.94	8.8	19.4

$10^3/T(K^{-1})$	Formyl	
	$\Delta\nu_{obs}$ (Hz)	$1/T_{2P}(10^3 sec^{-1})$
0.00995 (continued)		
2.85	9.6	21.3
2.76	9.5	19.1
2.69	8.9	17.9
2.60	7.3	10.7
2.53	6.4	8.7
2.48	6.2	7.9
2.40	5.7	5.1
2.35	5.5	3.7

† Spectra recorded at 60 MHz.

A P P E N D I X   B

Appendix B gives the conductance measurements of several solvents containing various concentrations of bis-(diphenyldithiophosphinato)-oxo-vanadium(IV). The Tables give the molarity of the phenyl complex, M, the measured resitance of the conductance cell, R, and the calculated conductance, L.

TABLE B-1

Conductance of Several Solvents Containing Various Concentrations of Bis-(diphenyldithiophosphinato)-oxo-vanadium(IV).

Solvent	$M(ml^{-1})$	$R(ohm)$	$L(ohm^{-1})$
1% HMP/toluene	0	1.0×10^6	1.0×10^{-6}
	1.7×10^{-4}	1.0×10^6	1.0×10^{-6}
	9.0×10^{-4}	1.0×10^6	1.0×10^{-6}
	1.37×10^{-3}	1.0×10^6	1.0×10^{-6}
	2.58×10^{-3}	1.0×10^6	1.0×10^{-6}
	4.44×10^{-3}	1.0×10^6	1.0×10^{-6}
	6.44×10^{-3}	1.0×10^6	1.0×10^{-6}
	8.98×10^{-3}	1.0×10^6	1.0×10^{-6}
5% pyridine/CS_2	0	1.0×10^6	1.0×10^{-6}
	4.1×10^{-4}	1.0×10^6	1.0×10^{-6}
	8.63×10^{-4}	1.0×10^6	1.0×10^{-6}
	1.67×10^{-3}	1.0×10^6	1.0×10^{-6}
	2.67×10^{-3}	1.0×10^6	1.0×10^{-6}
	4.22×10^{-3}	1.0×10^6	1.0×10^{-6}
	7.02×10^{-3}	1.0×10^6	1.0×10^{-6}
10% HMP/toluene	0	1.0×10^6	1.0×10^{-6}
	1.6×10^{-4}	1.0×10^6	1.0×10^{-6}
	6.4×10^{-4}	9.0×10^5	1.1×10^{-6}
	1.54×10^{-3}	6.2×10^5	1.6×10^{-6}
	2.26×10^{-3}	5.0×10^5	2.0×10^{-6}
	3.60×10^{-3}	3.7×10^5	2.7×10^{-6}
	5.58×10^{-3}	2.47×10^5	4.09×10^{-6}
	7.88×10^{-3}	1.67×10^5	6.05×10^{-6}
	1.06×10^{-2}	1.10×10^5	9.18×10^{-6}

(continued.......)

TABLE B-1 (continued)

Solvent	$M(ml^{-1})$	$R(ohm)$	$L(ohm^{-1})$
HMP	0	2.82×10^3	3.58×10^{-4}
	2.6×10^{-4}	2.64×10^3	3.83×10^{-4}
	5.6×10^{-4}	2.48×10^3	4.07×10^{-4}
	1.11×10^{-3}	2.23×10^3	4.53×10^{-4}
	2.43×10^{-3}	1.83×10^3	5.52×10^{-4}
	4.64×10^{-3}	9.2×10^2	1.10×10^{-3}
	6.30×10^{-3}	7.45×10^2	1.36×10^{-3}
	8.59×10^{-3}	5.90×10^2	1.71×10^{-3}
	1.22×10^{-2}	4.60×10^2	2.20×10^{-3}
pyridine	0	3.0×10^5	3.3×10^{-6}
	2.5×10^{-4}	6.73×10^3	1.49×10^{-4}
	5.9×10^{-4}	4.18×10^3	2.39×10^{-4}
	1.24×10^{-3}	2.58×10^3	3.88×10^{-4}
	2.48×10^{-3}	1.63×10^3	6.13×10^{-4}
	3.84×10^{-3}	1.21×10^3	8.26×10^{-4}
	6.63×10^{-3}	8.20×10^2	1.22×10^{-3}
	9.26×10^{-3}	6.45×10^2	1.55×10^{-3}
DMF	0	3.2×10^4	3.1×10^{-5}
	7.8×10^{-4}	1.49×10^3	6.83×10^{-4}
	3.9×10^{-3}	3.30×10^2	3.08×10^{-3}
	1.95×10^{-2}	7.9×10^1	1.3×10^{-2}

A P P E N D I X   C

Appendix C gives the FORTRAN computer program which was used to simulate EPR spectra of liquids as discussed in Chapter III.

```
C     FORTRAN PROGRAM FOR SIMULATION OF EPR SPECTRA IN LIQUIDS
C     PROGRAM SIMULATES SPECTRA COMPOSED OF UP TO TWO SPECIES WITH
C     INDEPENDANT PARAMETERS FOR EACH SPECIES, INCLUDING A SHIFT
C     IN GAUSS BETWEEN CENTRES OF THE TWO SPECTRA.
C
C     SECTION 1   INPUT DATA
C     SECTION 2   CALCULATES POSITIONS AND INTENSITIES OF LINES
C     SECTION 3   CALCULATES SPECTRAL INTENSITY AT SPECIFIED MAGNETIC
C                 FIELD VALUES
C     SECTION 4   PLOTS SPECTRUM ON CALCOMP PLOTTER
C
C
C     INPUT DATA
C     CARD 1 TITLE CARD; ANY FORMAT
C     CARD 2 NO. OF POINTS TO BE CALCULATED IN SPECTRUM;
C            NO. OF COMPONENTS IN SPECTRUM; 2I4 FORMAT
C     CARD 3 HEIGHT OF LARGEST PEAK IN MM.;SWEEP WIDTH IN GAUSS;SWEEP
C            WIDTH OF EXPERIMENTAL SPECTRUM IN CM.; IN 3E12.5 FORMAT
C     CARD 4 NO. OF LINEWIDTHS; NO. OF NUCLEI PER LINEWIDTH;005 FOR
C            ETHOXY SPECTRUM TO INTERCHANGE LINEWIDTH ORDER,0 OTHERWISE;
C            IN 3I3 FORMAT
C     CARD 5 LINEWIDTHS AS SPECIFIED IN CARD 4; IN 6E12.5 FORMAT, USE AS
C            MANY CARDS AS NECESSARY
C     CARD 6 SHIFT OF SPECTRUM IN GAUSS, SET TO 0 FOR SINGLE COMPONENT;
C            FRACTION OF COMPONENT, SET TO 1.0 FOR SINGLE COMPONENT;
C            IN E12.5 FORMAT
C     CARD 7 NO. OF DIFFERENT KINDS OF NUCLEI; IN I3 FORMAT
C     CARD 8 NO. OF NUCLEI IN EACH GROUP; IN I3 FORMAT
C     CARD 9 SPLITTING CONSTANT IN GAUSS;SPIN OF NUCEUS; 2 FOR SECOND
C            ORDER TREATMENT, 0 OTHERWISE; IN FORMAT 2E12.5,I2
C            ONE SUCH CARD FOR EACH GROUP OF DIFFERENT NUCLEI
C     IF HAVE TWO COMPONENTS REPEAT CARDS4 TO 9 FOR SECOND COMPONENT
C
```

```
      DIMENSION SFT(2000),SFP(2000),NPR(20),A(20),SPOP(2000),SPOT(2000),
     X         EINT(2000), TITLE(20), OUT(120), NOW(120), SPIN(20),
     X         FLD(20,100),  STM(20,100), NLIN(20), W(1000),B(1000),C(1000)
     X,FIELD(2000),WIDTH(1000),ISD(20),FEINT(2000),FW(1000)
     X,NFPR(20),FA(20),FSPIN(20)
      EQUIVALENCE (FIELD(1),SPOT(1)),(EINT(1),SFT(1))
      COMMON /CCWRIT/ A,TITLE, SPIN, W, SWP, SINT, SMAX, SMIN, NPR, ICC,
     XNGP,NLWCC,NFGP,NFPR,FSPIN,FA,FRAC,FFRAC,CM,NSPEC,SHIFT,FSHIFT
      LOGICAL LOG
C
C                                    SECTION 1.
C
      NDIM = 1000
      ICC = 1
    1 CONTINUE
      ISPEC=0
      READ (5,1000,END=2000) (TITLE(I), I = 1, 18)
      WRITE(6,1001) (TITLE(I), I = 1, 18)
      READ(5,1010)NPT,NSPEC
      READ(5,1020)SINT,SWP,CM
      WRITE(6,1021)SINT,SWP,CM
  100 READ(5,1030)NLW,NRPLW,IWC
      READ(5,1020)(W(I),I=1,NLW)
      READ(5,1020)SHIFT,FRAC
      WRITE(6,1022)FRAC,SHIFT
      WRITE(6,1023)(W(I),I=1,NLW)
      READ(5,1030)NGP
      READ(5,1030)(NPR(I),I=1,NGP)
      READ(5,1031)(A(I),SPIN(I),ISD(I),I=1,NGP)
      WRITE(6,1032)(NPR(I),SPIN(I),A(I),I=1,NGP)
C
C                                    SECTION 2.
C
      NLWCC = NLW
      DO 570 I=1,NGP
      S=SPIN(I)
      AD=A(I)
```

```
      ADD = 1.536E-4 * AD * AD
      N=NPR(I)
      S1=S*FLOAT(N)
      SA = -S1 * AD
      LM=2.*S + 1.1
      II = 2.0 * S1 + 1.1
      DO 510 J=1, II
      SFT(J)=C.0
  510 SPOT(J) = SA + AD * FLOAT(J - 1)
      NL=1
      SFP(1)=1.0
      DO 550 II=1,N
      DO 530 J=1,LM
      DO 520 K=1,NL
      N1=J+K-1
  520 SFT(N1)=SFT(N1) + SFP(K)
  530 CONTINUE
      NL=N1
      DO 540 K=1,NL
      SFP(K)=SFT(K)
  540 SFT(K)=0.0
  550 CONTINUE
      IF(ISD(I).LE.0) GO TO 5529
      IBTM = 1
      FLIP = SFP(1)
      FLOP = 0.0
      K = 1
  551 S2 = S1 * (S1 + 1.0)
      ITOPS = NL - IBTM + 1
      DO 552 J = IBTM , ITOPS
      EMJSQ = (FLOAT(J - IBTM) - S1)**2
      SPOP(K) = SPOT(J) - ADD * (S2 - EMJSQ)
      SFT(K) = FLIP
  552 K = K + 1
      S1 = S1 - 1.0
      IF(S1.LT.0.0) GO TO 5531
      IBTM = IBTM + 1
      FLOP = FLOP + FLIP
```

```
      FLIP = SFP(IBTM) - FLOP
      IF(FLIP.LT.1.0E-05) GO TO 5531
      GO TO 551
5529  DO 5530 K = 1 , NL
      STM(I,K) = SFP(K)
5530  FLD(I,K) = SPOT(K)
      NLIN(I) = NL
      GO TO 570
5531  IBTM = IBTM - 1
553   NL = K - 1
      DO 560 K = 1 , NL
      STM(I,K) = SFT(K)
560   FLD(I,K) = SPOP(K)
      NLIN(I)=NL
570   CONTINUE
      SFP(1)=1.0
      SPOP(1)=0.0
      NL=1
      DO 610 I=1,NGP
      N1=1
      N=NLIN(I)
      DO 590 J=1,N
      SA=STM(I,J)
      SB=FLD(I,J)
      DO 580 K=1,NL
      SFT(N1)=SFP(K)*SA
      SPOT(N1)=SPOP(K)+SB
      N1=N1+1
580   CONTINUE
590   CONTINUE
      NL=N1-1
      TEMP = 0.0
      DO 600 K=1,NL
      SFP(K)=SFT(K)
      SPOP(K)=SPOT(K)
      TEMP = TEMP + SFP(K)
600   CONTINUE
```

```
610   CONTINUE
      IF(NSPEC.EQ.1) GO TO 699
      IF(ISPEC.EQ.1) GO TO 699
      NF=NL
      NFPLW=NRPLW
      NFGP=NGP
      FFRAC=FRAC
      FSHIFT=SHIFT
      DO 705 K=1,NGP
      NFPR(K)=NPR(K)
      FSPIN(K)=SPIN(K)
705   FA(K)=A(K)
      DO 706 K=1,NLW
706   FW(K)=W(K)
699   DO 650 I=1,NL
      CA=1.0E+14
      DO 640 J=1,NL
      S=SPOT(J)
      IF (CA .LE. S) GO TO 630
      CA=S
      II = J
630   CONTINUE
640   CONTINUE
      SPOP(I)=SPOT(II)
      SFP(I)=SFT(II)
      SPOT(II)=1.0E+15
650   CONTINUE
      DO 660 K=1,NL
      SPOP(K)=SPOP(K)+SHIFT
660   SFP(K)=SFP(K)*FRAC/TEMP
      WRITE(6,1500)NL,(SPOP(K),SFP(K),K=1,NL)
1500  FORMAT(' SPECTRUM CONTAINS ',I4,' LINES',/,(2X,2E12.5,4X,2E12.5,
     X4X,2E12.5,4X,2E12.5,/))
C
C
C                                              SECTION 3.
```

228.

```
      IF(NL.LE.2000) GO TO 829
      WRITE(6,1998) NL
1998  FORMAT('0IT CONTAINS',I5,' LINES')
     X/'0IT CONTAINS STICK SPECTRUM CONTAINS MORE THAN 2000 LINES'
      GO TO 2000
829   CONTINUE
      IF (NLW .GT. 1) GO TO 840
      CI = (W(1)*0.8660254)**2
      LOG = .FALSE.
      GO TO 871
840   CONTINUE
      LOG = .TRUE.
      K = 1
      DO 998 I = 1 , NLW
      DO 998 J = 1 , NRPLW
      WIDTH(K) = W(I)
998   K = K + 1
      IF(IWC.LT.5) GO TO 999
      DO 997 J=1,5
      L=NRPLW*J
      N=L+1
      WCI=WIDTH(L)
      WIDTH(L)=WIDTH(N)
997   WIDTH(N)=WCI
999   IF((K-1).EQ.NL) GO TO 860
      WRITE(6,1035)
      GO TO 1
860   CONTINUE
861   CONTINUE
      DO 870 I=1,NL
1999  FORMAT(3E18.8)
      WI = WIDTH(I) * 0.8660254
      B(I)=0.6366198*WI
      C(I)=WI*WI
870   CUTOFF = 10.0*W(1)
871   DELTA=SWP/FLOAT(NPT)
      HMIN =-0.5*SWP
```

```fortran
      NPT=NPT+1
      DO 60 I=1,NPT
      H=HMIN+DELTA*FLOAT(I-1)
      EIT=0.0
      DO 50 J=1,NL
      HA=H-SPOP(J)
      IF(HA.GT.CUTOFF) GO TO 50
      IF(HA.LT.-CUTOFF) GO TO 51
      IF(LOG) GO TO 45
      TRUMP = HA/(CI + HA*HA)**2
      GO TO 46
   45 TRUMP = HA*B(J)/(C(J)+HA*HA)**2
   46 EIT = EIT - SFP(J) * TRUMP
   50 CONTINUE
   51 CONTINUE
      FINT(I)=EIT
      FIELD(I)=H
   60 CONTINUE
      ISPEC=ISPEC+1
      IF(NSPEC.EQ.1) GO TO 200
      IF(ISPEC.EQ.2) GO TO 199
      DO 61 K=1,NPT
      FEINT(K)=EINT(K)
   61 FEINT(K)=EINT(K)
      GO TO 100
  199 DO 62 I=1,NPT
   62 EINT(I)=EINT(I)+FEINT(I)
  200 SMIN=0.0
      SMAX=0.0
      DO 63 K=1,NPT
      IF(EINT(K).GT.SMAX)SMAX=EINT(K)
   63 IF(EINT(K).LT.SMIN)SMIN=EINT(K)

C                          SECTION 4.
C
C            CALCOMP PLOT:
C
      IF(ICC.NE.1) GO TO 203
      CALL CPLOT1 (FIELD, EINT, NPT)
      GO TO 206
```

```
203   CALL CPLOT2 (FIELD, EINT, NPT)
C       ICC IS AN INDEX FOR THE COUNTING AND POSITIONING OF THE
C           PLOTS.
206   ICC = ICC + 1
C
      GO TO 1
C
C           TERMINATE PLOT.
C
2030  CALL CCEND
      STOP
C
1000  FORMAT(18A4)
1001  FORMAT(56H1COMPUTER SIMULATION OF ESR SPECTRA IN LIQUID SOLUTIONS.
     1/1H0,18A4)
1010  FORMAT(18I4)
1020  FORMAT(6F12.5)
1021  FORMAT(26H0INTENSITIES NORMALIZED TOF10.1/ 7H SWEEP F9.2,7H GAUSS
     X,'SPANNING',F7.2,' CENTIMETERS.')
1022  FORMAT(' FRACTION OF THIS SPECIES =',F10.5,/,' SHIFT OF THIS SPECI
     XES =',F10.5,' GAUSS')
1023  FORMAT(' SPECTRUM CONSTRUCTED FROM LORENTZIAN LINES OF PEAK TO PEA
     XK WIDTHS IN GAUSS OF :',/,8(E12.3,2X))
1030  FORMAT(24I3)
1031  FORMAT(2E12.5,I2)
1032  FORMAT(1H0,I3,17H NUCLEI WITH SPIN,F4.1,14H AND SPLITTING,F6.2,6H
     1GAUSS)
1035  FORMAT(29H0ERROR IN WIDTH SPECIFICATION)
      END
C
C
C
      SUBROUTINE CPLOT1 (X,Y,NPT)
C
C
C
C           THIS SUBROUTINE CALCOMP PLOTS DATA OF ESR SPECTRA IN
C     LIQUID SOLUTIONS. MULTIPLE ENTRY POINTS ARE USED TO HANDLE
```

```fortran
C       MULTIPLE GRAPHS FOR EACH RUN OF THE MAIN PROGRAM.
C
        DIMENSION AREA(2048), X(1    ), Y(1    )
        COMMON /CCWRIT/A(20),TITLE(20),SPIN(20),W(1000),SWP,SINT,SMAX,SMIN
       X,NPR(20),ICC,NGP,NLW,NFGP,NFPR(20),FSPIN(20),FA(20),FW(1000)
       X,FRAC,FFRAC,SHIFT,FSHIFT,CM,NSPEC
C
C       INITIALIZE PLOT
C
        CALL PLOTS (AREA, 8192)
        CALL PLOT (0.0, 0.0,-100)
        CALL SYMBOL(0.0,0.0,0.15,'COMPUTER SIMULATION OF ESR SPECTRA IN LI
       XQUID SOLUTIONS.',90.0,55)
        ENTRY CPLOT2 (X, Y, NPT)
C
C       WRITE INPUT DATA
C
        CALL SYMBOL(0.3,0.0,0.15,TITLE(1),90.0,72)
C
        CALL SYMBOL(0.6,0.0,0.15,' FRACTION OF SPECIES ONE =          WIT
       XTH SHIFT =        GAUSS',90.0,61)
        CALL NUMBER(0.6,3.5,0.15,FRAC,90.0,3)
        CALL NUMBER(0.6,6.2,0.15,SHIFT,90.0,3)
        DO 20 I=1,NGP
        XSTEP=0.6+0.3*I
        CALL SYMBOL(XSTEP,0.0,0.15,'             NUCLEI WITH SPIN       AND SPLITTING
       X           GAUSS',90.0,53)
        CALL NUMBER (XSTEP, 0.0, 0.15, FLOAT(NPR(I)), 90.0, -1)
        CALL NUMBER (XSTEP,2.7,0.15,SPIN(I),90.0,1)
        CALL NUMBER (XSTEP, 5.05, 0.15, A(I), 90.0, 2)
     20 CONTINUE
        CALL SYMBOL(XSTEP+0.3,0.0,0.15,'SPECTRUM CONSTRUCTED FROM LORENTZI
       XAN LINES OF PEAK-TO-PEAK WIDTHS IN GAUSS',90.0,75)
        YSTEP=0.0
        XSTEP=XSTEP+0.3
        DO 25 I=1,NLW
        CALL NUMBER(XSTEP,YSTEP,0.15,W(I),90.0,3)
```

```
   25 YSTEP=YSTEP+1.25
      IF(NSPEC.EQ.1) GO TO 310
      CALL SYMBOL(XSTEP+0.3,0.0,0.15,' FRACTION OF SPECIES TWO =
     X    WITH SHIFT =        GAUSS',90.0,63)
      CALL NUMBER(XSTEP+0.3,3.5,0.15,FFRAC,90.0,3)
      CALL NUMBER(XSTEP+0.3,6.2,0.15,FSHIFT,90.0,3)
      XVAL=XSTEP+0.3
      DO 21 I=1,NFGP
      XSTEP=XVAL+0.3*I
      CALL SYMBOL(XSTEP,0.0,0.15,'        NUCLEI WITH SPIN        AND SPLITTING
     X        GAUSS',90.0,53)
      CALL NUMBER(XSTEP,0.0,0.15,FLOAT(NFPR(I)),90.0,-1)
      CALL NUMBER(XSTEP,2.7,0.15,FSPIN(I),90.0,1)
      CALL NUMBER(XSTEP,5.05,0.15,FA(I),90.0,2)
   21 CONTINUE
      CALL SYMBOL(XSTEP+0.3,0.0,0.15,'SPECTRUM CONSTRUCTED FROM LORENTZI
     XAN LINES OF PEAK-TO-PEAK WIDTHS IN GAUSS',90.0,75)
      YSTEP=0.0
      XSTEP=XSTEP+0.6
      DO 26 I=1,NLW
      CALL NUMBER(XSTEP,YSTEP,0.15,FW(I),90.0,3)
   26 YSTEP=YSTEP+1.25
  310 CALL SYMBOL(XSTEP+0.3,0.0,0.15,'INTENSITIES NORMALIZED TO ',
     1    90.0, 26)
      CALL NUMBER (XSTEP+0.3, 3.5, 0.15, SINT, 90.0, 1)
      CALL SYMBOL (XSTEP+0.6, 0.0, 0.15, 'SWEEP        GAUSS SPANNING
     X        CM',90.0,42)
      CALL NUMBER (XSTEP+0.6, 0.9, 0.15, SWP, 90.0, 2)
      CALL NUMBER(XSTEP+0.6,3.9,0.15,CM,90.0,2)
C
C        OUTLINE OF PAGE FOR CUTTING
C
      ORG = XSTEP + 0.5
      XMOVE = ORG + 0.75
      CALL PLOT (ORG,0.0,-3)
      CALL PLOT (0.0,11.0,2)
      CALL PLOT (16.5,11.0,2)
```

```
      CALL PLOT  (16.5,0.0,0.2)
      CALL PLOT  (0.0,0.0,2)
C
C                MOVE THE X-AXIS TO THE MIDDLE OF THE PAGE
C
      CALL PLOT(0.75,5.5,-3)
C
C          SET UP SCALING FACTORS FOR X AND Y
C
C           PLOT DATA POINTS
C
      CALL OFFSET(X(1),SWP/(CM*0.3937) ,  0.0, 25.4*(SMAX-SMIN)/SINT)
C
      CALL PLOT(X(1),Y(1),13)
      DO 27 I=2,NPT
   27 CALL PLOT(X(I),Y(I),12)
C
C           DRAW CENTER LINE
C
      CALL PLOT(0.0,0.0,2)
C
C           MOVE PEN FOR NEXT PLOT
C
      IF (ICC .GT. 2*(ICC/2)) GO TO 30
      IF(XMOVE.GT.XMOVER) XMOVER = XMOVE
      CALL PLOT(16.5 + XMOVER,-19.0,-3)
      RETURN
   30 CALL PLOT (-XMOVE, 8.0, -3)
      XMOVER = XMOVE
      RETURN
C
C           TERMINATE PLOT
C
      ENTRY CCEND
      CALL PLOT (0.0, 0.0, 999)
      RETURN
      END
```